arXiv:1403.4620v1 [astro-ph.GA] 18 Mar 2014

The Co-Evolution of Galaxies and Supermassive Black Holes: Insights from Surveys of the Contemporary Universe

Timothy M. Heckman

Center for Astrophysical Sciences, Department of Physics & Astronomy, The Johns Hopkins University, Baltimore, MD 21218, USA

Philip N. Best

Institute for Astronomy, Royal Observatory Edinburgh, Blackford Hill, Edinburgh EH9 3HJ, UK

Keywords

Active Galactic Nuclei, Seyfert Galaxies, QSOs, Radio Galaxies

Abstract

We summarize what large surveys of the contemporary (low-redshift) universe have taught us about the physics and phenomenology of the processes that link the formation and evolution of galaxies and their central supermassive black holes. The surveys are powerful because their large size and high data quality enable the careful control of systematics needed to untangle the complex inter-relationships in a robust way. We emphasize the particular importance of high-quality optical spectra from the Sloan Digital Sky Survey. We present a picture in the contemporary universe in which the population of Active Galactic Nuclei (AGN) can be divided into two distinct populations. The Radiative-Mode AGN are associated with black holes that produce radiant energy powered by accretion at rates in excess of $\sim$1% the Eddington Limit. This population today is primarily associated with less massive black holes growing in high-density pseudo-bulges at a rate sufficient to produce the total mass budget in these black holes in about 10 Gyr. The circum-nuclear environment contains high density cold gas and associated on-going star-formation. Major mergers are not the primary mechanism for transporting this gas inward; secular processes appear dominant. The association between black hole growth and star-formation means that stellar feedback will be generic in these objects. Strong AGN feedback in the form of global outflows is seen only in the most powerful AGN. In the Jet-Mode AGN the bulk of energy extracted from the accretion process takes the form of collimated outflows (jets). This population is associated with the more massive black holes in the more massive (classical) bulges and elliptical galaxies. Neither the accretion onto these black holes nor star-formation in their host bulge is significant today. These AGN are probably fueled by the accretion of slowly cooling hot gas that is limited by the feedback/heating provided by AGN radio sources. Surveys of the high-redshift universe are painting a very similar picture for the characteristic population of AGN that are responsible for the bulk of the mass in relic black holes in today's fossil record: they live in normal galaxies with the (high) star-formation rates characteristic of those epochs. We speculate that a mode in which black holes are formed in major mergers and generate galaxy-scale winds may be responsible for the minority population lying above the knee in the AGN luminosity function. Noting that the volume-averaged ratio of star formation to black hole growth has remained broadly similar over the past 10 Gyrs, we argue that the processes that linked the cosmic evolution of galaxies and supermassive black holes are still at play today.

1. INTRODUCTION

1.1. A Brief History

It has been nearly a century since Hubble (1925) decisively demonstrated that the Andromeda nebula is a vast island universe of stars similar to our own Milky Way galaxy. His discovery soon thereafter of an expanding cosmos filled with galaxies opened up a vista of an immense and seemingly serene universe. However, this picture of serenity was deceptive. As we write this review, it is the 50 year anniversary of Maarten Schmidt's (1963) realization that the radio source 3C273 was associated with an optically unresolved object with the (then) enormous redshift of 0.158. Subsequent identifications of a whole population of quasi-stellar radio sources at even higher redshifts were soon followed by the discovery of a more numerous population of otherwise-similar but radio-quiet quasi-stellar galaxies (Sandage 1965). [It is fascinating in hindsight that the discovery of the cosmic X-ray background (Giacconi et al. 1962) and of the Kerr metric (Kerr 1963) occurred at the same time.] The concept of the Violent Universe was born.

It is beyond the scope of this article to review the twists and turns that finally led to the consensus that all these quasi-stellar objects (QSOs) were the extremely luminous active nuclei of distant galaxies. Qualitatively similar objects had been found much earlier in the nuclei of some relatively nearby galaxies by Seyfert (1943). It is sobering that the significance of this discovery was long unrecognized: the first investigation into the nature of Seyfert galaxies was published 16 years later by Burbidge et al. (1959) who concluded that NGC 1068 was explosively ejecting ionized gas from its nucleus. Likewise, although other radio sources had been identified with distant galaxies before the discovery of QSOs – e.g. Cygnus A by Baade & Minkowski (1954) – there was great confusion as to the origin of this very large-scale radio-emission which had no obvious connection to the galaxy nucleus.

For most of the past five decades the communities that studied galaxies and active galactic nuclei (AGNs) remained largely disconnected. AGNs were studied primarily as laboratories in which to probe exotic high-energy processes. There was some effort to understand the role that the environment might play in triggering or fueling the AGN – for example, see the ancient review in this journal by Balick & Heckman (1982) – but there was almost no idea that AGNs played any significant role in the evolution of typical galaxies. Of course, things could hardly be more different today. The notion of the co-evolution of galaxies and AGN has become inextricably engrained in our current cosmogony. Indeed, our review represents the third article in this journal in consecutive years that deals with some aspect of this co-evolution (Fabian 2012, Kormendy & Ho 2013).

The reasons for this change are easy to see. First came the realization that powerful AGNs (as represented by QSOs) were only the tip of the iceberg. Extensive surveys in the radio, optical, and X-ray domains revealed local populations of Seyfert and radio galaxies and established that signs of lower-level activity were commonplace in the nuclei of early-type galaxies. This strongly suggested that the AGN phenomenon – rather than being simply a rare spectacle – was a part of the lifecycle of typical galaxies. The demography and physical properties of these low-power AGN has been comprehensively reviewed in this journal by Ho (2008).

A second reason followed from the documentation of the overall build-up over most of cosmic time of the populations of galaxies (as traced via star-formation) and of supermassive black holes (SMBHs, whose growth is traced by AGN). The evolution of the two populations is strikingly similar: a steep rise in both the star-formation rate (SFR) and SMBH growth rate by about a factor of 10 from redshift z = 0 to 1, a broad maximum in both rates at $z \sim 2$ to 3 and then a relatively steep decline at higher redshifts (see



Fig. 1.— The cosmic history of black hole growth and stellar mass growth. The average black hole accretion rate is compared to the SFR as a function of redshift, where the latter is given by Hopkins & Beacom (2006) and Fardal et al. (2007), scaled by the factor 0.8×10^{-3}. The shaded grey area shows the 3σ uncertainty region from Hopkins & Beacom (2006). Figure from Shankar et al. (2009).

Fig. 1 – Shankar et al. 2009 and references therein). For at least the last ∼11 Gyr of cosmic history the ratio of these two growth rates has remained roughly constant with a value of-order 10^3. Thus, at least in a volume-averaged sense, the growth of galaxies and SMBHs has been synchronized somehow.

Finally, and even more remarkably, observations over the past decade have not only established that SMBH exist in the nuclei of (probably) all galactic bulges, they have shown that the properties of these present-day SMBHs and the galaxies in which they live are linked on a galaxy-by-galaxy-basis. This impressive fossil record of co-evolution has been exhaustively reviewed by Kormendy & Ho (2013). In addition to the accumulating observational evidence for the co-evolution of galaxies and SMBHs, a considerable theoretical motivation to invoke this linkage has developed as well. Without some form of feedback from AGN, neither current semi-analytic models nor numerical simulations can successfully reproduce the properties of massive galaxies. This fascinating subject has been reviewed in this journal by Fabian (2012).

In conclusion, while the evidence to date remains indirect, it is hard not to infer that the cosmic evolution of galaxies and of SMBHs have seemingly been driven by a suite of inter-linked physical processes.

1.2. Our Perspective: Large Surveys of the Contemporary Universe

Our goal here is to review the evidence for the co-evolution of galaxies and SMBHs as derived from large surveys of the contemporary (low redshift) universe. The majority of the growth of SMBH and of the stellar components in galaxies occurred between redshifts of roughly 0.5 and 2, and the present-day growth rates of both populations are over an order-of-magnitude smaller than during the peak epoch. A reasonable question is then whether one can learn anything very useful by studying the contemporary universe. We hope that by the end of the review the reader will agree with us that one can actually learn a great deal.

We believe that there are a number of reasons why this is the case. The contemporary universe contains a

rich fossil record that (once successfully decoded) reveals the processes that produced this record. Moreover, the basic physical processes that operated during the peak epoch of SMBH/galaxy growth are still in place and can be studied in greater detail due to their relative proximity. However, the primary reason to study the contemporary universe is that it is the only place where has it been possible to carry out the surveys of galaxies and SMBHs that are of both sufficiently large size and whose data are of sufficiently high quality to have finally allowed us to be able to fully explore the complex inter-relationship between these two populations in a statistically robust way. This has led to a much clearer picture of both the fossil record of galaxy/SMBH co-evolution and of the processes by which the co-evolution continues to play out.

The particular importance of high-quality optical spectroscopy cannot be over-stated: these data form the interpretational backbone of the whole structure defined by extensive multi-band imaging and photometric surveys. Of most relevance to the specific topic of our review, studies of the lower-luminosity objects that dominate the AGN population in the local universe benefitted immensely from galaxy spectra obtained as part of the main galaxy sample of the Sloan Digital Sky Survey (SDSS – Strauss et al. 2002). The high quality of the spectra enabled them to be used to characterize both the AGN and the stellar populations in the host galaxies. Finally, the uniformity and completeness of the SDSS main galaxy sample rendered it ideal for statistical studies of the multi-parameter characteristics of the galaxy population in the contemporary universe, including their AGN properties.

The uniformity and wide sky coverage of the 2dF Galaxy Redshift Survey (2dFGRS; Colless et al. 2001) and SDSS galaxy redshift survey make them an ideal starting point for studies of AGN and their host galaxies in regions of the electromagnetic spectrum other than the optical. This encompasses the study of radio-selected AGN using surveys such as the 1.4 GHz National Radio Astronomy Observatory (NRAO) VLA Sky Survey (NVSS; Condon et al. 1998) by Sadler et al. (2002) and Mauch & Sadler (2007) and the Faint Images of the Radio Sky at Twenty centimeters (FIRST; Becker et al. 1995) survey by Best et al. (2005) and Best & Heckman (2012). Recently, samples of tens of thousands of nearby mid-infrared-detected AGN covering large areas of the sky have been constructed by cross-correlating sources detected by the Wide-field Infrared Survey Explorer (WISE; Wright et al. 2010) with the SDSS (Donoso et al. 2012, Shao et al. 2013). X-ray data having the depth and wide-field sky coverage to fully exploit the SDSS galaxy sample do not exist. However, to date the SWIFT/BAT survey has detected over 700 (mostly local) AGN at energies above 15 keV (Baumgartner et al. 2013). Near-IR data from WISE and vacuum-ultraviolet data from the Galaxy Evolution Explorer (GALEX; Martin et al. 2005) provide important additional information about AGN host galaxies. In subsequent sections, we will summarize the new scientific insights that resulted from all these large surveys.

1.3. The Landscape of the Galaxy Population and How It Got That Way

To help frame the main issues addressed in this review it is helpful to briefly summarize the basic properties of the population of galaxies in the contemporary universe and the current thinking about how these galaxies were built. The reader is referred to the review by Madau & Dickinson in this volume for all the details.

Results from the SDSS have shown that the galaxy population in the contemporary universe occupies a very small part of the parameter space defined by the structure, stellar content, and chemical composition of a galaxy. In particular, the existence of clear bimodality in the galaxy population was revealed (Kauffmann et al. 2003b, Blanton et al. 2003, Baldry et al. 2004). One population (blue, for short) consists of galaxies



Fig. 2.— The distribution of galaxies in the SDSS main galaxy sample on the plane of stellar mass *vs.* specific star formation rate (sSFR = SFR/M$_*$). The greyscale indicates the volume-weighted distribution of all galaxies, with each lighter color band indicating a factor of two increase. Galaxies predominantly fall within two regions: a 'main sequence' of star-forming galaxies, and a red sequence of 'quenched' galaxies. The blue and red contours show the volume-weighted distributions of high (>1%; mostly radiative-mode) and low (< 1%; mostly jet-mode) Eddington-fraction AGN, with contours spaced by a factor of two.

with significant on-going star-formation, small stellar masses (M$_*$), low stellar surface mass densities ($\mu_* = 0.5M_*/(\pi R_{50}^2)$, where R_{50} is the radius containing 50% of the light; see Section 2.4), and small concentrations ($C = R_{90}/R_{50}$) of their light (late Hubble type). The other (red) consists of galaxies with little on-going star formation, large M$_*$, high μ_*, and large C (early Hubble type). The characteristic parameter values that mark the transition between populations are M$_* \sim 10^{10.5}$ M$_\odot$, $\mu_* \sim 10^{8.5}$ M$_\odot$kpc^{-2}, and $C \sim 2.6$. Subsequent work showed that the blue population is characterized by a tight almost linear relationship between the star-formation rate (SFR) and M$_*$ (Brinchmann et al. 2004, Schiminovich et al. 2007). This has come to be called the star-forming main sequence. Fig. 2 shows the relationship between M$_*$ and the specific star formation rate (sSFR = SFR/M$_*$) in the contemporary universe.

Over the past few years, deep surveys have established that the qualitative distribution shown in Fig. 2 is characteristic of the galaxy population out to at least a redshift of 2 (e.g. Whitaker et al. 2013). The most significant difference is that the actual values of sSFR on the star forming main sequence evolve extremely rapidly with time: Elbaz et al. (2011) find as the age of the universe (t$_{cos}$) increased from 2.2 to 13.6 Gyr ($z = 3$ to 0) the characteristic value of the sSFR declined with time as $t_{cos}^{-2.2}$.

The simplest picture for the evolution of a typical galaxy (e.g. Lilly et al. 2013) is that it evolves along the (strongly evolving) blue star-forming main sequence, increasing in mass through the accretion of cold gas from the cosmic web and (secondarily) through mergers with other galaxies. As it approaches a critical mass, its supply of cold gas is shut off, the star formation is quenched, and the galaxy then evolves into the red population. It can continue to increase in mass through subsequent mergers with other galaxies. It is presently not clear whether the mass-scale at which quenching occurs pertains to the stellar mass or the dark matter halo mass.

The physical process(es) that quench the galaxy are unclear. In part, quenching may be due to a change in the nature of accretion: rapid accretion of cold streams of infalling gas at low mass transitioning to slow accretion of hot gas in hydrostatic equilibrium at high mass (e.g. Dekel et al. 2009). In principle these processes are included in numerical and semi-analytic models of galaxy evolution. Nevertheless, these models require some additional process to be at play in order to reproduce the observed properties of massive galaxies. Heating and/or the ejection of surrounding gas by an AGN-driven outflow to suppress the cold accretion is a popular idea. In addition the models also require AGN feedback to keep galaxies that arrive in the red/dead population from forming too many stars from the slow accretion of their hot halo gas. Thus, in the current paradigm, AGN play a crucial role in the evolution of massive galaxies.

2. BASIC METHODOLOGY

2.1. Overview of the Local AGN Population

The fundamental property that we consider to define an AGN is that its power source involves extracting energy from the relativistically-deep potential well of a SMBH at or near the center of a galaxy.

In this paper we will present strong empirical evidence that the low-redshift population of AGN can be divided into two main categories. The first category consists of objects whose dominant energetic output is in the form of electromagnetic radiation produced by the efficient conversion of the potential energy of the gas accreted by the SMBH. Historically, these objects have been called either Seyfert galaxies or QSOs depending upon rather vague and arbitrary criteria involving luminosity and/or redshift. In the rest of this review we will refer to these as radiative-mode AGN. The second category consists of objects that produce relatively little radiation, and whose primary energetic output takes the form of the bulk kinetic energy transported in two-sided collimated outflows (jets). These jets may be ultimately powered by the accretion of gas or by tapping the spin energy of the SMBH. Historically, this AGN population has been called (low-excitation) radio galaxies. In this review we will refer to them as jet-mode AGN. As we will show in this review, these two populations are virtually disjoint in terms of the basic properties of their SMBHs and host galaxies.

Let us then begin by describing the basic building blocks for these two types of AGN (see Fig. 3 for schematic diagrams). We refer readers to the texts of Krolik (1999), Netzer (2013), Osterbrock & Ferland (2005), Peterson (1997), and the review by Yuan & Narayan in this volume, for the gory details. In the first category (radiative-mode AGN), the SMBH is surrounded by a geometrically-thin, optically-thick accretion disk through which an inflow occurs. The accretion disk has a radial temperature gradient and the resulting total thermal continuum emission emerges in the extreme ultraviolet through visible portion of the electromagnetic spectrum. The accretion disk is surrounded by a hot corona which Compton-up-scatters the soft seed photons from the disk into the X-ray regime. As the X-rays impact the accretion disk their spectral energy distribution is modified through fluorescence and reflection off the accretion disk. The ionizing radiation from the disk and corona heats and photo-ionizes a population of dense gas clouds located on scales of light-days to light-years from the SMBH leading to the production of UV, optical, and near-IR permitted emission-lines. The velocity dispersion of the population of clouds is typically several thousand km s^{-1}, leading to its designation as the Broad Line Region based on the resulting emission-line spectrum.

On larger scales, the SMBH and accretion disk are surrounded by a region of dusty molecular gas (which we will refer to as the obscuring structure). Its inner radius is set by the sublimation temperature of the most refractory dust grains and is hence larger in more luminous AGN. In this region some of the incident UV/visible photons from the accretion disk and the soft X-rays from the corona are absorbed by the dust



Fig. 3.— Schematic drawings of the central engines of radiative-mode and jet-mode AGN (not to scale). Radiative-mode AGN (left panel) possess a geometrically-thin, optically-thick accretion disk, reaching in to the radius of the innermost stable orbit around the central supermassive black hole. Luminous ultraviolet radiation from this accretion disk illuminates the broad-line and narrow-line emission regions. An obscuring structure of dusty molecular gas prohibits direct view of the accretion disk and broad-line regions from certain lines of sight (Type 2 AGN), whereas they are visible from others (Type 1 AGN). In a small proportion of sources (predominantly towards the high end of the range of black hole masses) powerful radio jets can also be produced. In jet-mode AGN (right panel) the thin accretion disk is replaced in the inner regions by a geometrically-thick advection-dominated accretion flow. At larger radii (beyond a few tens of Schwarzschild radii, the precise value depending upon properties of the accretion flow, such as the Eddington-scaled accretion rate), there may be a transition to an outer (truncated) thin disk. The majority of the energetic output of these sources is released in bulk kinetic form through radio jets. Radiative emission is less powerful, but can ionize weak, low-ionization narrow-line regions, especially where the truncation radius of the thin disk is relatively low.

and this absorbed energy emerges as thermal infrared emission. The total column density of the obscuring structure spans a range in inferred column densities from roughly 10^{23} to $10^{25}\mathrm{cm}^{-2}$. The highest column densities are sufficient to absorb even hard X-rays (these cases are Compton-thick). As ionizing radiation escapes along the polar axis of the obscuring structure it photo-ionizes gas on circum-nuclear scales (few hundred to few thousand pc). This more quiescent and lower density population of clouds produces UV, optical, and infrared forbidden and permitted emission-lines, Doppler-broadened by several hundred $\mathrm{km\,s}^{-1}$, and is hence called the Narrow Line Region.

Observing an AGN from a sight-line nearer the polar axis of the obscuring structure yields a clear direct view of the SMBH, the disk/corona, and Broad Line Region. These are called Type 1 (or unobscured) AGN. When observing an AGN from a sight-line nearer the equatorial plane of the obscuring structure, this central

region is hidden and these are called Type 2 (or obscured) AGN. This is the basis for the standard Unified Model for radiative-mode AGN (e.g. Antonucci 1993) which asserts that the Type 1 and 2 populations differ only in the viewing angle from which the AGN is observed. The presence of AGN can still be inferred in the Type 2 objects from the thermal infrared emission from the obscuring structure, from hard X-rays transmitted through the structure (when it is Compton-thin), and from the emission-lines with tell-tale line ratios from the Narrow Line Region.

In some cases, the obscuring material can be the larger-scale dusty interstellar medium of the host galaxy. This is particularly relevant when the host galaxy's disk is viewed at a large inclination or the galaxy is in the throes of an on-going major merger with a strong central concentration of dusty gas. This material will sometimes be sufficient to obscure the optical, UV, and soft X-ray emission from the AGN accretion disk and Broad Line Region, but insufficient to attenuate the hard X-rays (e.g. Gelbord 2003). The effect of this is nicely demonstrated by Lagos et al. (2011), who use SDSS data to show that the host galaxies of optically-obscured AGN are skewed toward edge-on orientations, while those optically-classified as Type 1 have a much higher probability of having a face-on orientation.

In the second category (jet-mode AGN) a distinct mode of accretion onto the SMBH exists that is apparently associated with low accretion rates and which is radiatively inefficient. The geometrically-thin accretion disk is either absent, or is truncated in the inner regions, and is replaced by a geometrically-thick structure in which the inflow time is much shorter than the radiative cooling time (e.g. Narayan & Yi 1994, 1996, Quataert 2001, Narayan 2005, Ho 2008). These are called advection-dominated or radiatively-inefficient accretion flows (ADAFs/RIAFs). A characteristic property of these flows is that they are capable of launching two-sided jets. Note that powerful jets are also launched by a small fraction of radiative-mode AGN (e.g. radio-loud QSOs). The jets are (far and away) most easily detected via the synchrotron emission they produce at radio wavelengths. This can extend from optically-thick (synchrotron self-absorbed) emission on pc-scales all the way out to regions far beyond the stellar body of the galaxy (reaching Mpc-scales in extreme cases). In typical local radio galaxies the jets travel at relativistic velocities (Lorentz gammas of several) when launched, but appear to rapidly decelerate and destabilize as they interact with the gaseous halo of the host galaxy and transition to sub-sonic turbulent plumes. At the highest radio luminosities (most commonly found in the radio-loud radiative-mode AGN) the jets survive as highly-collimated structures until they terminate as bright shocks (hot spots) at the interface with the circum-galactic or inter-galactic medium. The survival or disruption of the jets leads to the Fanaroff & Riley (1974) morphological classification of radio galaxies (see Urry & Padovani 1995 for further discussion).

Missing from the above description are the objects that may trace the lowest luminosity portion of the AGN population. This population has been reviewed in this journal by Ho (2008). Since his review, evidence has grown that at least some of the objects previously classified as the lowest-luminosity AGN (the Low-Ionization Nuclear Emission-line Regions, or LINERs, with the very weakest optical emission-lines) are not bona fide AGN (e.g. Cid Fernandes et al. 2012, Yan & Blanton 2013). However, the remaining more powerful LINERs are very likely to be members of the jet-mode AGN population (e.g. Nagar et al. 2005, Ho 2008, Best & Heckman in preparation), albeit with rather modest radio luminosities.

Fig. 4 summarizes this description of the local AGN population, and how the common AGN classes fit within in. The blue text within that figure describes the properties of a *typical* example of each category of AGN. As the review develops, we will describe the evidence for this, and discuss the range of properties seen for each AGN class.


L/L_Edd ≲ 0.01
L/L_Edd ≳ 0.01
Jet mode
Radiative mode
Type 2
Type 1
Radio Loud
Radio Quiet
Low−excitation radio source
* Very massive early−type galaxy
* Very massive black hole
* Old stellar population; little SF
* Moderate radio luminosity
* FR1 or FR2 radio morphology
* Weak (or absent) narrow, low ionisation emission lines
High−excitation radio source
* Massive early−type galaxy
* Massive black hole
* Old stellar population with some on−going star formation
* High radio luminosity
* Mostly FR2 morphology
* Strong high−ionisation narrow lines
Radio−loud QSO
Host galaxy properties like high−excitation radio source, but with addition of:
* Direct AGN light
* Broad permitted emission lines
* Sometimes, beamed radio emission
AGN LINER
* Massive early−type galaxy
* Massive black hole
* Old stellar population; little SF
* Weak, small−scale radio jets
* Moderate strength, low−ionisation narrow emission lines
Type 2 QSO / Seyfert 2
* Moderately massive early−type disk galaxy with pseudo−bulge
* Moderate mass black hole
* Significant central star−formation
* Weak or no radio jets
* Strong high−ionisation narrow lines
* QSOs more luminous than Seyferts
Radio Quiet QSO / Seyfert 1
Host galaxy properties like Type−2 QSO and Seyfert 2, respectively, but with addition of:
* Direct AGN light
* Broad permitted emission lines
* Bias towards face−on orientation
Light dominated by host galaxy
Direct AGN light

Fig. 4.— The categorisation of the local AGN population adopted throughout this review. The blue text describes *typical* properties of each AGN class. These, together with the spread of properties for each class, will be justified throughout the review.

2.2. Finding AGN

This review is focused on insights into the co-evolution of SMBHs and galaxies that have been derived from large surveys of the local universe. For such investigations of the radiative-mode AGN it is the obscured (Type 2) AGN that are far and away the more valuable. In these objects the blinding glare of the UV and optical continuum emission from the central accretion disk has been blocked by the natural coronagraph created by the dusty obscuring structure. The remaining UV and optical continuum is generally dominated by the galaxy's stellar component (Kauffmann et al. 2003a) which can then be readily characterized. In the sections to follow we will therefore restrict our discussion of radiative-mode AGN to techniques that can recognize Type 2 AGN. For the jet-mode AGN the intrinsic UV and optical emission from the AGN is generally weak or absent unless the observer is looking directly down the jet axis (e.g. Urry & Padovani 1995). Thus, the host galaxy properties can be easily studied without contamination.

The relevant techniques that have been used for very large surveys of the local universe are based on: 1) optical spectroscopy to identify emission from the AGN-powered narrow-line region, 2) mid-IR photometry to identify the warm dust emission from the obscuring structure, 3) hard X-ray imaging spectroscopy to detect emission from the accretion disk corona, and 4) non-thermal radio continuum emission to locate jets and jet-powered structures.

For the radiative-mode population, one important caveat to keep in mind is the degree to which Type 2 AGN and their hosts are the same as those of Type 1. In the most simplistic version of the AGN Unified Model described above, this complete overlap would be the case. However, in reality the fraction of the sky covered by obscuring material (as seen from the SMBH) will vary significantly from AGN-to-AGN. In this case, the AGN observed as Type 1 (2) will be systematically drawn from the portion of the AGN parent population with a smaller (larger) covering-factor for the obscuring material. It would therefore not be surprising if the properties of Type 1 and Type 2 AGN and their hosts differed in some systematic fashion.

2.2.1. Optical Emission-Line Surveys

Large-scale spectroscopic surveys of the contemporary universe (particularly 2dFGRS and SDSS) have revolutionized the study of emission-line AGN, by providing high-quality spectra for over a million galaxies, with well-understood selection functions. The broad emission-lines and strong non-stellar continuum emission in Type 1 radiative-mode AGN offer easily detectable and unambiguous evidence of the presence of an AGN origin (detailed discussions of the identification of Type 1 AGN and of the criteria used to discriminate between Type 1 and Type 2 AGN in the SDSS can be found in Richards et al. 2002 and Hao et al. 2005a). In contrast, the optical signature of Type 2 radiative-mode AGN, and of jet-mode AGN, is the presence of narrow emission lines. In general, such narrow emission-lines can also be produced by ordinary populations of O stars associated with on-going star formation. However, the relative intensities of the strong forbidden and permitted emission-lines resulting from photoionization by the relatively hard continuum from an AGN differ systematically from those produced by the much softer continuum of O stars. This approach to recognizing AGN was first systematized by Baldwin et al. (BPT – 1981) and later refined by Veilleux & Osterbrock (1987). The diagnostic diagrams (hereafter BPT diagrams) compare pairs of emission line flux ratios. Primary among these is the flux ratio pair [OIII] 5007/Hβ vs. [NII] 6584/Hα, but the [OI] 6300/Hα and [SII] 6716,6731/Hα flux ratios provide diagnostics that are complementary to [NII]/Hα (e.g. Kewley et al. 2006; see Fig. 5). The same diagnostic diagrams work for Type 1 AGN provided that only the narrow components of the Balmer lines are considered (e.g. Stern & Laor 2012a).

We show a set of BPT diagrams for the SDSS main galaxy sample in Fig. 5 (taken from Kewley et al. 2006). The basic morphology of the BPT diagrams reveals the presence of two populations. The first is that of purely star-forming galaxies whose locus runs from the upper left to lower middle of the plots in a sequence of downwardly increasing metallicity (e.g. Pettini & Pagel 2004). The second is the AGN population, which is joined to the star forming sequence at the high-metallicity end and then extends upward and to the right.

Physically, the observed difference in the emission from high-metallicity gas photoionized by an AGN reflects the increased rate of photoelectric heating by the hard AGN radiation field. This leads to a higher gas temperature and an increased strength of the collisionally-excited forbidden lines relative to the recombination lines of Hydrogen. Since real galaxies contain both AGN and regions of star-formation within the observed region, the extension of the AGN locus away from the star-forming sequence can be viewed as a mixing line along which the contribution to the total emission-line spectrum by the AGN increases relative



Fig. 5.— A set of BPT diagnostic diagrams for the SDSS main galaxy sample taken from Kewley et al. (2006). The red line is the maximal starburst line from Kewley et al. (2001) while the dashed line in the left panel shows the more stringent dividing line between pure star-forming galaxies and AGN adopted by Kauffmann et al. (2003a). The separation between star-forming galaxies and AGN is most cleanly done using the left panel while the center and right panels can be used to separate Seyferts from LINERs.

to that from the star-forming regions as the points move further away from the star-forming locus. This inference is confirmed in a statistical sense by the result that the relative distribution of points along this sequence migrates downward toward the star-forming sequence as the redshift of the galaxy population at fixed stellar mass increases and the SDSS fiber encompasses a progressively larger region of the host galaxy (Kauffmann et al. 2003a, Kewley et al. 2006, LaMassa et al. 2013).

Kewley et al. (2001) used photo-ionization and stellar population synthesis models to define an upper boundary to the possible location of star-forming galaxies in the BPT diagrams, above which a clean sample of AGN can be selected. Kauffmann et al. (2003a) used empirical methods, based on the tight locus of star-forming galaxies within the [NII]/Hα BPT diagram, to produce an alternative demarcation which should provide a more complete census of the AGN population that is less biased against AGN in strongly star-forming galaxies. These demarcation lines are shown in Fig. 5. Other authors have proposed further refinements of this division (e.g. Stasinska et al. 2006, Kewley et al. 2006, Cid Fernandes et al. 2011). This diagram has often been used to separate emission-line galaxies into three classes: star-formation-dominated (below and to the left of the Kauffmann et al. line), AGN-dominated (lying above and to the right of the Kewley line), and Composite (between the Kewley and Kauffmann lines). In this paper we will not distinguish between the Composite and AGN-dominated objects (we regard them all as AGN).

It is important to emphasize here that while the optical emission-lines used to classify AGN and star-formation-dominated galaxies can be substantially affected by dust absorption, these optical classifications agree with mid-IR based classifications in the great majority of cases (LaMassa et al. 2012).

In 1980 a separate class of optical emission line AGN was proposed, known as LINERs (Heckman 1980). LINERs are distinguished from Seyfert nuclei by the relative strength of their low-ionization emission lines; the original definition was based on the forbidden lines of oxygen, with LINERs having emission-line flux

ratios [OII] 3727/[OIII] 5007 > 1 and [OI] 6300/[OIII] 5007 > 0.32. Subsequent classifications have built upon the BPT diagrams separating the AGN population into Seyferts and LINERs (see Fig. 5). Although LINERs typically have lower nuclear luminosities than Seyferts, many of the fundamental characteristics of the objects close to the demarcation boundary are very similar to those of the low-luminosity end of the distribution of Seyferts (e.g. Kewley et al. 2006, Ho 2008, Netzer 2009).

Stasinska et al. (2008), Sarzi et al. (2010), Cid Fernandes et al. (2011), Capetti & Baldi (2011), and Yan & Blanton (2012) have all presented evidence that those LINERs with the weakest emission-lines (which are located in galaxies with predominantly old stars) are not powered by an AGN. Instead most of these papers argue that they are produced by photo-ionization of neutral atomic gas by a population of Post-Asymptotic Giant Branch stars (PAGB). A problem with this idea is that HST ultraviolet images of the bulge of M31 (the site of a LINER) do not reveal the predicted population of these PAGB stars (Brown et al. 1998, 2008, Rosenfield et al. 2012). For these weak LINERs to be photo-ionized by old stars, a population that is less luminous and more numerous than the PAGB stars would be needed.

In this review we will be conservative and consider the possibility that weak LINERs are not members of the AGN population. Here we consider weak LINERs to be objects with [OIII] 5007 equivalent widths smaller than ∼1Å (e.g. Capetti & Baldi 2011). It is important to note that although these objects constitute the majority of LINERs in the SDSS, they contribute a negligible amount to the overall AGN emissivity of the contemporary universe. It is also important to note that objects classified as LINERs in the SDSS span over two-orders-of-magnitude in [OIII] luminosity ($L_{[OIII]}$) and roughly three-orders-of-magnitude in $L_{[OIII]}/M_{BH}$ (Kewley et al. 2006, Netzer 2009; where M_{BH} is the black hole mass in solar units). While a stellar origin for the LINER emission is likely at the lowest luminosities, the more powerful LINERs are most likely to be AGN (Best & Heckman, in preparation).

2.2.2. X-Ray and Infrared Surveys

X-ray surveys have played a critical role in defining the radiative-mode AGN population and delineating its evolution over cosmic time (see Brandt & Hasinger 2005 for a thorough review). In our review we are most interested in the population of Type 2 obscured AGN in the contemporary universe. The ROSAT all-sky survey (Voges 1999) has the requisite wide-field coverage, but the survey is very shallow compared to the SDSS in terms of finding AGN, and its 0.1-2.4 keV band is too soft to recover the bulk of the obscured AGN population (e.g. Anderson et al. 2003, Shen et al. 2006). Hard X-ray observations are much more useful, and the current state-of-the-art is represented by the survey undertaken with the Burst Alert Telescope (BAT) onboard the Swift gamma-ray burst observatory. As of late 2012, BAT observations have yielded a catalog of 1171 X-ray sources detected in the 14-195 keV band, drawn from a survey with nearly uniform sensitivity over the entire sky based on 70 months of observations (Baumgartner et al. 2013). Of these over 700 are AGN. At these high X-ray energies only Compton-thick obscured AGN will be under-represented, and indeed the 70 month catalog contains roughly equal numbers of Type 1 and Type 2 Seyfert galaxies.

The signature of an obscured AGN in the infrared is unusually strong mid-IR (∼ 3 to 30 μm) emission produced by the dusty obscuring structure. IRAS pioneered the detection and characterization of the local AGN populations in the mid and far-IR (e.g. Miley et al. 1985, Spinaglio & Malkan 1989). Unfortunately, the sensitivity of IRAS was not well matched to the bulk of the optically-selected local AGN in the SDSS (e.g. Pasquali et al. 2005). The Spitzer Space Telescope was considerably more sensitive than IRAS but did not undertake wide-field surveys optimized to the local AGN population. Nonetheless, a number of

different techniques based on near- and mid-IR color selection were developed to find AGN using Spitzer data (e.g. Lacy et al. 2004, Stern et al. 2005, Richards et al. 2006, Donley et al. 2008). The situation has been revolutionized with the completion of the mission of NASA's Wide-field Infrared Survey Explorer (WISE) which has detected near- and mid-IR emission from roughly 30,000 optically-classified AGN in the SDSS main galaxy sample (Donoso et al. 2012, Shao et al. 2013) and many other AGN as well (e.g. Stern et al. 2012, Rosario et al. 2013).

It is important to note here that while samples of AGN selected by their optical emission-lines, their mid-IR emission, or their hard X-ray emission are roughly similar to one another in terms of both the properties of the AGNs and the host galaxies (e.g. La Massa et al. 2010, Kauffmann et al. 2003a, Winter et al. 2010, Shao et al. 2013), they may not be identical (e.g. Koss et al. 2011, Juneau et al. 2013, Hickox et al. 2009).

2.2.3. Radio Continuum Surveys

Radio continuum surveys offer an important means to find AGN, particularly the jet-mode AGN for which jets represent the bulk of the AGN's energetic output. For radiative-mode AGN, the dusty obscuring structure is optically thin to radio continuum emission, so the detection of radio-emitting Type-2 AGN is also reasonably straightforward. Deep radio sky surveys such as NVSS, FIRST, the Westerbork Northern Sky Survey (WENSS; Rengelink et al. 1997) and the Sydney University Molonglo Sky Survey (SUMSS; Bock et al. 1999) cover large sky areas with sufficient sensitivity to probe the majority of the radio-AGN in the contemporary universe, reaching down to at least $P_{1.4\mathrm{GHz}} \sim 10^{23}\mathrm{W\,Hz^{-1}}$ out to $z \sim 0.1$. More problematic issues than simple detection, however, are the accurate association of observed radio sources with their optical host galaxies, and the confirmation that the observed radio emission arises from AGN activity rather than being associated with star formation within the host galaxy.

The NVSS was the first large-area radio survey of sufficiently high angular resolution (45 arcsec) to permit automated cross–correlation with optical surveys (cf. Machalski & Condon 1999). However, the positional accuracy of NVSS sources is only 1-2 arcsec at 10 mJy flux levels, increasing to 4-5 arcsec or more at the 2.5mJy flux limit of the survey (Condon et al. 1998). This leads to significant uncertainties in cross-identifying the radio sources with their optical host galaxies, which are further exacerbated by the extended and multi-component nature of some radio sources: even though $> 95\%$ of $z < 0.1$ radio sources are contained within a single NVSS component, the radio centroid of asymmetric extended sources may not match the host galaxy position. This leads to a trade-off between the reliability and the completeness of the matched sample. For example, Sadler et al. (2002) cross-matched the NVSS with galaxies from the 2dFGRS, accepting matches within 10 arcsec of the optical galaxy; they calculated that the catalog would be 90% complete at this level, but that 5-10% of the matches were expected to be false identifications.

Higher reliability samples can be derived using radio surveys with better angular resolution, such as the 5 arcsec resolution of FIRST (cf. the SDSS cross-matching by Ivezić et al. 2002). However, these surveys can miss extended radio emission, leading to the radio luminosity of sources larger than a few arcsec being systematically low (Becker et al. 1995), and also to a much larger fraction of extended radio sources being split into multiple components. These multi-component sources can usually be associated with host galaxies by visual inspection, which is practical for moderate sample sizes (e.g. Mauch & Sadler 2007), but not for the very large samples produced from SDSS. Automated cross-matching routines therefore need to be used, which take account of the possible multi-component nature of radio sources. So-called collapsing algorithms

aim to identify multi–component radio sources by using the angular separations, flux densities and flux-density ratios of close source pairs to determine whether these are likely to be associated (e.g. Magliocchetti et al. 1998); for optical cross-matching, the relative separations and position angles from the host galaxy position offer further information (e.g. McMahon et al. 2002, de Vries et al. 2006). Best et al. (2005a) developed a combined approach, using data from both NVSS (for reliable luminosities) and FIRST (for accurate cross-matching), along with all of the above information and incorporating visual analysis for the most extended radio sources. They were able to develop samples with $\sim 95\%$ completeness and $\sim 99\%$ reliability. Adaptations of this method have since been widely used (e.g. Sadler et al. 2007, Donoso et al. 2009, Lin et al. 2010, Best & Heckman 2012).

The derived radio source populations comprise a mixture of AGN and star-forming galaxies. A variety of different methods have been adopted in the literature for separating radio-loud AGN from star-forming galaxies. Perhaps the cleanest of these uses the ratio of far-infrared to radio luminosity: star-forming galaxies show a very tight correlation between these properties (see review by Condon et al. 1992), whereas radio-loud AGN are offset to brighter radio luminosities. This technique has been widely used at higher redshifts (e.g. Ibar et al. 2008, Sargent et al. 2010, Padovani et al. 2011, Simpson et al. 2012), but the shallow depth of wide-area far-IR surveys has limited its use locally (cf. Sadler et al. 2002). For local galaxies, the information provided by the large spectroscopic surveys can be used instead. BPT emission-line-ratio diagnostic diagrams offer an approach consistent with that used to classify emission-line selected AGN, although a large fraction of the radio population lack the required emission line detections (Sadler et al. 1999, Best et al. 2005a). Radio-loud AGN can also be identified as being offset from the tight correlation that star-forming galaxies display between Hα emission line luminosity and radio luminosity (Kauffmann et al. 2008, Vitale et al. 2012). An alternative method developed by Best et al. (2005a) considers the 4000Å break strength (a measure of stellar population age; see Section 2.4.2) against the ratio of radio power per stellar mass, on the basis that star-forming galaxies with a wide range of star formation histories occupy a similar locus in this plane.

These different AGN/SF classification schemes agree on the classification of most sources, but do produce significant differences (see the comparison by Best & Heckman 2012). Primary amongst these differences is that way that 'radio-quiet' AGN are classified. These AGN often display compact radio cores and weak jet-like structures, but those which lack these features lie on the same far-IR to radio correlation as star-forming galaxies (Roy et al. 1998). This suggests that the bulk of their radio emission is powered by star formation. BPT diagnostics classify these sources as AGN, since the AGN drives the emission line ratios away from the star-forming locus, but in contrast the sources are generally classified as star-forming using the far-IR to radio or emission line to radio luminosity ratio diagnostics, or the 4000Å break strength. Best & Heckman (2012) combined these different classification methods to provide a sample of 18,286 radio-loud AGN from the SDSS, excluding radio-quiet AGN (see Fig. 6). This is the sample used to construct relevant plots throughout this review.

2.3. Determining AGN Physical Properties

2.3.1. Proxies for Bolometric Luminosity in Radiative-Mode AGN

In this section we will discuss how best to estimate the bolometric luminosity of radiative-mode AGN. Type 2 AGN are (by definition) obscured and this complicates the estimation of perhaps the most basic physical property of an AGN: its total (bolometric) luminosity. We cannot directly observe the great bulk of this radiant energy, and must therefore rely on attempting to calibrate various proxies for the bolometric



Fig. 6.— Diagnostic diagrams showing the galaxies within the SDSS main galaxy sample that are detected in the radio waveband above $S_{1.4\mathrm{GHz}} = 5\,\mathrm{mJy}$. These diagrams are used to separate genuine radio-loud AGN from other radio-detected galaxies in which the radio emission is powered by star-formation (this includes both radio-quiet AGN and star-forming galaxies). The upper-left plot shows the 'D(4000) *vs.* $L_{1.4\mathrm{GHz}}$/M' method, originally developed by Best et al. (2005a). The upper-right plot shows the widely-used 'BPT' emission line ratio diagnostic. The lower plot shows the relationship between Hα and radio luminosity (arrows indicate upper limits to the Hα luminosity). In all plots, the dotted lines indicate the division used by Best & Heckman (2012) for that classification method. For the 'BPT' diagnostic diagram, this division separates AGN from star-forming galaxies in terms of what powers the emission lines, rather than what powers the radio emission. The division line in the $L_{\mathrm{H}\alpha}$ *vs.* $L_{1.4\mathrm{GHz}}$ plot was defined to ensure a clean sample of genuine radio-loud AGN below the division. Through combinations of the locations of galaxies in the three diagrams (see Best & Heckman for details) sources can be given an overall classification as radio-loud AGN (red diamonds) or star-forming galaxies / radio quiet AGN (black crosses). Adapted from Best & Heckman (2012).

luminosity based on the radiation that does escape. Let us then assess these various proxies and begin by briefly listing their pros and cons.

Proxy 1: The [OIII]5007 emission-line. The proxy that we will primarily use later in this review is the luminosity of the [OIII]5007 narrow emission-line. The [OIII] line is produced in AGN by ionizing radiation that escapes along the polar axis of the dusty obscuring structure where it photo-ionizes and heats ambient

gas clouds on radial scales of-order 0.1 to 1 kpc from the SMBH (in the Narrow-Line Region, or NLR).

Pros: 1) This line is easily observed and can be measured (if present) in the existing SDSS spectra of a few million galaxies. 2) Since the NLR lies outside the very high column density in the obscuring structure its emission suffers far less attenuation due to dust near the AGN than the optical emission from the accretion disk. Modest amounts of dust extinction can be corrected using the ratio of the fluxes of the narrow Hα and Hβ emission-lines (the Balmer decrement). Typical implied corrections are 1 to 2 magnitudes (e.g. Kewley et al. 2006).

Cons: 1) Significant amounts of more wide-spread dust extinction due to the galaxy interstellar medium may be present and it may not be possible to reliably correct for this extinction if it is too large. 2) The [OIII] line can be contaminated by a contribution due to star-formation (which will be significant in the composite objects shown in Fig. 5). Examples of the empirical techniques for correcting for contamination by stellar ionization are described in Kauffmann & Heckman (2009) and Wild et al. (2010). 3) The luminosity of the line will depend on the uncertain fraction of the AGN ionizing luminosity that is intercepted by clouds in the NLR.

Proxy 2: The [OIV]25.9 micron and [NeV]14.3,24.3 micron emission-lines. These proxies have the same physical origin as the [OIII]5007 line, arising from photoionized gas in the NLR.

Pros: 1) They arise well outside the region of the heaviest obscuration. 2) As mid-IR lines they are much less affected by dust extinction than the [OIII]5007 line. 3) They have ionization potentials above the HeII edge at 54.4 eV (where hot stars produce very little radiation). They therefore suffer much less contamination from stellar photoionization than [OIII]. This is especially true for [NeV]. This advantage relative to [OIII] has been exploited by Satyapal et al. (2008, 2009) and Goulding & Alexander (2009) to identify examples of low-luminosity AGN in the nuclei of nearby late-type galaxies that were not recognized as AGN based on optical spectra that were dominated by regions of star formation.

Cons: 1) They are expensive to observe (having been detected in hundreds of objects rather than hundreds of thousands). 2) The luminosity will depend on the uncertain fraction of the AGN ionizing luminosity that is intercepted by clouds in the NLR.

Proxy 3: The Mid-Infrared Continuum. This is produced by warm dust in the obscuring structure and as such represents the reprocessing of the primary ultraviolet/visible emission from the accretion disk and the soft X-rays from its corona.

Pros: 1) Thanks to WISE, we now have measurements of the near- to mid-IR continuum in a very large sample of galaxies in the nearby universe (comparable in size to the SDSS main galaxy sample). 2) It represents a substantial fraction of the bolometric luminosity (roughly 25% in Type 1 AGN where we directly observe nearly all the emission).

Cons: 1) The mid-infrared light from the obscuring structure will not be emitted in an isotropic way and correction for this effect is uncertain at the level of factors of several. This effect is largest at the shortest mid-infrared wavelengths. 2) The net observed mid-infrared emission will be the sum of the emission from the AGN and dust heated by hot stars. A decomposition of these two emission processes is uncertain and model-dependent. This effect is worse at longer infrared wavelengths.

Proxy 4: The Hard X-ray Continuum. In a Type 2 AGN the observed hard X-ray emission will be a combination of whatever radiation succeeds in traversing the obscuring structure plus emission from the central AGN that has been scattered or reprocessed into our line-of-sight (e.g. Murphy & Yaqoob 2009).

Pros: 1) The hard X-ray emission probes regions very close to the SMBH (the accretion disk corona), but suffers far less obscuration than optical or UV observations of the accretion disk. 2) This hard X-ray emission is a rather unambiguous indicator of an AGN (rather than a starburst) at luminosities greater than about 10^{42} erg s^{-1}.

Cons: 1) Hard X-rays are poor probes of the AGN emission at the high column densities often inferred for the obscuring structure. This is true for column densities above 10^{24} cm^{-2} in the 2-10 keV band and above 10^{25} cm^{-2} even in the Swift BAT band. These latter are the Compton-thick AGN. 2) The SWIFT/BAT wide all-sky survey is quite shallow relative to SDSS in its ability to detect AGN.

Having briefly described the various proxies, we now summarize the evidence as to how well they actually do in estimating the AGN bolometric luminosity. The problem with this is that we do not know the ground truth needed to make this evaluation. The best approach is to inter-compare these different proxies among the Type 2 AGN and also to evaluate their behavior relative to the Type 1 AGN (where obscuration is minimized); see Fig. 7.

LaMassa et al. (2010) examined a wide range of proxies in two complete samples of Type 2 AGN. One was selected on the basis of the flux of the [OIII]5007 emission-line from SDSS and the other was selected on the basis of the mid-infrared (12μm) flux measured with IRAS (hereafter the SDSS-OIII and IRAS-MIR samples). The proxies they considered for the bolometric luminosity were the luminosities of the [OIII]5007 line, the [OIV] 25.9 micron line, the mid-infrared (12μm) continuum, the hard X-ray Swift BAT continuum, and the 8.4 GHz nuclear radio continuum. They examined the correlations between all possible pairs of the proxies and compared the distributions of the flux ratios of all proxy-pairs to those of samples of unobscured Type 1 AGN (cf. Fig. 7). They concluded that the luminosity of the [OIV] line is the single best proxy and that the radio and hard X-ray luminosities are the worst. The problem with the hard X-ray luminosity is that many of the Type 2 AGN in the SDSS-OIII and IRAS-MIR samples are Compton-thick and significantly obscured even in the Swift BAT band (14-195 keV) – see also Heckman et al. (2005), Winter et al. (2010). Similar conclusions were drawn by Rigby et al. (2009) based on comparison of the flux ratio of the [OIV] 25.9 micron line and hard X-ray continuum (above 10 keV) in optically-selected Type 1 and Type 2 AGN drawn from the Revised Shapley-Ames Catalog (hereafter the RSA sample).

An analysis of multiple proxies in the RSA sample was undertaken by Diamond-Stanic et al. (2009). They found that the ratio of the flux of the 2-10 keV continuum and the [OIV] emission-line was smaller on-average in the Type 2 AGN than in Type 1 AGN and varied by about three orders-of-magnitude. This implies a wide range in the amount of attenuation of the 2-10 keV X-ray emission in these Type 2 AGN (see Fig. 7). They also found that the flux ratio of the [OIII]5007/[OIV]25.9 micron lines was systematically smaller in Type 2 than in Type 1 AGN and showed more scatter in the RSA sample. They argued that this was a result of a greater amount of dust-extinction in Type 2 AGN (by typically one to two magnitudes). LaMassa et al. (2010) found a much smaller offset in this ratio in the SDSS-OIII and IRAS-MIR samples (implying a mean excess extinction of [OIII] by only about 0.5 magnitudes in the Type 2 AGN). These results do underscore the importance of correcting the [OIII] flux for extinction (when possible).

Shao et al. (2013) have analyzed WISE observations of a sample of 30,000 Type 2 AGN identified in SDSS spectra. They find an excellent overall correlation between the luminosities of the (extinction-corrected) [OIII]5007 emission-line and the (starlight-subtracted) 4.6 micron emission from hot AGN-heated dust (rms scatter of about 0.3 dex). Moreover, the partitioning of the AGN emission as a function of host galaxy parameters is the same based on the [OIII] and 4.6 micron emission (once LINERs were excluded). Finally they show that the existing color-color techniques that have been used to identify AGN from Spitzer



Fig. 7.— Relationships between different estimators of bolometric luminosity for radiative-mode AGN. Top panels: a comparison of the [OIII] emission line luminosity with the [OIV] line luminosity (left) and mid-infrared continuum luminosity (right), for samples of galaxies selected from their [OIII] emission line and their 12μm mid-IR flux (data from LaMassa et al. 2010). Bottom panels: the hard X-ray *vs.* [OIII] luminosity for X-ray selected (left) and emission-line selected (right) samples of AGN (data from Heckman et al. 2005). Type 2 AGN in the emission line selected samples do not show a good correlation due to X-ray absorption.

and WISE data recover only the most luminous AGN (objects in which the AGN significantly outshines its host galaxy in the near- and mid-IR). This misses most of the optically identified Type 2 AGN in SDSS, which have lower luminosities.

A simple summary of the above is that there no single perfect proxy for the bolometric luminosity in obscured AGN. Even relatively good proxies will produce an estimate of the bolometric luminosity of any individual obscured AGN that will be uncertain at the level of a factor of several (in an rms sense). Given the huge number of AGN with measured [OIII]5007 luminosities (e.g. Hao et al. 2005a, Kauffmann & Heckman 2009), we will adopt this as our default proxy for the optically-selected Type 2 AGN. Based on an analysis of multi-waveband data for two samples of Type 1 AGN, Heckman et al. (2004) calculated a mean bolometric correction to the [OIII]5007 luminosity of a factor of 3500. This refers to [OIII] luminosities derived from

the raw [OIII] flux with no correction for dust extinction and assumes that Type 1 and Type 2 AGN have the same bolometric correction. Kauffmann & Heckman (2009) adopted a mean bolometric correction of 600 for the extinction-corrected [OIII]5007 luminosity. This was based on the multi-waveband data subsequently presented in LaMassa et al. (2010) and is consistent with the average value for the extinction of the [OIII] emission as measured in Type 2 Seyferts by Kewley et al. (2006). We adopt this factor 600 bolometric correction for calculations within this review.

Netzer (2009) finds similar mean bolometric corrections for the observed and extinction-corrected [OIII]5007 luminosities. He argues, however, that the bolometric correction for a given AGN will depend on the ionization state of the gas in the NLR and that a combination of the luminosities of the [OIII]5007 and [OI]6300 lines is a more robust estimator of the bolometric luminosity. We agree with this point, but note that the [OI]6300 line is significantly weaker than the [OIII]5007 line (by a factor of typically 3 in LINERs and 10 in Seyfert nuclei). Requiring the [OI] line to be well-detected diminishes the ability to probe AGN at lower luminosities and/or over larger volumes in the SDSS main galaxy sample. The difference between Netzer's method and ours is most significant in the case of LINERs. As we have discussed above, a number of recent papers have concluded that the majority of LINERs in the SDSS (those with the weakest emission-lines) are not bona fide AGN. However, for the minority population of LINERs that are clearly AGN we agree that Netzer's methodology is better.

Finally, it is important to note that these bolometric corrections can be luminosity dependent. This dependence is well-established in the hard X-ray regime where the bolometric correction increases systematically with luminosity (e.g. Marconi et al. 2004). There have been claims and counter-claims about a luminosity dependence for the bolometric correction to the [OIII] luminosity. Most recently, Stern & Laor (2012b) have analyzed SDSS spectra of a large sample of Type 1 AGN and find that in log-log plots the [OIII] luminosity has a sub-linear dependence on the UV continuum luminosity and on the broad Hα luminosity, but a linear dependence on the hard X-ray luminosity. They derive a bolometric correction to the [OIII] luminosity that increases by an order-of-magnitude over the range between $L_{[\mathrm{OIII}]} \sim 10^{6.5}$ and 10^{9} $\mathrm{L}_{\odot}$. However, Shao et al. (2013) find a linear dependence of the [OIII] luminosity on the mid-IR luminosity (from WISE) for Type 2 SDSS AGN over the same range in [OIII] luminosity. LaMassa et al. (2010) found a super-linear dependence of $L_{[\mathrm{OIII}]}$ on the mid-IR continuum luminosity for Type 2 AGN. Hainline et al. (2013) confirm this relationship, extending it to the yet higher luminosities of Type 2 QSOs. The implied bolometric correction to $L_{[\mathrm{OIII}]}$ decreases by about an order-of-magnitude between $L_{[\mathrm{OIII}]} \sim 10^{6}$ and $10^{9.5}$ $\mathrm{L}_{\odot}$ (i.e. the opposite of the result Stern & Laor found for Type 1 AGN). The reason for this disagreement is not clear. Hainline et al. also find a possible saturation in $L_{[\mathrm{OIII}]}$ at MIR luminosities above about 10^{12} $\mathrm{L}_{\odot}$ and attribute this to a transition to matter-bounded conditions where the AGN is effectively photo-ionizing the entire galaxy ISM (see also Netzer et al. 2006). We emphasize in closing that most of the results reviewed below (and our own new analyses) have assumed a luminosity-independent bolometric correction for $L_{[\mathrm{OIII}]}$ in Type 2 AGN.

2.3.2. Mechanical Energy Outflow Rates in Radio Jets

We now turn our attention to estimating the energy outflow rate in radio jets. In jet-mode AGN, this can greatly exceed the radiative bolometric luminosity. It can also make a significant contribution to the total energetics in the small population of radio-loud radiative-mode AGN.

The AGN jets are observable through their radio synchrotron emission. Monochromatic radio luminosity

represents only a small fraction of the energy transport: the mechanical (kinetic) power of the jets is estimated to be about 2 orders of magnitude larger (Scheuer 1974). The jet mechanical power ($P_{\rm mech}$) can be estimated from the synchrotron emission using the minimum energy condition to estimate the energy stored in the radio lobes. This assumes that the magnetic field has the strength that minimizes the combined energy content of particles and magnetic fields needed to produce the observed synchrotron emission (see Miley 1980). This is then combined with the age of the radio source (from synchrotron spectral ageing techniques, or radio source growth models; cf. Willott et al. 1999) and an efficiency factor that accounts for losses due to work done by the expanding radio source (Rawlings & Saunders 1991).

Our incomplete knowledge of the physics of radio sources leads to significant uncertainties in this estimation. Primary amongst these are the composition of the radio jet plasma and the low energy cutoff of the electron energy distribution. The observed synchrotron emission traces only the highly relativistic electron population, and there are indications that the energy density in protons may be up to an order of magnitude higher (e.g. Bell 1978). Similarly, extrapolating the electron energy distribution down from the observed limit of $\gamma > 100$ to $\gamma \sim 1$ can increase the energy estimates by a factor of a few (depending upon the spectral index). Willott et al. (1999) combined all of the uncertainties into a single factor, $f_{\rm W}$, which through observational constraints they determined to lie between ~ 1 and 20. Subsequent work favored values towards the upper end of that range (e.g. Blundell & Rawlings 2000, Hardcastle et al. 2007). The mechanical jet power derived by Willott et al., expressed in terms of the 1.4 GHz radio luminosity, corresponds to:

$$P_{\rm mech,sync} = 4 \times 10^{35} (f_{\rm W})^{3/2} (\rm L_{1.4GHz}/10^{25} WHz^{-1})^{0.86} \text{ W (Eq 1)}$$

Note that weak dependencies on other radio source properties such as environment and source size also exist (see also Shabala & Godfrey 2013), but can be ignored to first-order. O'Dea et al. (2009) used deep multi-frequency radio data for 31 powerful radio galaxies to observationally estimate the pressure, volume and spectral age of the lobes, and hence the derive jet power. Daly et al. (2012) combined these with the radio luminosities to derive a relation between $P_{\rm mech}$ and $L_{\rm radio}$ and found a slope of 0.84, almost exactly the same as the Willott et al. theoretical prediction. Their normalization is consistent with Eq 1 for $f_{\rm W} \sim 5$.

The expanding radio sources inflate lobes of relativistic plasma, which in X-rays can be observed as bubbles, or cavities, in the surrounding hot gas (Böhringer et al. 1993). As X-ray facilities developed the sensitivity and angular resolution to accurately measure the extent of these cavities and the pressure of the surrounding intergalactic medium, an alternative method of estimating the radio jet power became available. Bîrzan et al. (2004) derived the pV energy associated with the cavities in a sample of groups and clusters, and used the buoyancy timescale (e.g. Churazov et al. 2001) to estimate their ages. They combined these cavity powers with the monochromatic 1.4 GHz radio luminosities to show that the two were well-correlated, with a scatter of $\sim$0.7 dex. Further cavity power measurements in systems ranging from giant elliptical galaxies to the most massive clusters have refined this correlation (e.g. Dunn et al. 2005, Rafferty et al. 2006, Bîrzan et al. 2008, Cavagnolo et al. 2010; see Fig.8). The largest uncertainty in this method is the determination of the cavity energy from the measured pressure and volume: $\rm E_{cav} = f_{cav} pV$. The work done inflating the cavity implies $f_{\rm cav} > 1$, while for the relativistic plasma of the radio lobes the enthalpy of the cavity is $4pV$. Additional heating arising directly from the radio jet shocks (e.g. Forman et al. 2007) could imply higher values of $f_{\rm cav}$, with some authors arguing that $f_{\rm cav}$ can be as high as ~ 10 (e.g. Nusser et al. 2006). The value of $f_{\rm cav} = 4$ is the one usually adopted (e.g. Cavagnolo et al. 2010) and is consistent with a broad balance between AGN heating and radiative cooling in massive clusters (see Section 6).

Fig. 8 shows a compilation of jet mechanical energy (assuming $4pV$) and radio luminosity measurements, primarily drawn from the analysis of Cavagnolo et al. (2010), recast into the same format as Eq 1. From



Fig. 8.— The jet mechanical energy of radio sources, estimated as $4pV$ from cavities and bubbles in the X–ray gas, versus the monochromatic 1.4 GHz radio luminosity. Data are primarily sourced from Cavagnolo et al. (2010), Bîrzan et al. (2008) and Rafferty et al. (2006). The solid line indicates the best-fit linear relation, given in Eq 2. For comparison, the dotted lines show the synchrotron estimate of Eq 1, for values of $f_{\rm W} = 10$ and 20.

this we derive a best-fit linear relation of

$$P_{\rm mech,cav} = 7 \times 10^{36} f_{\rm cav} (L_{1.4\rm GHz}/10^{25} \rm W Hz^{-1})^{0.68} \ \rm W \ (Eq\ 2)$$

Eqs 1 and 2 show very similar slopes, and for factors of $f_{\rm cav} = 4$ and $f_{\rm W} = 15$, the normalizations also agree for typical sources of $L_{1.4\rm GHz} \sim 10^{25} \rm W\,Hz^{-1}$ (see Fig. 8). Although discrepancies would exist for lower values of $f_{\rm W}$ (cf. Daly et al. 2012), the degree of agreement between these two independent estimators is encouraging. Hereafter in this review, Eq 2 with $f_{\rm cav} = 4$ is adopted to calculate jet mechanical power from the radio luminosity.

2.3.3. Black Hole Masses, Eddington Ratios, & Accretion Rates

The masses for supermassive black holes (SMBH) have been determined in two types of situations. In the case of Type 1 AGN, the time-dependent response of the gas in the Broad Line Region (BLR) to changes in the ionizing continuum flux can be used to infer a size for the BLR (from light-travel-time arguments). This size, together with the measured velocity dispersion in the BLR can be used to estimate $M_{\rm BH}$ under the assumption that gas is acting solely under the dynamical influence of the SMBH. This technique is called reverberation mapping and has been recently reviewed by Peterson (2013). The sub-sample of SMBH with masses determined by reverberation mapping can be used to calibrate a relation between $M_{\rm BH}$ and a combination of the widths of the broad emission-lines and the optical continuum luminosity in Type 1 AGN (e.g. Kaspi et al. 2000, Bentz et al. 2013).

In this review we are focused on Type 2 and jet-mode AGN and their relationship to the more numerous population of inactive galaxies. In these cases, $M_{\rm BH}$ has been measured directly through the dynamical modeling of the spatially resolved kinematics of stars and/or gas. This subject has been recently reviewed

by Kormendy & Ho (2013). There are still fewer than 100 galaxies in which $M_{\rm BH}$ has been determined directly. In order to estimate $M_{\rm BH}$ in large surveys like SDSS, indirect (secondary) techniques must be used. The most widely used secondary technique is based on a fit to the relationship between $M_{\rm BH}$ and the stellar velocity dispersion (σ) of the surrounding galactic bulge (the M-σ relation – Ferrarese & Merritt 2000, Gebhardt et al. 2000; see Fig. 9). This technique is particularly useful for the SDSS main galaxy sample. The SDSS fiber typically covers the region within a radius of a few kpc of the nucleus. The typical hosts for the SDSS AGN are early-type galaxies (see Section 4 below) and thus the measured stellar velocity dispersion is representative of the bulge.

Most of the results in the literature that used the M-σ relation were based on the fit given in Tremaine et al. (2002): $\log(M_{\rm BH}/M_\odot) = 8.13 + 4.02\log[\sigma/(200{\rm kms}^{-1})]$. More recent work has found a steeper slope and a different normalization than the Tremaine et al. fit (see the Kormendy & Ho 2013 review). More specifically, the recent analyses by Graham & Scott (2013), McConnell & Ma (2013), and Woo et al. (2013) find respective slopes of (6.18,5.64,5.48) and zero-points of (8.15, 8.32, 8.33). Woo et al. (2013) also conclude that the relationship between black hole mass and σ is consistent between samples of AGN and quiescent galaxies (see Fig. 9), and this conclusion was reinforced by an investigation of powerful AGN with more massive black holes by Grier et al. (2013). In terms of applicability to SDSS, note that the SDSS spectra can only reliably measure stellar velocity dispersions above $\sigma \sim 70\,{\rm km\,s^{-1}}$, corresponding to black hole masses larger than of-order 10^6 $M_\odot$ (depending on which version of M-σ is adopted). A complementary probe of lower-mass SMBH in SDSS is provided by using mass estimates based on the broad emission-line width for Type 1 AGN (Greene & Ho 2007b, Dong et al. 2012, Kormendy & Ho 2013).

Another secondary technique uses the correlation between $M_{\rm BH}$ and the stellar mass of the bulge (e.g. Marconi & Hunt 2003, Haring & Rix 2004). While this is straightforward to apply to elliptical galaxies, the typical AGN host galaxies in the SDSS sample have significant bulge and disk components (Section 4). The SDSS images are shallow and do not well-resolve the bulge component in typical cases. This makes the task of robustly determining the bulge/disk mass ratio rather expensive in terms of computational time and the need for human intervention (e.g. Gadotti 2009, Lackner & Gunn 2012). Thus, this technique for estimating $M_{\rm BH}$ is less readily applicable to the SDSS AGN sample. Moreover, the new data compiled by Kormendy & Ho (2013) and the analysis in Graham & Scott (2013) both imply that the correlation of $M_{\rm BH}$ is significantly poorer with stellar bulge mass than with σ.

In this review we derive values for $M_{\rm BH}$ using the simple power-law M-σ relation in McConnell & Ma (2013), specifically:

$\log(M_{\rm BH}/M_\odot) = 8.32 + 5.64\log[\sigma/(200{\rm kms}^{-1})]$ (Eq 3)

It is important to emphasize here that it is *not* a reasonable approximation to assume that the black hole mass is some fixed fraction of the *total* stellar mass. To illustrate this we show in the right panel of Fig. 9 a plot of the total galaxy stellar mass *vs.* the black hole mass as estimated using our adopted M-σ relation for the SDSS main galaxy sample. The ratio of estimated black hole to galaxy mass drops from an average of about $10^{-2.5}$ at $M_* \sim 10^{11.5}$ $M_\odot$ to about 10^{-4} at $M_* \sim 10^{10}$ $M_\odot$. As also shown in this figure, this is true for galaxies in general and for the hosts of both radiative-mode and jet-mode AGN.

With an estimate of the AGN bolometric luminosity and supermassive black hole mass in hand it is useful to then recast things in terms of the Eddington ratio for the AGN ($L_{\rm bol}/L_{\rm Edd}$). Here $L_{\rm Edd}$ is the luminosity of the classical Eddington limit:

$L_{\rm Edd} = (4\pi G m_p c/\sigma_T) M_{\rm BH} = 3.3 \times 10^4 M_{\rm BH}$ (Eq4)



Fig. 9.— Left: The M_{BH}-σ relation of local galaxies with direct black hole mass measurements (data from Woo et al. 2013 and references therein). Both AGN (the color-coding includes both radiative-mode and jet-mode AGN) and quiescent galaxies are consistent with the McConnell & Ma (2013) relation, shown by the solid line. Right: The distribution of galaxies in the SDSS main galaxy sample on the stellar mass *vs.* black hole mass plane, using black hole masses derived from the M_{BH}-σ relation. The greyscale indicates the volume-weighted distribution of all galaxies, with each lighter color band indicating a factor of two increase. It is clear that the black hole mass is not a fixed fraction of the *total* stellar mass. This is also true for AGN: the blue and red contours show the volume-weighted distributions of high (>1%; mostly radiative-mode) and low (< 1%; mostly jet-mode) Eddington-fraction AGN, with contours spaced by a factor of two.

where for the numerical form of the relation the luminosity and mass are in solar units. More uncertain still is an estimate of the accretion rate onto the SMBH. This is typically computed assuming a fixed efficiency ϵ for the conversion of accreted mass into radiant energy:

$$L_{\rm bol} = \epsilon \dot{M} c^2 \quad \text{(Eq 5)}$$

It is typically assumed that $\epsilon \sim 0.1$. This relatively high efficiency is well-motivated theoretically for a black hole radiating at a significant fraction of the Eddington limit (i.e. the radiative-mode AGN), but may substantially under-estimate the accretion rate of AGN with very small Eddington ratios (the jet-mode AGN). We will discuss this more quantitatively in Section 5 below.

2.4. Determining Basic Galaxy Parameters

2.4.1. From Imaging and Photometry

With the advent of digital surveys of large regions of the sky, astronomers were motivated to design automated algorithms for measuring the principle properties of galaxies (e.g. Lupton et al. 2002). The size of a galaxy is most often parameterized by the radius that encloses a fixed fraction (often 50%; written as R_{50}) of the total light. The shape of the radial surface-brightness profile provides a simple way to estimate the prominence of the bulge with respect to the disk: galaxies with concentration index $C = R_{90}/R_{50} > 2.6$ are predominantly bulge-dominated systems, with Hubble classification of Type Sa or earlier, whereas galaxies with $C < 2.6$ are mostly disk-dominated systems (Shimasaku et al. 2001). Gadotti (2009) performed 2-

dimensional bulge/bar/disk decompositions of a representative sample of galaxies from the SDSS and found that the concentration index correlated more tightly with bulge-to-disk ratio than the Sersic index n obtained from 1-dimensional profile fitting. Lackner & Gunn (2012) reached a similar conclusion from analysis of a larger SDSS sample. Recently, the power of citizen science has been exploited to create visual classifications of roughly 900,000 SDSS galaxies (Lintott et al. 2011). These classifications have been used to document the nature of the host galaxies of AGN.

The stellar mass-to-light ratio (and hence the stellar mass) of a galaxy can be measured using multi-band optical and near-IR photometry to an accuracy of $\sim 10\%$. While this spectral energy distribution will be sensitive to both the (luminosity-weighted) age of the stellar population and the amount of dust reddening, these two effects operate in such a way that the relation between optical color and M/L is linear with little scatter if galaxies have undergone relatively smooth recent star formation histories (Bell & De Jong 2001, Salim et al. 2005). These estimates assume a fixed stellar initial mass function (IMF). The effective surface mass density μ_* is then defined as $0.5M_*/(\pi R_{50}^2)$.

The star formation rate of a galaxy can also be estimated from fits to the ultraviolet through near-IR multiband photometry (e.g. Salim et al. 2005). Ultraviolet photometry from GALEX is particularly important as it probes the young stellar population in star-forming galaxies. We note, however, that in the absence of far-infrared photometry, which allows the thermal emission from dust to be measured directly, star formation rates estimated from UV/optical photometry can be significantly biased if the range of dust extinction values in the SED model library is incorrect (Saintonge et al. 2011, Wuyts et al. 2011a). Most of this dust emission powered by the reprocessing of ultraviolet light from massive stars emerges in the far-infrared. Unfortunately, the depth of the all-sky IRAS survey is not well matched to the SDSS main galaxy sample, with only about 2% of these galaxies being reliably detected by IRAS at 60 and 100 μm (Pasquali et al. 2005). The situation has been improved in some respects by the WISE survey which detects about 25% of the SDSS main galaxies in all four WISE bands (3.4, 4.6, 12, and 22 μm). The disadvantage of the WISE data for estimating the star formation rate is that larger and more uncertain corrections need to be made to estimate the total infrared luminosity than in the case of IRAS. In the case of AGN, the WISE data suffer from the further problem of potential contamination by AGN-powered emission from warm dust in the obscuring structure, even at the longest-wavelength WISE band (22 μm).

Finally, radio continuum emission can also be used to estimate the star-formation rate since it shows a strong correlation with the far-infrared emission in star-forming galaxies (Condon et al. 1992). Given the depth of the FIRST survey, the sensitivity of this technique over the SDSS volume is rather similar to that of the IRAS Faint Source Catalog, but – for our purposes – it has the disadvantage of being more susceptible to contamination by AGN emission than the far-IR.

2.4.2. From Spectra

The spectra available for galaxies from the SDSS are taken through 3 arcsecond diameter fibers. At the median redshift of the main galaxy sample ($z \sim 0.1$), only about 25-30% of the total light from the galaxy is sampled. As a result, estimates of the global star formation rates of SDSS galaxies cannot be made using only the spectra (Brinchmann et al. 2004). The spectra do, however, provide a very useful probe of the central stellar populations of normal galaxies and AGN hosts.

The break occurring at 4000Å is the strongest discontinuity in the optical spectrum of a galaxy. The main contribution to the opacity comes from low-ionization metals. In hot stars, the elements are multiply

ionized and the opacity decreases, so the 4000Å break will be small for young stellar populations and large for old, metal-rich galaxies. A break index, D(4000), was defined initially by Bruzual (1983). A definition using narrower and more closely-spaced continuum bands was introduced by Balogh et al. (1999), and has the advantage of being considerably less sensitive to reddening effects.

Strong Balmer absorption lines arise in galaxies that experienced a burst of star formation that ended $\sim 10^8$ to 10^9 years ago, when A stars are the dominant contributors to the optical continuum (e.g. Dressler & Gunn 1983). Worthey & Ottaviani (1997) defined an Hδ_A index using a central bandpass bracketed by two pseudo-continuum bandpasses. Kauffmann et al. (2003b) used stellar population models (Bruzual & Charlot 2003) to show that the locus of galaxies in the D(4000)-Hδ_A plane is a powerful diagnostic of whether galaxies have been forming stars continuously or in bursts over the past 1-2 Gyr. In addition, these two stellar indices are largely insensitive to the dust attenuation effects that complicate the interpretation of broad-band colors. These indices are very useful diagnostics of the recent star formation history of Type 2 and jet-mode AGN.

Measurements of the Hδ_A index that have a precision that is good enough to provide useful constraints require relatively high signal-to-noise data. However, the Hδ line itself is only one of a handful of other high-order Balmer lines in the blue/near-UV portion of the spectrum. The situation can be significantly improved by utilizing the combined information in these lines. One technique for doing so uses Principal Component Analysis (PCA). This approach has been successfully applied to SDSS spectra by Wild et al. (2007) and Chen et al. (2012). More examples of the use of PCA and other sophisticated techniques for extraction of information about the stellar content and star-formation history from the SDSS galaxy spectra include Panter et al. (2003, 2007), Cid Fernandes et al. (2005), and Yip et al. (2004).

3. BLACK HOLE MASS & AGN LUMINOSITY FUNCTIONS

3.1. The Radiative-Mode Population

The luminosity functions for the radiative-mode AGN (Seyferts and QSOs) can be constructed using a variety of different indicators. Some indicators, such as broad-band optical luminosities, are effective at probing unobscured black holes accreting near their Eddington limit at high redshifts. However, when the accretion rate is low, these broad-band optical luminosities are dominated by stellar emission from the host galaxy. Moreover, the optical/UV continuum will not recover the obscured (Type 2) AGN population. Other indicators, such as high-ionization nebular emission line luminosities, mid-infrared continuum emission, and X-ray emission have been used to probe lower accretion rate and obscured systems. Nice syntheses of these multi-waveband data have been undertaken by Hopkins et al. (2007) and Shankar et al. (2009) who use them to produce bolometric luminosity functions for the radiative-mode AGN that span the redshift range from ~ 0 to 6.

At a given redshift, the AGN bolometric luminosity function can be approximated as a double power-law:

$$d\Phi/d\log(L) = \phi_*/((L/L_*)^{\gamma_1} + (L/L_*)^{\gamma_2}) \quad \text{(Eq6)}$$

This is characterized by a faint end slope (γ_1), a bright end slope (γ_2), the characteristic luminosity of the break in the function (L_*) and the co-moving space density of AGN with that luminosity (ϕ_*). The evolution of the bright end of the luminosity function from redshifts ~ 0 to 3 can be well-described by a so-called pure luminosity evolution (PLE) model in which L_* evolves strongly with redshift, while γ_2 and ϕ_* do not (Hopkins et al. 2007). Fiore et al. (2012) show that this behavior of the bright AGN population may extend

to even higher redshifts. The value for L_* (bolometric) increases from about $10^{11.5}$ $L_\odot$ at $z \sim 0$ to 10^{13} $L_\odot$ at $z \sim 2$ to 3, and then declines at higher redshift (e.g. Hopkins et al. 2007, Shankar et al. 2009).

The first clear indications for a departure from the PLE model came from X-ray surveys of AGN using Chandra, which generated complete samples of Type 1 AGN down to significantly lower luminosities than was possible with optical surveys (see Brandt & Hasinger 2005). These surveys demonstrated that the space density of lower luminosity AGN peaks at lower redshift than that of higher luminosity AGN, a phenomenon that is often referred to as AGN down-sizing. Similar results were later obtained by optical QSO surveys that pushed down to fainter flux levels. The QSO luminosity function of the completed 2dF-SDSS optically-selected QSO survey (Croom et al. 2009) agrees extremely well in both amplitude and shape with the X-ray selected QSO luminosity functions of Hasinger et al. (2005).

In terms of the luminosity function, this departure from a pure PLE model is primarily manifested as an evolution in the faint end slope with γ_1 increasing from ∼0.3 at $z = 3$ to ∼0.9 at $z = 0$ (Hopkins et al. 2007). The steep faint-end slope at low-z is seen for both Type 1 and Type 2 AGN and in both the [OIII]5007 (Hao et al. 2005a) and hard X-ray (Ueda et al. 2011 and references therein) luminosity functions. Note that a faint end slope of 1 corresponds to equal radiant output per bin in log L. This has an important implication: while at high-redshifts the bulk of the radiant output occurs in AGN near L_*, this is not the case in the contemporary universe where it is spread rather evenly across a broad range in luminosity (and only about 20% is produced by AGN with $L_{\rm bol} > L_*$).

Heckman et al. (2004) used data from the SDSS to compute the integrated [OIII] luminosity emitted by (Type 2 and jet-mode) emission-line AGN per unit black hole mass for nearby black holes spanning the mass range from $3 \times 10^6 - 10^9$ $M_\odot$. They adopted a bolometric correction $L_{\rm bol}/L_{\rm [OIII]} = 3500$ (see Section 2.3.1) and a mass-to-energy conversion efficiency of $\epsilon = 0.1$ to transform these ratios into estimates of the time taken for the entire population of black holes to have grown to their present-day mass, given their present-day volume-averaged accretion rate. They defined the mass-dependent volume-averaged growth time for the local population of black holes to be the total mass of the BH population per unit volume in a given BH mass bin divided by the total growth rate of the BH population per unit volume in the same BH mass bin. They then found that this volume-averaged growth time of the population was of-order the Hubble time for black holes with masses less than $10^{7.5} M_\odot$, but that this growth time increased sharply for higher mass black holes, implying that most of their mass was accreted at high redshifts (Fig. 10). Greene & Ho (2007a, 2009) reached similar conclusions for the local Type 1 AGN population in the SDSS.

Heckman et al. (2004) also studied the fraction of black holes of mass $M_{\rm BH}$ with accretion rates above a given value. They showed that these cumulative accretion rate functions cut off sharply at $\dot{M}_{\rm BH}/\dot{M}_{\rm Edd} \simeq 1$. Many more low mass black holes than high mass black holes had accretion rates near the Eddington limit (0.5% of $10^7 M_\odot$ black holes are accreting above a tenth the Eddington limit, as compared to 0.01% of black holes with masses $3 \times 10^8 M_\odot$). In a later paper, Kauffmann & Heckman (2009) analyzed Eddington ratio distribution functions in narrow bins of black hole mass. They found that the distribution functions can be decomposed into a log-normal distribution of accretion rates, plus a power-law function that dominates at low Eddington ratio. We will describe the dependence of this distribution function on the age of the central stellar population in Section 4.2 below (see also Fig. 12).



Fig. 10.— Logarithm of the ratio of the total bolometric radiated luminosity (as calculated from the [OIII] emission line; see Section 2.3.1) per unit volume due to emission-line AGN of a given black hole mass to the total mass per unit volume in black holes at that black hole mass (both in solar units) in the contemporary universe. The right axis shows the corresponding growth time (mass-doubling time) for the population of black holes in units of the Hubble time. The solid black line shows the result obtained by integrating over all AGNs in the sample. The dotted red line shows the effect of correcting the [OIII] luminosities for the contribution from star formation in composite galaxies. The dashed blue line shows the result obtained if only AGN with (reddening-corrected and star-formation corrected) [OIII] luminosities above $10^{7.5} L_{\odot}$ are included. The dash-dot green line includes only AGN with bolometric luminosities above 1% of the Eddington rate (this cut effectively reduces the sample to only radiative-mode AGN). Adapted from Heckman et al. (2004).

3.2. The Jet-Mode AGN

The broad nature of the radio luminosity function of local galaxies has been well-established for many years (e.g. Toffolatti et al. 1987, Condon 1989), but the large spectroscopic surveys have enabled both improved statistics and an accurate separation of the star-forming and radio-AGN populations. Radio luminosity functions derived from the Las Campanas redshift survey (Machalski & Godlowski 2000), the 2dFGRS (Sadler et al. 2002), the SDSS (Best et al. 2005a, Best & Heckman 2012) and the 6-degree-field galaxy survey (6dFGS; Mauch & Sadler 2007) are all in excellent agreement, and show that the local radio luminosity function of AGN is well-fitted by a double power-law model similar in form to Eq 6:

$\rho = \rho_0 / ((P/P_0)^{\alpha} + (P/P_0)^{\beta})$ (Eq7)

At 1.4 GHz, the best-fitting values from combining all four spectroscopic surveys above give $\rho_0 = 10^{-(5.33 \pm 0.12)}$ Mpc^{-3} $\log_{10}(P)^{-1}$, $P_0 = 10^{24.95 \pm 0.14}$ W Hz^{-1}, $\alpha = 0.42 \pm 0.04$ and $\beta = 1.66 \pm 0.21$. Mauch & Sadler (2007) show that, at the faint end, the radio luminosity function of radio-loud AGN continues with the same slope down to at least $P_{1.4\mathrm{GHz}} \sim 10^{20}$W Hz^{-1}. They argue that the luminosity function must begin to turn-over at around $P_{1.4\mathrm{GHz}} \sim 10^{19.5}$W Hz^{-1}, or the total space density of radio sources would exceed the space density of galaxies brighter than L_*, which form the typical hosts. Cattaneo & Best (2009) similarly argue for a turn-over no fainter than $P_{1.4\mathrm{GHz}} \sim 10^{19.2}$W Hz^{-1} by comparison with the local space density of supermassive black holes above 10^6 M$_{\odot}$. Thus, the observed radio luminosity functions now broadly constrain the entire distribution of AGN radio luminosities.



Fig. 11.— The local radio luminosity function of radio-loud AGN, split into radiative-mode and jet-mode sources. The data are largely drawn from the results of Best & Heckman (2012) who split these two populations and derived luminosity functions using radio-selected AGN in the SDSS main galaxy sample. However, as shown by Gendre et al. (2013), these results under-estimate the luminosity function of the radiative-mode AGN above 10^{26} W Hz^{-1}, where Type-1 AGN dominate. Therefore the results of Gendre et al. are adopted for the three highest luminosity points of the radiative-mode population. The local radio luminosity functions are well-fitted by broken power law models.

The AGN population as revealed by radio surveys is composed of two distinct categories of sources: a population with strong QSO/Seyfert-like emission-lines (historically refered to as high-excitation sources) and a population with weak LINER-like emission-lines (referred to as low-excitation; e.g. Hine & Longair 1979, Laing 1994). In the language of the present review these are radiative-mode and jet-mode AGN, where the high excitation sources form a small sub-population of radiative-mode AGN that produce powerful jets. Best & Heckman (2012) separated the radio luminosity function into these two radio source populations and showed that both are found over the full range of radio powers they observed (see Fig. 11). The jet-mode sources constitute about 95% of the radio-AGN population at all radio luminosities below $P_{1.4\rm GHz} = 10^{25}$W Hz^{-1}, but the radiative-mode population becomes dominant above 10^{26}W Hz^{-1}. In the radio samples derived from large spectroscopic surveys of the contemporary universe, therefore, the radio-AGN population is predominantly composed of the jet-mode (low-excitation) sources.

The local radio-AGN population has historically been split by Fanaroff & Riley (FR; 1974) radio morphology, where FR2 sources are 'edge-brightened' with jets that remain collimated until they end in bright hotspots, and FR1 sources are 'edge-darkened' with jets that flare and gradually fade. The FR1 and FR2 populations are also found over a wide range of overlapping radio powers, with the switch in the dominant local population occuring at around $P_{1.4\rm GHz} \sim 10^{25}$ W Hz^{-1} (cf. Best 2009, Gendre et al. 2010). There is considerable overlap between the jet-mode AGN population and those radio sources morphologically classified as FR1s, and also between the radiative-mode AGN with strong radio emission and the FR2s. However, the radio morphological split and the division in the nature of the accretion flow are not the same thing. The large overlap arises because the population switch occurs at similar radio powers, but there exists a large cross-population of jet-mode FR2s (e.g. Laing 1994) and a smaller population of radiative-mode FR1s

(e.g. Heywood et al. 2007), as quantified by Gendre et al. (2013).

Best et al. (2005b) considered the distribution of radio emission associated with AGN activity across galaxies of different black hole masses. They showed that the prevalence of radio-AGN activity is a very strong function of black hole mass, rising as $f_{\rm rad} \propto M_{\rm BH}^{1.6}$. This offered a proper quantification of earlier widespread statements in the literature that radio-loud AGN are found only in galaxies at the top end of the black hole mass function. Best et al. (2005b) also considered the bivariate distribution of radio luminosity and black hole mass. They found that the shape of the radio luminosity function showed only weak dependence on black hole mass.

The Eddington ratio distribution function of radio-loud AGN can be calculated by summing the jet mechanical luminosity and the bolometic radiative luminosity (cf. Section 2.3) to provide the total energetic output of the AGN. Best & Heckman (2012) showed that the radiative-mode and jet-mode radio sources show distinct distributions of Eddington ratios, with the latter typically accreting below 1% of their Eddington rate, while the former have typical accretion rates between 1 and 10% of Eddington. Considering sources with black hole masses between $10^{7.5}$ and 10^{9} $M_\odot$, the right panel of Fig. 12 shows the distribution of Eddington ratios of radio-loud AGN in the SDSS main galaxy sample, above 10^{-3} of the Eddington limit (incompleteness prohibits analysis below this level). The jet-mode sources dominate at low Eddington ratios and show a roughly power-law distribution with a slope of about -1.5. In contrast, the radiative-mode population shows a distribution peaked at a few percent of the Eddington limit.

3.3. The Black Hole Mass Function

The super-massive black hole mass function (BHMF) is defined as the co-moving number density of black holes per bin in log mass at a given redshift. The techniques used to determine the BHMF have been reviewed recently by Kelly & Merloni (2012). Here we briefly summarize the properties and implications of the BHMF.

In the contemporary universe the BHMF can be measured in an empirical model-independent fashion by adopting the measured scaling relation between black hole mass and the bulge mass or velocity dispersion (described in Section 2.3.3). Combined with the measured volume density of bulges as a function of velocity dispersion or stellar mass from the SDSS, the BHMF can then be computed. Shankar et al. (2009) have compared the BHMF derived this way by different groups (Fig. 13).

The two main conclusions to be drawn from this figure are that the distribution of mass in black holes today peaks in black holes with masses of around $10^{8.5} M_\odot$ and that the mass distribution is actually quite narrow (half the total mass in black holes resides in the mass range from $\sim 10^{7.8}$ to $10^{8.8}$ $M_\odot$). The integral of this distribution represents the total mass per unit volume in the contemporary universe ($\rho \sim 10^{5.7}$ $M_\odot$ Mpc^{-3}). This mass density is directly connected to the total energetic output of AGN over the history of the universe (Soltan 1982). Consistency with the cosmic evolution of the AGN bolometric luminosity function (summarized above) implies a mean accretion efficiency ($\epsilon = L_{\rm bol}/\dot{M}c^2$) of-order 10% (Yu & Tremaine 2002, Marconi et al. 2004, Hopkins et al. 2007, Shankar et al. 2009).

At higher redshifts the BHMF has usually been computed in a model-dependent fashion. These computations take the present-day BHMF as a boundary condition and use a continuity equation to relate the evolution of the BHMF to the accretion history as inferred from the evolution of the AGN luminosity function. To compute BHMF(z) an assumption must be made about the mean AGN light curve ($L(M_{\rm BH}, t)$)


D(4000) < 1.4
$10^{6.75} < M_{BH} < 10^{7.00}$
$10^{7.00} < M_{BH} < 10^{7.25}$
$10^{7.25} < M_{BH} < 10^{7.50}$
$10^{7.50} < M_{BH} < 10^{7.75}$
$10^{7.75} < M_{BH} < 10^{8.00}$
D(4000) > 1.7
$10^{7.0} < M_{BH} < 10^{7.5}$
$10^{7.5} < M_{BH} < 10^{8.0}$
$10^{8.0} < M_{BH} < 10^{8.5}$
$10^{8.5} < M_{BH} < 10^{9.0}$
Fraction of sources
$\log_{10}([L_{bol} / L_{Edd}])$
All radio-loud AGN
Jet-mode subset
Radiative-mode subset
$7.5 < \log M_{BH} < 9.0$
Fraction of sources
$\log_{10}([L_{rad} + L_{mech}] / L_{Edd})$

Fig. 12.— Left: the distribution of Eddington-scaled accretion ratios for emission-line selected AGN from the SDSS main galaxy sample, split by star-formation activity. Following Kauffmann & Heckman (2009), the distributions are shown separately for actively star-forming host galaxies (D(4000)<1.4) and for passive host galaxies (D(4000)> 1.7), each for a range of black hole masses. Fractions plotted are within each 0.25-dex wide bin in Eddington ratio. As found by Kauffmann & Heckman, the passive galaxies show a power-law distribution of Eddington fractions, the amplitude of which decreases with increasing black hole mass. In contrast, the Eddington ratios of the star-forming hosts show a log-normal distribution peaking at a few percent of Eddington. This distribution is largely independent of black hole mass (though this depends slightly upon the version of the M-σ relation adopted). Right: the Eddington-scaled accretion ratios of radio-loud AGN from SDSS, split into jet-mode and radiative-mode sources; again, fractions plotted are within each 0.25-dex wide bin. Here the bolometric luminosity is calculated by summing the radiative and mechanical contributions. The two classes show distributions remarkably similar to the populations seen for emission-line AGN in the left panel.

and the accretion efficiency (ϵ). Examples of this approach are Marconi et al. (2004), Shankar et al. (2009, 2013) and Cao (2010). An alternative technique for measuring BHMF(z) uses the mass function of actively accreting black holes and the so-called Black Hole Fundamental Plane (Merloni & Heinz 2008).

All these analyses reach qualitatively similar conclusions: the BHMF grows anti-hierarchically with the population of more massive BHs being produced at higher redshifts. The population of black holes with masses $> 10^9$ $M_\odot$ was largely in place by $z \sim 2$. Since $z \sim 1$ only the population of black holes with masses below about 10^8 $M_\odot$ has been growing significantly. As we have summarized above, this inference is directly confirmed by measurements of the mass-dependent growth rates of supermassive black holes in the contemporary universe (Heckman et al. 2004, Kauffmann & Heckman 2009).

4. HOST GALAXY PROPERTIES

4.1. Overview

In the introduction to this review we summarized the overall landscape defined by the population of galaxies in the contemporary universe and described the bimodal galaxy population (lower mass, lower density, star-forming (blue) *vs.* higher mass, higher density quiescent (red) galaxies. Here we want to see



Fig. 13.— A collection of estimates of the distribution of mass across the local black hole population (ie., the local black hole mass function scaled by black hole mass) taken from Shankar et al. (2009). The shaded grey area represents the range of estimates based on local scaling relations of M_{BH} with σ, M_{Bulge}, and L_{Bulge}. See Shankar et al. (2009) for details.

where the population of growing black holes today lives within this landscape. As we will see, both the structural properties of the galaxies and their stellar populations turn out to be crucial in this regard. We begin with an overview of both the radiative-mode and jet-mode AGN in this section, and will then follow with detailed discussions of the two populations in the two sections to follow.

To fully appreciate the interplay between the structural properties and the stellar population in AGN host galaxies it is worth taking a guided tour of the pair of multi-panel plots shown in Figs. 14 and 15, derived from the SDSS. Fig. 14 plots the volume-weighted values of various key parameters in the 2-dimensional space of stellar mass (M_*) and D(4000). The top four panels show the distributions of M_*, black hole mass (M_{BH}), extinction-corrected [OIII] luminosity from AGN ($L_{[OIII]}$; tracing bolometric radiative output), and the production of mechanical energy in radio jets (L_{mech}). The bottom four panels show the ratios of $L_{[OIII]}/M_*$, $L_{[OIII]}/M_{BH}$, L_{mech}/M_*, and L_{mech}/M_{BH}.

The plot weighted by M_* shows the basic layout of the bimodal galaxy population. The plot weighted by M_{BH} shows a shift towards higher values of M_* (consistent with the steep dependence of M_{BH} on M_* shown in Fig. 9). The plot weighted by $L_{[OIII]}$ traces the growth of black holes through accretion (this is essentially tracing the radiative-mode population of AGN). It is immediately clear that black hole growth is occurring primarily in moderately massive galaxies ($M_* \sim 10^{10}$ to a few times 10^{11} $M_\odot$) with a young central stellar population (see Kauffmann et al. 2003a; also see Fig. 2). This is further quantified by the panels below. The plot of $L_{[OIII]}/M_*$ shows a strong dependence on the age of the stellar population and only a weak dependence on M_* over the range from $M_* \sim 10^{10}$ to $10^{11.5}$ $M_\odot$. The plot of $L_{[OIII]}/M_{BH}$ (a proxy for the Eddington ratio) tells a similar story, but here the dependence is almost entirely in stellar age with essentially no dependence on stellar mass for a given value of D(4000).

A complementary set of plots is shown in Fig. 15 which shows the same set of distributions in the 2 dimensional space of M_{BH} *vs.* D(4000). These plots reinforce the conclusions above. The growth of black



Fig. 14.— Top panels: the distribution of galaxies from the SDSS main galaxy sample in the plane of stellar mass *vs.* 4000Å break strength, weighted according to (from left to right): stellar mass; black hole mass; reddening-corrected [OIII] line luminosity (ie., bolometric radiative luminosity); jet mechanical luminosity. Each color band corresponds to a factor of two difference, increasing from dark to light. Bottom panels: ratios of upper panels (same color coding) to illustrate the distributions of (from left to right): bolometric radiative luminosity per stellar mass; bolometric radiative luminosity per black hole mass; jet mechanical luminosity per stellar mass; jet mechanical luminosity per black hole mass.

holes as traced by [OIII] emission is primarily occurring in the lower mass black holes ($\sim 10^{6.5}$ to 10^8 $M_\odot$; Heckman et al. 2004), more specifically in the subset of these black holes that live in galaxies undergoing significant central star-formation. The plots of $L_{[OIII]}/M_*$ and $L_{[OIII]}/M_{BH}$ both illustrate the fact that the strong dependences of these ratios are primarily on the age of the central stellar population.

Turning our attention now to the panels involving L_{mech}, we see that the jet-mode population of AGN is almost disjoint from the radiative-mode AGN in the properties of the host galaxies and their black holes (see also Fig. 2). The bulk of the jet mechanical energy is produced by the most massive black holes ($M_{BH} \sim 10^8$ to $10^{9.5}$ $M_\odot$) living in the most massive galaxies ($M_* \sim 10^{11}$ to 10^{12} $M_\odot$), and generally having old stellar populations (although there is a minority population of massive galaxies with younger stellar populations). In direct contrast to the radiative-mode AGN, the plots of L_{mech}/M_* and L_{mech}/M_{BH} show strong positive correlations with both M_* and M_{BH} (see Best et al., 2005b) but only weak dependences on the age of the stellar population.

The main dependences revealed in these 2-D plots are summarized in a simpler form in Fig. 16 in which the mass-normalized AGN outputs are plotted as 1-D functions of M_*, μ_*, and D(4000). Three key



Fig. 15.— As Fig. 14, but now showing the distributions in the black hole mass *vs.* 4000Å break strength plane.

conclusions are evident.

First, there is only a slow rise of about 0.5 dex in L_{rad}/M_* on M_* over the range from 10^9 to $10^{10.7}$ $M_\odot$, but then a steeper drop at higher masses. This can be contrasted with the very steep increase in L_{mech}/M_* with M_*. This shows that the predominant form of energy produced by black holes switches from radiation to jet energy at the highest stellar masses ($> 10^{11.5}$ $M_\odot$). The cross-over corresponds to $M_{BH} > 10^9$ $M_\odot$. It is intriguing that the sum of the mass-normalized L_{rad} and L_{mech} remains relatively constant over the full stellar mass range plotted. Since the ratio of black hole to galaxy stellar mass rises strongly with increasing mass (Fig. 9) this near-constancy would not apply to AGN output normalized to black hole mass (e.g. Fig. 10).

Second, both modes of black hole output plummet precipitously below the characteristic value $\mu_* \sim 10^{8.5}$ $M_\odot$ kpc^{-2} that divides the bimodal galaxy population described in Section 1.3. The effective growth of black holes evidently requires conditions of high central density.

Finally, the strong overall increase in L_{rad}/M_* moving from old (D(4000) > 2) to intermediate-age (D(4000) ~ 1.5) stellar populations, followed by saturation at still younger ages is very clear. This was shown most explicitly by Kauffmann & Heckman (2009), and is consistent with the left-hand panel of Fig. 12. In contrast, the jet output is only significant compared to the radiative output in the galaxies with the oldest stellar populations (see Best et al. 2005b).

Taken together these figures clearly support the division of the AGN population into two separate modes,



Fig. 16.— The distribution of AGN luminosity per unit stellar mass amongst galaxies from the SDSS main galaxy sample, as a function of galaxy stellar mass (left), stellar surface mass density (middle) and 4000Å break strength (right). In each plot the blue line indicates the radiative luminosity output (estimated from the [OIII] emission line), the red line shows the mechanical luminosity output in the radio jet, and the black line shows the sum of the two.

as we have stressed throughout our review. The broad conclusions on host galaxy properties of the different AGN populations are summarised in Fig. 4.

4.2. The Hosts of Radiative-Mode AGN

The above plots for the radiative-mode AGN lead to a simple and physically satisfying conclusion: the accretion-driven growth of black holes in the contemporary universe is primarily occurring in centers of galaxies where two criteria are met: 1) there is an abundant supply of cold gas (whose presence is implied by recent or on-going star-formation) and 2) the stellar surface mass density is high. Putting these two criteria together it is natural to conclude that there is really one over-arching requirement, namely an abundant central supply of cold and dense gas. This is shown in an explicit and compact way in Fig. 17. In this section we will expand on this by considering different aspects of the relationship between black hole growth and star formation in some detail.

4.2.1. The Relationship to the Star-Formation Rate

So far we have discussed the relationship between AGN and star-formation only in a qualitative sense. Here we summarize what has been learned about the quantitative relationship. Let us consider the correlation between star-formation rate and AGN luminosity. There are two complementary approaches to this. One is to select a sample of AGN spanning a range of luminosity and then measure the star-formation rates for each. This is conceptually simple, but ignores the fact that many galaxies do not host detectable AGN, and these galaxies are ignored in the above approach. Thus, the second approach is to examine the distribution of AGN luminosity as a function of star-formation rate for a complete sample of galaxies selected without regard to the presence of an AGN.



Fig. 17.— The distributions of AGN bolometric radiative luminosity per unit galaxy stellar mass (left) and bolometric radiative luminosity per black hole mass (right) in the stellar surface mass density *vs.* 4000Å break strength plane. [Color-banding as in Fig. 14]. Radiative-mode AGN activity clearly requires both an abundant supply of cold gas (indicated by recent or on-going star formation) and a high stellar surface mass density.

As an example of the first approach, Kauffmann et al. (2003a) used SDSS to measure the distribution of the strength of the 4000Å break for AGN as a function of raw [OIII] luminosity. Based on subsequent calibration (by Brinchmann et al. 2004) of the 4000Å break as a function of specific star-formation rate (sSFR = SFR/M_*), there is a clear but shallow dependence: as the [OIII] luminosity increases from 10^6 to 10^9 $L_\odot$, the median sSFR only increases from $10^{-11.3}$ to 10^{-10} year^{-1}. This is consistent with the SDSS-based results of LaMassa et al. (2013) who find that the mean specific star-formation rate in Type 2 Seyferts (within a radius of about 2 kpc) only increases from $\sim 10^{-11}$ to 10^{-10} year^{-1} as the ratio of $L/L_{\rm Edd}$ increases from $\sim 10^{-3}$ to ~ 1. Similarly, they found that the star-formation rate in this central region only increases from 0.1 to 1 $M_\odot$ year^{-1} as the extinction-corrected [OIII] luminosity increases from $10^{6.5}$ to 10^9 $L_\odot$ (ie., SFR $\propto L_{\rm AGN}^{0.4}$). Diamond-Stanic & Rieke (2012) and Netzer (2009) find steeper but still sub-linear relations between star-formation rate and AGN luminosity (SFR $\propto L_{\rm AGN}^{0.6-0.8}$). Rosario et al. (2012) find no correlation (at z $\sim$ 0) between the global (galaxy-wide) SFR and AGN luminosity for AGN bolometric luminosities below about 10^{44} erg/s, and SFR $\propto L_{\rm AGN}^{0.5}$ at higher luminosity.

The second approach was taken by Kauffmann & Heckman (2009). They looked at the distribution of the Eddington ratio ($L_{\rm bol}/L_{\rm Edd}$) as a function of the amplitude of the 4000Å break for a complete SDSS-based sample of galaxies (see Fig. 12, left panel). They found that for galaxies with predominantly old central stellar populations, the probability of finding an AGN decreases with increasing Eddington ratio as a power-law. Using the calibration of Brinchmann et al. (2004), the results in Kauffmann & Heckman (2009) imply that the normalization of this power-law increases roughly linearly with the central sSFR over the range in the latter from $\sim 10^{-12}$ to $10^{-10.5}$ year^{-1}. However, at higher values of central sSFR, the Eddington ratio distribution transitions to a log-normal that peaks at an Eddington ratio of about 3%. In this regime, the Eddington ratio distribution is independent of the central sSFR. It is also largely independent of the mass of the black hole (though the precise details depend upon the version of the M-σ relation adopted). Thus, Kauffmann & Heckman found no simple monotonic relation between central star-formation and black hole growth rates. Once the central region of the galaxy has a mass-doubling time (M_*/SFR) that is comparable

to the current Hubble time, the SMBH growth rate saturates and is not boosted by additional star-formation. We will discuss some possible interpretations of this in Sections 5 and 6 below.

The combination of power-law plus narrow peaked distribution for the Eddington ratio distribution found for emission-line AGN bears close resemblance to the results of the radiative-mode *vs.* jet-mode decomposition of Eddington ratio distributions for radio AGN (Section 3.2; Fig. 12 right panel). This fits with the picture discussed above, that radiative-mode AGN are generally found in star-forming host galaxies while jet-mode AGN are mostly in passive galaxies. It also indicates that the main properties of the Eddington ratio distribution are largely independent of whether or not an AGN is classified as radio-loud. This further justifies our approach throughout this review of considering just two fundamental AGN modes (cf. Fig. 4).

4.2.2. The Radial Distribution of Star-Formation and Cold Gas

The physical connection between the fueling of the SMBH and star-formation should be clearer on smaller scales near the SMBH. Kauffmann et al. (2007) compared this relationship determined on two scales. They found that the luminosity of the AGN (relative to the Eddington limit) correlates much more tightly with the youth of the central stellar population of the galaxy as probed with the SDSS spectra than with its global stellar population as probed with SDSS and GALEX optical/UV imaging. They concluded that on-going star-formation in the global galaxy disk is a necessary but not sufficient condition for on-going star formation in the center and the concurrent growth of the SMBH: young bulges and their growing SMBH are only found in galaxies with star-forming disks, but many galaxies with star-forming disks have dead bulges and quiescent SMBHs.

A similar result was found by Diamond-Stanic & Rieke (2012) based on an analysis of Spitzer mid-IR imaging and spectroscopy of a sample of very nearby Seyfert galaxies. They found that the correlation between the star-formation rate and the rate of SMBH growth (measured using the luminosity of the [OIV]25.9 μm line) was significantly stronger for the star-formation rate measured in the inner-most kpc than for the entire galaxy. The radial distribution of the star-formation as a function of the AGN luminosity was mapped in a statistical sense by LaMassa et al. (2013) for a sample of 28,000 Type 2 Seyfert galaxies drawn from the SDSS. They examined the star-formation rate within the SDSS fiber for sub-samples matched in both host galaxy properties and AGN luminosity but spanning a range in mean redshift from $z \sim 0.05$ to 0.15 (so that the fiber mapped the star-formation over different radial scales in each sub-sample). They found that as the AGN luminosity increased, the total star-formation increased and became more and more centrally concentrated (located within about 2 kpc of the nucleus).

On smaller radial scales, the stellar populations in nearby Type 2 Seyfert nuclei have been investigated by Cid Fernandes et al. (2001) using optical spectra that probe typical radial scales of only a few hundred pc. By computing $L_{\rm bol}/L_{\rm Edd}$ for this sample, we find that a young stellar population can be directly detected surrounding about 75% of the Seyfert nuclei with luminosities exceeding 10% of the Eddington limit, but only in about 25% of those with lower luminosities. This investigation was extended to lower AGN luminosities and still smaller scales using ground-based and HST spectra by Cid Fernandes et al. (2004) and Gonzalez-Delgado et al. (2004) respectively. They found that the nuclear stellar populations were usually old, except in cases whose optical emission-line properties were consistent with an ionizing contribution from both an AGN and young stars.

A complementary picture emerges from consideration of the radial distribution of the cold gas associated

with star-formation. By comparing the hosts of radio-quiet AGN with control samples of non-AGN matched in stellar mass, structural properties and mean stellar age, Fabello et al. (2011) found that the global atomic gas (HI) content of a galaxy had no effect on the accretion rate on the central black hole. This agrees with earlier studies of the HI content of smaller samples of Seyfert galaxies (Heckman et al. 1978, Mirabel & Wilson 1984, Ho et al. 2008) which did not show systematic differences in HI content in Seyferts compared to normal galaxies. Atomic gas in a galaxy is generally spread out in a large-scale disk and the surface density of the HI exhibits a dip or even a hole in the center of the galaxy. If gas is present in the vicinity of the black hole, it is likely to be at high enough densities that it would exist primarily in molecular form.

Surveys of the global molecular content of AGN hosts using the mm-wave J=1-0 CO emission-line show only small (Heckman et al. 1989) or no (Maiolino et al. 1997, Saintonge et al. 2012) differences in the molecular content of AGN hosts compared to normal galaxies (in terms of CO luminosity normalized by galaxy optical luminosity, HI mass, or star-formation rate). On smaller radial scales, thick, clumpy disks of molecular gas with radii $\sim$ 30 pc have been found at the centers of nearby Seyfert galaxies (e.g. Hicks et al. 2009). More recently, Hicks et al. (2013) examined molecular gas on 50 pc to 1 kpc scales in a matched sample of Seyfert and quiescent galaxies and showed that the Seyferts had more centrally concentrated H_2 surface brightness profiles.

The presence of dust can serve as a proxy for cold gas. Kauffmann et al. (2007) showed that the central regions of the host galaxies of more rapidly growing black holes were more heavily dust-reddened than were the same regions in the hosts of low-power AGN. Simoes Lopes et al. (2007) used HST imaging to show that all of the 65 AGN host galaxies they studied have circum-nuclear dust structures on radial scales of $\sim$ 0.1 to 1 kpc (see also Gonzalez Delgado et al. 2008). This includes 34 early-type AGN hosts. In a carefully constructed control sample of normal galaxies only a minority (26%) of the early-type galaxies had circum-nuclear dust (though all the late-type control galaxies did). Subsequent Spitzer observations (Martini et al. 2013) imply dust masses of-order 10^6 $M_\odot$, or associated gas masses of-order 10^8 $M_\odot$. In a complementary study, Lauer et al. (2005) used HST images to discover a strong connection between the AGN emission-line activity and the presence, quantity and structure of central dust in a sample of 77 early-type galaxies. All-in-all, it seems reasonable to conclude that radiative-mode AGN reside in galaxies where the central (kpc-scale) supply of cold dense gas is substantial.

4.2.3. The Starburst-AGN Connection

We have seen above that the connection between SMBH growth and star-formation is clearer when the central kpc-scale region of the galaxy is probed. Such central star-formation can sometimes occur in a strong episodic burst, presumably related to the short dynamical times near the nucleus. The existence of a direct connection between the growth of a SMBH and intense star-formation in the centers of galaxies has long been a matter of speculation. In its most extreme form a direct starburst-AGN connection was posited: AGN were simply the evolved descendants of starbursts powered by a collection of supernovae and supernova remnants rather than by a SMBH (Terlevich & Melnick 1985, Terlevich et al. 1992). Many other authors have proposed less iconoclastic models in which the delivery of a fresh supply of cold gas to the center of a galaxy leads to both a strong starburst and the efficient fueling of the SMBH (e.g. Sanders et al. 1988a,b, Hopkins et al. 2006, 2008, Di Matteo et al. 2008).

Investigations of the starburst-AGN connection using SDSS spectra have shown that there is indeed a connection, but one that is more subtle than might have been expected. We have described above how SDSS



Fig. 18.— Top Panel: the mean black hole accretion rate (BHAR) averaged over all galaxies in a sample of starburst and post-starburst galaxies (black line). The grey-shaded area shows the typical 10th and 90th percentile range on the total BHAR estimated from bootstrap resampling of the data. The model prediction for the average gas mass-loss rate from the stars formed during the starburst (solid grey line) assumes an accretion efficiency onto the black hole of 0.5 per cent of the ejecta from intermediate and low-mass stars between the age of 250 and 600 Myr. Stars return mass to the ISM through supernova explosions and fast winds from massive stars (dotted line) and planetary nebula ejections and stellar winds from lower mass stars (dashed line). Bottom panel: the ratio of SFR (from Hα) to BHAR, with mean value and errors calculated as for the top panel. The BHAR lags the SFR and becomes significant only after several hundred Myr. Figure from Wild et al. (2010).

spectra can be used to identify starbursts and post-starbursts using the combination of the 4000Å break and the strength of the high-order Balmer absorption-lines. Based on this methodology, Kauffmann et al. (2003a) showed that high-luminosity Type 2 AGN in SDSS were more likely to have undergone a starburst within the last 10^9 years compared to low-luminosity AGN or normal galaxies of similar stellar mass (see also Goto 2006 and Yan et al. 2006). This issue was examined in more detail by Wild et al. (2007). Based on a sample 34,000 early-type galaxies in SDSS, they found that the post-starburst systems had the highest mean AGN luminosity. However, because these are relatively rare, they represent only about 15% of the total amount of SMBH growth in the contemporary universe. They found that galaxies with on-going (but less episodic) central star-formation are the sites of the majority of SMBH growth.

In a subsequent paper, Wild et al. (2010) examined the time history of SMBH growth during and after an intense burst of central star formation (involving roughly 10% of the galaxy stellar mass). They found that the growth of the SMBH was delayed by about 200 Myr relative to the start of the starburst (Fig. 18). These results pertain to the region within a radius of $\sim$ 1 to 2 kpc. Qualitatively similar results from SDSS were found by Schawinski et al. (2007) for galaxies selected morphologically to be ellipticals. On much smaller scales (ten to hundred pc) and for a much smaller sample, Davies et al. (2007) also find evidence for a delay of-order 100 Myr between a starburst and powerful AGN activity. We will return to a discussion of the implications of these results below.

4.3. The Hosts of Jet-Mode AGN

The results in Section 4.1 above show that the host galaxies of the black holes that dominate the production of jet mechanical energy are nearly disjoint from the host galaxies where black holes are actively growing. These jets are traced by their radio emission. Detailed investigations of the structure and stellar content of the radio-selected AGN population in SDSS were first undertaken by Best et al. (2005b). They confirmed the widely-held view that nearly all such AGN are hosted by massive elliptical galaxies with old stellar populations: the radio source hosts are highly bulge-dominated (their black hole mass *vs.* stellar-mass relation lies on the established black hole mass *vs.* bulge mass relation), with 4000Å break strengths clustered around 2.0, concentration indices typically between 2.9 and 3.4, and effective stellar surface mass densities around $10^9\,\mathrm{M}_\odot\,\mathrm{kpc}^{-2}$. This is entirely consistent with the results summarized in Section 4.1.

More interestingly, Best et al. (2005b) were able to quantify the prevalence of radio-AGN activity as a function of stellar mass and black hole mass with much greater statistical robustness than previous studies. They found that the fraction of galaxies selected via radio emission scaled as $\mathrm{M}_*^{2.5}$ and as $\mathrm{M}_{\mathrm{BH}}^{1.6}$, with these results being broadly independent of the radio luminosity limit. This is strikingly different from the mass-dependence of the prevalence of emission-line AGN activity (see Fig. 14). Best et al. (2005b) did not separate their sample into radiative-mode and jet-mode sources, but their sample was dominated by the latter, and it is these that drive the strong mass dependence. Janssen et al. (2012) considered the mass dependences of the two populations separately. They showed that the prevalence of radiative-mode radio sources has a much shallower dependence on mass, scaling as $\mathrm{M}_*^{1.5}$, albeit that this remains steeper than that found for radio-quiet radiative-mode AGN selected by their optical emission-lines.

For jet-mode sources, Best et al. found no evidence for any strong relationship between the [OIII] and radio luminosities; indeed the radio emitting fraction was found to be largely independent of whether or not the optical galaxy is classified as an emission-line AGN. This result breaks down at higher radio luminosities, when the radiative-mode radio sources begin to dominate. These have been long known to show a strong correlation between radio and emission line luminosities (e.g. Rawlings & Saunders 1991, Xu et al. 1999). Kauffmann et al. (2008) investigated the subset of radio sources within the SDSS that display emission lines, and confirmed this correlation, finding also that it became tighter if Eddington-scaled quantities (ie., $L_{1.4\mathrm{GHz}}/M_{\mathrm{BH}}$ and $L_{[\mathrm{OIII}]}/M_{\mathrm{BH}}$) were considered.

Lin et al. (2010) compared the host galaxies of radio sources separated into different radio morphological types. As previously discussed, these two radio morphological classes show a broad overlap with the jet-mode and radiative-mode classes, with most FR1s being jet-mode and most FR2s being radiative-mode; however, there are substantial differences between the segregation methods, and a significant population of jet-mode (low-excitation) FR2 sources exists. Lin et al. found that the most significant differences between FR1s and FR2s occurred for the subset of the FR2 population which displayed both strong high-excitation optical emission lines and hotspots close to the end of the radio lobes. They found this FR2 subset to be hosted by lower mass galaxies, with bluer colors, living in poorer environments and with higher accretion rates than the rest of the radio source population. Similarly Kauffmann et al. (2008) found that their radio-AGN with emission lines showed lower stellar masses, lower velocity dispersions, lower 4000Å break strengths, and stronger Balmer absorption features than those radio-AGN without emission lines.

Best & Heckman (2012) did an explicit separation of jet-mode and radiative-mode radio sources and confirmed these results. They also constructed matched samples of the two radio source classes, to investigate whether observed differences in host galaxy colors and morphologies were just secondary effects driven by, for example, the different stellar masses of the two samples. They found that the hosts of radiative-mode radio-

AGN have bluer colors, smaller half-light radii, lower concentration indices, and lower 4000Å break strengths than the hosts of jet-mode radio-AGN of the same stellar mass, black hole mass and radio luminosity. These results imply that the radiative-mode radio sources are associated with on-going star-formation activity, as is also seen in the radio-quiet AGN samples. Further evidence in support of this comes from the work of Sadler et al. (2013), who investigated differences in the mid-IR colors of the two radio source classes using WISE and concluded that star-formation activity was present in the radiative-mode AGN, but not the jet-mode AGN (see also Gürkan et al. 2013).

The larger scale lengths and higher concentration indices of the hosts of the jet-mode AGN can be explained if these sources are preferentially located toward the centers of groups and clusters (as suggested by their clustering and environmental properties; see Section 4.4), where host galaxies are typically larger and may have more extended (cD-type) light profiles. Mannering et al. (2011) compared the scale lengths of radio-AGN at both red and blue wavelengths and found that the ratio of the two was higher than for control galaxy samples, suggesting the possible presence of extended red envelopes (although their control samples were matched only in redshift and magnitude, so this result might be driven by morphology differences between the radio-AGN and control samples).

Janssen et al. (2012) considered the relationship between AGN classification, radio luminosity, and galaxy color. Red (passive) galaxies show a higher probability of hosting jet-mode radio-AGN than blue (star-forming) galaxies of the same stellar mass, by a factor of a few. Blue galaxies show a higher probability of hosting radiative-mode radio-AGN at all radio luminosities. For blue galaxies, the likelihood of hosting a radio-AGN of either class is a strong positive function of the star-formation rate. This suggests that the presence of cold, star-forming gas in a galaxy enhances the probability of its central black hole becoming a radio-loud AGN. This means that jet-mode AGN activity, especially at high radio luminosities, is not solely related to hot halo gas accretion (see Section 5 below).

4.4. Clustering, Environments, and Halo Masses of AGN

Since early in the study of Seyfert galaxies, QSOs, and powerful radio sources, attempts have been made to categorize the typical environments in which these sources are found (e.g. Gisler 1978, Longair & Seldner 1979, Yee & Green 1984). Analyses mostly relied on relatively small fields around the AGN, and either considered simple galaxy counts out to some projected radius, or divided those counts into annuli to enable a cross-correlation analysis. The majority of analyses indicated that AGN are found in a wide range of environments, with powerful QSOs and radio sources being often located in group or poor cluster environments, but Seyfert galaxies generally avoiding the densest environments. However, AGN samples were relatively small and contradictory results were obtained in different studies. Furthermore, AGN activity depends strongly on host galaxy properties such as stellar mass (especially for radio-selected AGN; see previous sections); therefore, in order to reliably isolate any trends of AGN activity that are explicitly caused by environment, large and homogeneous datasets like that offered by SDSS are required so that the AGN samples can be compared against control samples carefully matched in other galaxy properties. Even so, there has remained much debate as to the nature of these trends, largely because of the different definitions adopted both for AGN samples (all emission line AGN; just Seyfert sources; radio-AGN; etc) and for environment (local galaxy density; membership of, or distance from center of, a group or cluster).

Once stellar mass effects are properly accounted for, the incidence of optical emission-line AGN is generally found to be lower in denser environments and in groups and clusters, than in the field (Miller et al.

2003, Kauffmann et al. 2004, von der Linden et al. 2007): the fraction of AGN among galaxies of given stellar mass decreases by a factor of two from the field towards the cluster/group center. This is matched by a decrease in star-formation activity of these galaxies. Hwang et al. (2012) investigate these trends for early and late-type galaxies separately, and find that the prevalence of AGN activity in early-type galaxies already begins to decrease at the virial radius of the cluster, whereas in late-type galaxies it only decreases as the cluster center is approached. Chandra has revealed significant samples of X-ray-detected AGN in nearby galaxy clusters (e.g. Martini et al. 2006), the majority of which do not show emission lines and so are not identified as AGN in optical observations. These may be obscured AGN, or more likely may be jet-mode AGN. Haines et al. (2012) argues that luminous X-ray AGN in massive clusters are mostly an infalling population. These results are all generally consistent with a picture in which there is a gradual decline in emission-line AGN activity as the denser environment decreases the cold gas supply for an AGN.

In contrast to emission-line AGN, radio-selected AGN are found to be preferentially located in group and cluster environments (e.g. Best et al. 2005b, Sabater et al. 2013), confirming the results of many previous studies of small radio-loud AGN samples. This is particularly true of the jet-mode subset of the radio-AGN population (Best et al. 2004, Reviglio & Hefland 2006, Sabater et al. 2013), again suggesting a different mechanism for the triggering of AGN activity in these sources than for radiative-mode AGN. The prevalence of radio-AGN activity amongst brightest cluster galaxies (BCGs) is especially high (Best et al. 2007, Croft et al. 2007; cf. Burns 1990), while that of optical AGN is lower than in non-BCG galaxies of the same mass (von der Linden et al. 2007).

An alternative view of the environments of AGN can arise from looking at the two-point correlation function. This describes the excess probability of finding a galaxy at a given distance R from another galaxy, due to clustering. In the widely adopted halo-model description of large-scale structure, on small scales ($<$ 1Mpc) the signal in the correlation function is dominated by pairs of galaxies within the same dark matter halo (known as the one-halo term; e.g. Seljak 2000). This therefore measures the prevalence of a particular galaxy type amongst satellite galaxies in halos. Li et al. (2006) computed the cross-correlation function between Seyfert galaxies and the SDSS spectroscopic main galaxy sample, and compared this against the results for a non-AGN control sample that was matched in redshift, stellar mass, black hole mass (from velocity dispersion), concentration index and 4000Å break strength. They found that on scales between 100 kpc and 1 Mpc the AGN showed weaker clustering than the control sample. By comparison with simulations, they argued that this could be understood if AGN activity was dis-favored within satellite galaxies. This interpretation is consistent with the results arising from the study of AGN activity as a function of cluster membership or local galaxy density, discussed above.

On much larger scales (10-20 Mpc) the two-point correlation function measures the correlation between different dark matter halos (the two-halo term), which depends upon the properties of the parent halo for a given galaxy type (see review by Cooray & Sheth 2002). If the luminosity function and two-point correlation function of a set of objects is known, then (for a given cosmological model) it is possible to estimate the mean mass of the parent dark matter halo (e.g. Sheth, Mo & Tormen 2001). Mandelbaum et al. (2009) used this method to estimate dark matter halo masses for ($z < 0.3$) Seyfert galaxies from the SDSS, and confirmed the reliability of their measurements by using an alternative estimate from weak gravitational lensing of background galaxies. They found a mean halo mass of $\sim 10^{12}$ $M_{\odot}$. They compared these results against a control sample of non-AGN, and found that the halo mass versus stellar mass relation was independent of whether or not Seyfert activity was present.

Mandelbaum et al. (2009) also analyzed radio-loud AGN in the same redshift range. They found an average halo mass for the radio-loud AGN of 10^{13} solar masses, nearly an order of magnitude higher than

that of optically-selected AGN. Much of this increase is because radio-loud AGN are hosted by more massive galaxies, but Mandelbaum et al. also found that the dark matter haloes of radio-loud AGN are about twice as massive as those of control galaxies of the same stellar mass. A similar enhancement in the clustering strength of radio-loud AGN relative to a carefully-matched control sample of massive galaxies was found by Donoso et al. (2010) at redshifts $0.4 < z < 0.8$ using the SDSS Luminous Red Galaxy sample. Donoso et al. also showed that the clustering strength of the radio galaxy population is luminosity dependent. At low radio luminosities where the jet-mode AGN dominate the radio-AGN samples (these also dominated the Mandelbaum et al. sample), the clustering strength is enhanced relative to radio-loud QSOs. At higher radio luminosities the radio galaxy population is dominated by radiative-mode sources and the clustering amplitude is more in line with that of the radio-loud QSOs, as expected from the standard AGN Unified Model.

The 2dF and SDSS QSO redshift surveys have been used to study the dark matter haloes of powerful AGN to even higher redshifts (Porciani et al. 2004, Croom et al. 2005, Ross et al. 2009). Intriguingly, the mean mass of haloes hosting QSOs remains roughly constant (at around 2×10^{12} $M_{\odot}$) over the entire redshift range $z < 2.5$, and shows only weak dependence on QSO properties like luminosity, color or black hole mass (Croom et al. 2005, Shen et al. 2009). Only at the highest QSO luminosities is the clustering amplitude seen to increase. Shen et al. (2009) find that radio-loud QSOs reside in halos almost an order of magnitude larger than those of radio-quiet QSOs (though note that Donoso et al. 2010 do not find this strong signal amongst their $z \sim 0.6$ sample). Shen's result is in line with the local results of Mandelbaum et al.: a large part of this is likely to be driven by the higher typical stellar mass of radio-loud QSO hosts, but radio-AGN activity also seems to be preferentially found in denser environments.

In summary, radiative-mode AGN are located in dark matter haloes with a mean mass of $10^{12} M_{\odot}$, which is typical for their stellar masses. Once stellar mass biases are account for, the prevalence of radiative-mode AGN is lower in denser environments than in the field, because they are dis-favored in satellite galaxies; this mirrors the decrease in star formation activity in denser environments, with both trends being driven the reduced cold gas supply. Radiative-mode AGN that are found in denser environments are more likely to be radio-loud. This partly reflects the trend for radio-loud radiative-mode AGN to be hosted by more massive galaxies (see Fig. 4), but may also be enhanced by a boosting of the radio luminosity in dense environments, where confinement of the radio lobes reduces adiabatic losses (e.g. Barthel & Arnaud 1996). In contrast to radiative-mode AGN, jet-mode AGN have an increased prevalance in denser environments, and especially in the central galaxies of groups and clusters. This indicates a different fueling mechanism.

5. BLACK HOLE FUELING

5.1. The nature of the accretion flow

There are three main features that we need to consider when examining the fueling of AGN: the origin of the fueling gas, the mechanism by which it is transported to the vicinity of the black hole (e.g. Hopkins & Quataert 2011), and the nature of the accretion flow onto the black hole. With regards to the last of these, the most important determining properties are the black hole mass, its spin, and the nature and rate of the inflow. Note that even if the AGN is powered by tapping the black hole spin via the Blandford & Znajek (1977) mechanism, accretion is required for this to occur.

Before embarking upon a discussion of the effects of different modes of accretion, it is worth summarizing the lessons that have been learned from studying accretion onto stellar-mass black holes in galactic X-ray

binary systems. These are systems consisting of a black hole of between roughly 4 and 20 solar masses in a close binary system with a normal star. At least in terms of the black hole properties, these represent analogs of accreting supermassive black holes, scaled down in both luminosity and the accretion timescales. They are not precise equivalents of AGN because the temperature of the accretion disk around a stellar mass black hole is typically two orders of magnitude higher than that around an AGN which can lead to differences in processes at atomic levels, such as ionization-dependent accretion instabilities. Nevertheless, stellar mass black holes offer the considerable advantage that variations in the accretion flow can be directly tracked, with changes in the accretion happening on timescales of less than days. The observed accretion rates vary between the Eddington rate and values several orders of magnitude below this.

X-ray binaries have been shown to display two fundamentally different X-ray spectral states (see the review by Remillard & McClintock 2006 in this journal). In the low-hard state, the source spectrum is characterised by low-luminosity, hard (predominantly > 10 keV) X-ray emission, and low-power radio jets are ubiquitous. The power of the radio jets is correlated (albeit non-linearly) with the X-ray luminosity (Gallo et al. 2003). In the high-soft state, sources are dominated by a high-luminosity thermal X-ray component, peaking at lower energies and with the characteristics of a standard geometrically-thin, optically-thick accretion disk. The primary difference between these two accretion modes is observed to be the accretion rate onto the black hole relative to the Eddington rate: the low-hard state is associated with accretion rates below a few percent of the Eddington rate, whereas the high-soft state arises when the accretion rate exceeds that value (Maccarone 2003). X-ray binaries are observed to traverse from one state to another. Within the low-hard state, there are indications that the transition radius between an inner advection-dominated flow and an outer thin disk (cf. Fig. 3) decreases with increasing luminosity (Narayan 2005). As the accretion rate increases, the luminosity increases in all bands, until they reach a transition or intermediate phase where they undergo a short-lived but strong radio outburst in which both a thermal accretion disk and powerful and highly relativistic radio jets are seen (e.g. Fender et al. 2004). The radio emission then ceases as the source moves into the high-soft state. A further important property of X-ray binaries is that winds and jets appear to anti-correlate (Miller et al. 2008, Neilsen & Lee 2009, Ponti et al. 2012): winds occur in the high-soft state when jets are not observed, but are not observed in the low-hard state where jets are ubiquitous.

These states of X-ray binary activity each have an analog amongst the AGN population. The low-hard state X-ray binaries are analogs of the jet-mode radiatively-inefficient AGN. Indeed these AGN and low/hard X-ray binaries fall on the same fundamental plane of black hole accretion: a relationship between the radio luminosity, X-ray luminosity and black-hole mass of black holes (Merloni et al. 2003, Falcke et al. 2004). The high-soft state X-ray binaries are a direct analog of the radiative-mode AGN (Seyferts and QSOs). The transition-phase objects have properties that make them a broad analog of the radio-loud radiative-mode AGN, although in AGN there is no observational evidence for these sources being a transition phase that pre-empts radio-quiet radiative-mode activity.

The critical accretion rate for the switch between X-ray binary states (a few percent of the Eddington rate) also appears to be broadly comparable in AGN. As shown in Section 4.2 (left panel of Fig. 12) the emission-line AGN (predominantly Seyferts) in gas-rich (star-forming) galaxies in SDSS show a log-normal distribution of Eddington rates peaking at a few percent of Eddington. This result is also confirmed at higher redshifts with QSOs seen to have lower limits to their accretion rates at around 1% of Eddington (e.g. Kollmeier et al. 2006, Trump et al. 2009). Radiative-mode (Seyfert/QSO-like) radio-AGN show a similar Eddington ratio distribution (Best & Heckman 2012; see Section 3.2 and right panel of Fig. 12). In contrast to this, the jet-mode radio-AGN have accretion rates distributed below a few percent of Eddington (Best & Heckman 2012; see Section 3.2). If powered by the Blandford & Znajek mechanism then these accretion rates

would be lower still. This last result is also supported at higher redshift, since BL Lac objects (believed to be beamed versions of the jet-mode sources) are also found to have luminosities below about 1% of Eddington, while Russell et al. (2013a) find a transition from jet-mode to radiative-mode AGN at a similar Eddington ratio amongst brightest cluster galaxies (see also Churazov et al. 2005, Merloni & Heinz 2007).

As in the case of X-ray binaries, the spectra of the AGN subclass of LINERs (jet-mode AGN) are best explained if the inner ADAF is supplemented by a truncated thin disk at larger radii, with the transition between the two being dependent upon the Eddington-scaled accretion rate (Yuan & Narayan 2004, Ho 2005). Sadler et al. (2013) found a weak signature of mid-IR AGN emission at the highest radio luminosities in jet-mode radio-AGN, supporting this idea.

All of these results are in line with theoretical predictions of advection-dominated flows, which predict a change in the nature of the inner accretion flow below a critical fraction of the Eddington rate (e.g. see the review by Narayan 2002, or by Yuan & Narayan in this volume), with the precise value of that fraction depending strongly upon the viscosity of the accretion disk (e.g. Mahadevan 1997, Qiao & Liu 2009). This is consistent with the picture we have advocated in this review: the high Eddington-rate (radiative-mode) AGN, and the low-Eddington rate (jet-mode) are two fundamentally distinct populations. We include the small population of radio-loud radiative-mode AGN together with the (radio-quiet) rest of the radiative-mode population: the results in the previous sections have shown that their host galaxy properties and Eddington-scaled accretion rates are broadly similar, albeit that the radio-loud QSOs are predominantly located at the upper end of the range of stellar and black hole masses seen in the radio-quiet population (see Fig. 4).

5.2. The Fueling of Radiative-Mode AGN

5.2.1. Mergers and Interactions

The idea that AGN are largely triggered through the process of galaxy mergers or strong tidal interactions has long been a key component of most theoretical models (e.g. Kauffmann & Haehnelt 2000, Hopkins et al. 2006, 2008). Nevertheless, it has proven difficult to establish this idea observationally, with many claims and counter-claims in the literature. As we will explain below, this is a clear case in which arriving at the correct answer requires a superb control of the systematics, and this is made possible by a very large and homogeneous data set like that provided by the SDSS. We consider two types of observational tests for a link between interactions/merger and AGN fueling. The first is to measure the incidence of close companion galaxies and the second is to determine the morphological structure of the host galaxy.

The amplitude of the cross-correlation function on scales less than $\sim 100\,\mathrm{kpc}$ probes interacting pairs of galaxies where tidal forces begin to influence the internal structure of the pair. In two companion papers, Li et al. (2008a,b) used the amplitude of the cross-correlation function on scales of tens of kpc as a probe of the effects of galaxy interactions on star formation and AGN activity in galaxies. They first showed that on scales less than 100 kpc, the amplitude of the cross-correlation function exhibits a strong dependence on the sSFR of the galaxy, reflecting the well-known result that galaxy interactions and mergers trigger star-bursts in galaxies (Larson & Tinsley 1978). As the separation between the two galaxies in the pair decreased, their sSFR also increased relative to the mean value for field galaxies of the same mass. In a follow-up paper, Li et al. applied the same techniques to active galactic nuclei (AGN) in the survey, showing that interactions do not lead to enhancement of nuclear activity over and above that expected as a result of the boost in the central star formation rates. In other words, the relation between central star formation and AGN activity



Fig. 19.— The relationship between $L_{[\mathrm{OIII}]}/M_{\mathrm{BH}}$, D4000, and galaxy lopsidedness (A_1^i). The color coding of these two-dimensional histograms indicates the median $L_{[\mathrm{OIII}]}/M_{\mathrm{BH}}$. The primary correlation is between stellar age and $L_{[\mathrm{OIII}]}/M_{\mathrm{BH}}$, as is apparent from the horizontal nature of the color contours. There is no independent correlation between $L_{[\mathrm{OIII}]}/M_{\mathrm{BH}}$ and lopsidedness in these data. Figure from Reichard et al. (2009).

in interacting galaxies is no different from that observed for non-interacting galaxies.

Mergers can be identified quantitatively through measures of the global asymmetry (lopsidedness) of the light distribution of the galaxy (e.g. Conselice et al. 2000). An analysis of the SDSS population of normal and AGN-host galaxies by Wild et al. (2007) showed that the majority of black hole growth in the contemporary universe occurs in galaxies with relatively quiescent recent star formation histories that have not experienced recent mergers or strong interactions. In subsequent work, Reichard et al. (2009) followed up on the Li et al. analysis by showing that AGN activity is not enhanced in lopsided galaxies, compared to symmetric galaxies of the same central star formation rate. They found that even among AGN radiating near the Eddington limit, only a small minority exhibited the highly lopsided morphologies of a major merger.

There are many papers reaching seemingly contrary conclusions, of which some recent examples are Koss et al. (2011, 2012), Alonso et al. (2007), Ellison et al. (2011), Hwang et al. (2012), Liu et al. (2012), and Sabater et al. (2013). We stress that these results are actually not at odds with the results above. As Reichard et al. (2009) showed explicitly, the hosts of strong AGN are in fact more lopsided on-average than normal galaxies with the same stellar mass, radius, and concentration. However they showed that this link is a secondary unphysical one induced by much stronger correlations between lopsidedness and central star formation and between central star formation and the presence of a strong AGN (Fig. 19). They interpreted this as implying that the fueling of the SMBH is enhanced by the presence of circum-nuclear star-formation (and its associated cold gas), but this SMBH fueling process does not depend upon the way in which this central star-formation arises.

In summary, contrary to the assumption of many theoretical models, most of the AGN activity in the contemporary universe appears to occur without the need for major mergers or strong tidal interactions. All that is required is an abundant supply of cold, dense gas in the central regions of the galaxy (regardless of its origin).

5.2.2. Fueling via Secular Evolution

The radial transport of gas inward in a disk galaxy requires torque on the gas that allows angular momentum to be transferred from the gas to the stars or dark matter. While this can be accomplished in a sudden and spectacular way in a major merger or strong tidal interaction, a slower but significant inflow can be driven by non-axisymmetric perturbations in the underlying mass distribution that arise through internal dynamical processes in the disk. Examples of such non-axisymmetric perturbations are bars, oval distortions, and even spiral arms (e.g. Athanassoula 2008, Kormendy & Kennicutt 2004, Sellwood 2014).

Kormendy & Kennicutt (2004) argued that the consequence of this secular evolution for the inner regions of disk galaxies is the creation of a pseudo-bulge (perhaps more descriptively called a disky bulge by Athanassoula 2005, 2008). These are defined observationally as central regions of enhanced surface brightness relative to an inward extrapolation of the radial surface brightness profile of the galaxy disk. Unlike classical bulges, they are dynamically-cold structures as revealed by the presence of spiral arms, rings and bars. Unlike typical classical bulges, they are the sites of significant on-going star-formation (e.g. Gadotti 2009). They have exponentially-declining radial surface-brightness profiles whose functional form is more similar to a classic exponential Freeman disk than the $r^{1/4}$ de Vaucouleurs law for elliptical galaxies. The boundary between classical and pseudo-bulges is typically set at a value for the Sersic index of $n \sim 2$ for the bulge component (e.g. Gadotti 2009, Kormendy & Kennicutt 2004, Athanassoula 2008, Fisher & Drory 2011).

If the growth of SMBH in the contemporary universe is largely fueled by secular processes that transport gas inward, we would therefore expect rapidly growing SMBHs to be found primarily in pseudo-bulges. We have summarized above the general link between the presence of a young central stellar population (one of the defining characteristics of a pseudo-bulge) and the rapid growth of the SMBH. Moreover, Figure 17 in Kormendy & Ho (2013) shows that the transition from classical- to pseudo-bulges occurs below a bulge velocity dispersion $\sigma \sim 150$ km s^{-1}, and below a SMBH mass $M_{\rm BH} \sim$ few $\times 10^7$ M$_\odot$ (cf Fig. 9; and see also Fisher & Drory 2011). This is just the regime where SDSS shows the bulk of SMBH growth to be occurring today (Heckman et al. 2004, Kauffmann & Heckman 2009).

Is there other more direct evidence that growing SBMHs are preferentially found in pseudo-bulges? Intriguingly, the compilation of SMBHs in Kormendy & Ho (2013) shows that Seyfert nuclei are present in only 1 of the 45 cases classified as an elliptical galaxy (the powerful radio source Cygnus A), in only 1 of the 20 cases classified as classical bulges (NGC4258), but in 11 of the 22 cases classified as pseudo-bulges. The preference of Seyfert nuclei for pseudo-bulges is confirmed by the HST imaging survey of nearby active galaxies by Malkan et al. (1998). Simple visual inspection of these images shows that spiral arms, rings, dust-lanes, and bars are present in the majority of the AGN hosts on radial scales of-order a kpc or less from the nucleus (see Fig. 20). Malkan et al. assigned an inner-Hubble-type for each galaxy based on these images, and only 20 of the 107 (19%) of the Type 2 Seyferts had inner Hubble types of E or S0 as expected for a classical bulge. Jiang et al. (2011) reached similar conclusions for an SDSS sample of Type 1 AGN associated with black holes with estimated masses below 10^6 M$_\odot$.

If AGN are typically fueled via secular processes, one might naturally expect that they would be preferentially found in barred galaxies (since bars are one of the major mechanisms for driving radial gas flows; e.g. Shlosman et al. 1990). As in the case of establishing a link between interactions and AGN, there have been many studies over the years that have reached contradictory conclusions on this matter. The most recent studies based on SDSS do not show evidence for a link once a proper control sample has been identified (Lee et al. 2012, Cisternas et al. 2013; and references therein). Finally we note that there are rare cases of AGN in galaxies without any detectable bulge at all (Filippenko et al. 1993, Satyapal et al. 2009, Simmons et al.



Fig. 20.— HST optical images of the central regions of four typical Type 2 Seyfert galaxies from Malkan et al. (1998). The arrowhead points North and the bar points East, and the angular scale is indicated. Note that the linear scale (pc per arcsec) quoted in each case assumed $H_0 = 50\ \mathrm{km\,s^{-1}Mpc^{-1}}$. In all these examples the central few-kpc-scale region shows the spiral arms and dust lanes typical of pseudo-bulges.

2013). The fueling mechanism for these systems is mysterious.

5.3. Fueling of Jet-Mode AGN

The idea that supermassive black holes can be fed through the accretion of gas shed by evolved stars in the central region of the galaxy is an old one (e.g. Bailey 1980, David et al. 1987, Norman & Scoville 1988, Ciotti & Ostriker 1997).

As discussed in Section 4.2, Kauffmann & Heckman (2009) found evidence for two distinct regimes of black hole growth in nearby galaxies. We highlight here the regime in which the Eddington ratio distribution

is a steep power-law. This regime dominates for the more massive black holes living in the older bulges and typically accreting at the low Eddington rates associated with jet-mode AGN (see Fig. 12). For this population, Kauffmann & Heckman found that at fixed 4000Å break strength (broadly, fixed mean stellar age), the time-averaged accretion rate on to the black hole scales in proportion with the stellar mass of the galaxy bulge, and the overall rate is higher in galaxies with younger mean stellar ages. They argued that this is consistent with the black hole being fueled from the recycled hot gas arising from stellar mass loss.

In fact, hot gas has been widely argued to be the fueling source of the jet-mode radio-AGN (e.g. Hardcastle et al. 2007). These radio-AGN are found predominantly in massive galaxies, often at the centers of groups and clusters, with associated hot gaseous X-ray emitting haloes. These hot gas halos offer not only a potential source of fueling gas for the radio-AGN, but also a confining medium for the radio source to expand against and a depository for the bulk kinetic energy emitted in the radio jet: this allows for the possibility of the radio-AGN feedback cycle that is broadly supported by both observations and galaxy formation models (as we will discuss in Section 6; see also the reviews by Cattaneo et al. 2009 and Fabian 2012).

The rate at which hot gas accretes on a black hole was first calculated by Bondi (1952) for a spherically symmetrical geometry with negligible angular momentum or magnetic fields. The Bondi accretion rate from a gas cloud of uniform density (ρ) and pressure is $\dot{M}_{\rm B} = 4\pi\lambda(GM_{\rm BH})^2\rho/c_s^3$, where λ is an order-unity scaling factor and c_s is the sound speed. In reality, the gas density around a black hole is far from uniform, but the Bondi formula remains approximately correct if ρ and c_s are calculated at the Bondi radius (the radius within which the gravitational potential energy of the black hole dominates over the thermal energy of the surrounding gas). Allen et al. (2006) showed that for a sample of 9 nearby systems, a strong correlation exists between the calculated Bondi accretion rate and the jet mechanical energy estimated from the cavities inflated in the surrounding gas. Both the slope and normalization of the relation were found to be close to unity, indicating that simple Bondi accretion of hot gas could be powering these objects.

More recently, however, Russell et al. (2013a) have found a much weaker correlation between Bondi accretion rates and jet powers. Furthermore, for the most luminous radio sources, Bondi accretion rate estimates fall more than two orders of magnitude short of providing the required jet powers (e.g. Cao & Rawlings 2004, McNamara et al. 2011). To produce such powerful sources with direct Bondi accretion would require the black hole masses to be far higher than currently estimated (requiring black hole masses significantly above 10^{10} $M_\odot$). Such large black hole masses would, however, help to explain how the nuclei of these powerful objects can be radiatively inefficient (i.e. below $\sim 1\%$ Eddington; see Hlavacek-Larrondo & Fabian 2011).

A more plausible alternative to direct Bondi accretion of hot gas, is that the gas cools out of the hot phase prior to accretion. The most powerful jet-mode radio sources are invariably located in dense galaxy groups or clusters, frequently with strong cooling flows. Hydrodynamic simulations (most recently by Gaspari et al. 2013) including gas cooling, turbulence and feedback from AGN heating, reveal that when the hot gas is cooling then accretion on to the black hole occurs predominantly in a cold and chaotic manner. Cold clouds and filaments form out of the cooling gas in the simulations, decouple from the hot gas, and enter a quasi free-fall regime. Multiple cloud-cloud collisions reduce the angular momentum of the cold gas, and lead to stochastic accretion at rates which can be two orders of magnitude higher than the Bondi rate. This is sufficient to produce the observed jet powers of even the most luminous jet-mode sources. Hillel & Soker (2013) suggest that accretion of cooled gas may also dominate over direct Bondi accretion in less extreme systems as well: they argue that even the stellar winds of stars in orbit near the central supermassive black hole would violate the zero-pressure assumption of the Bondi formulism, and that the cooling shocked gas

from such winds would probably accrete in cold clumps.

Observationally, cool clouds and filaments are almost universally observed in galaxies, groups and clusters with cooling times significantly below the Hubble time, but not in systems with higher gas entropy (e.g. Hu et al. 1985, Cavagnolo et al. 2008). As extensively reviewed by Fabian (2012), the cooled material is predominantly cold molecular gas, which can extend tens of kpc around the brightest cluster galaxy. This is in good agreement with the numerical simulations. The observed masses of cooled molecular gas are comfortably high enough to provide sufficient accretion energy to fuel the inflated cavities (e.g. McNamara et al. 2011); in many objects they are two or more orders of magnitude higher, indicating that the bulk of the cooled molecular gas does not feed the black hole, but rather fuels star formation activity, which can also be seen in these systems (e.g. Rafferty et al. 2006, O'Dea et al. 2008).

McNamara et al. (2011) show that the mass of cooled molecular gas does not correlate well with the radio jet power. This implies that either the efficiency with which the cooled gas gets funneled down to the black hole must vary greatly (which is at least plausible, given that only a small fraction of the gas reaches the black hole), or that another factor as well as accretion rate is important in determining the jet power. An obvious 'hidden factor' is black hole spin. Blandford & Znajek (1977) showed that when material accretes onto rapidly rotating black holes threaded by high-power magnetic fields, the spin energy of the black hole can additionally be extracted. Even if the Blandford-Znajek mechanism does not operate, the jet power can still be a strong function of the black hole spin, because frame-dragging from the black hole's rotation can contribute to the twisting of the magnetic field lines, amplifying any outflow generated by the Blandford-Payne model (Blandford & Payne 1982; see also Punsly & Coroniti 1990, Meier 1999).

Black hole spin has been widely cited as a possible explanation for the wide range of radio-loudness observed in the QSO population (the so-called spin-paradigm of Wilson & Colbert 1995). According to current models, rapidly-spinning black holes are required in order to produce sufficient jet power to account for the most radio luminous sources (e.g. Meier 2001, Nemmen et al. 2007). Using these models, it is possible to reproduce both the QSO radio loudness distribution and the SDSS-derived local radio luminosity functions of both jet-mode and radiative-mode radio sources (Martínez-Sansigre & Rawlings 2011). This requires a bimodal distribution of black hole spins, with black holes being either close to maximally-spinning or with very low spin parameters. Nevertheless, despite the success of these models, the role of black hole spin in powering radio jets remains unproven. Even at the scale of X-ray binaries, there is ongoing debate in the literature as to whether the power of the radio jet produced depends upon the spin of the black hole (e.g. Russell et al. 2013b, Steiner et al. 2013).

In conclusion, evidence is strong that a majority of low Eddington fraction AGN are fueled directly or indirectly from hot gas. The accretion flows are radiatively inefficient, and a significant fraction of the energetic output occurs through jet outflows, the strength of which may be enhanced by rapidly spinning black holes. For many galaxies, the fueling hot gas arises from recycled material from stellar mass loss. In more massive systems (the most massive ellipticals, and galaxies at the centers of groups and clusters) extended hot gas halos provide a more abundant gas source, and large-scale cooling flows can greatly enhance the accretion rate. In such systems the extended hot gas halo also provides a working surface for a jet, and a medium to confine the expanding radio lobes, minimizing adiabatic losses and leading to luminous radio emission. The hot halo also acts as a repository for the radio jet energy, offering the ideal conditions for a radio-AGN feedback cycle (see Section 6).

6. FEEDBACK PROCESSES

As recently reviewed by Cattaneo et al. (2009) and in this journal by Fabian (2012), feedback from AGN is currently invoked in both semi-analytic models and numerical simulations in order to successfully reproduce the observed properties of massive galaxies (e.g. Di Matteo et al. 2005, Springel et al. 2005, Bower et al. 2006, Croton et al. 2006, Hopkins et al. 2006, Ciotti et al. 2010). While AGN feedback is generally assumed to be negative (inhibiting star-formation and/or black hole growth), it could also be positive in nature (e.g. Ishibashi & Fabian 2012, Silk 2013, Zinn et al. 2013). Feedback from AGN is generally invoked in two flavors, which relate to the two fundamental modes of AGN activity. The first is a mode of powerful AGN-driven winds that are postulated to occur in galaxies with actively growing black holes and is argued to be responsible for the termination of star-formation and the migration of the galaxy from the blue star-forming main sequence to the red sequence. It may also be responsible for setting up the correlation between black hole mass and bulge properties (see review by Kormendy & Ho 2013). We discuss this in Section 6.1. Complementary to this is the requirement to keep the galaxies as red and dead once they have arrived at the red sequence, by preventing further gas cooling. Recurrent low-luminosity radio-AGN activity is often posited to be responsible for this kinetic mode of feedback, which is often referred to as maintenance-mode or radio-mode feedback. We examine this in Section 6.2

6.1. Feedback and Radiative-Mode AGN

We have reviewed above the evidence that the growth of supermassive black holes is related to the formation of massive stars in the central (few-kpc-scale) region of the host galaxy. Thus, we will first summarize the evidence for feedback associated with short-lived massive stars and then the evidence for feedback from the black hole itself.

6.1.1. Feedback from Massive Stars

Could the feedback provided by massive stars formed in the central region of the host galaxy affect the fueling of the black hole or the evolution of the host galaxy? To set the scale, note that for a normal Kroupa/Chabrier stellar IMF, massive stars return about 1.4×10^{49} ergs in kinetic energy per solar mass of star formation (based on Starburst 99; Leitherer et al. 1999). This amount of kinetic energy per unit mass is equivalent to a characteristic velocity of about 1200 km/s (far larger than the galaxy escape velocity). Provided that this energy can be efficiently coupled to the surrounding gas, it could indeed result in significant feedback.

There is certainly compelling evidence that this can occur. The most dramatic effect is the production of galactic winds that can be traced in emission and absorption in both the local (e.g. Heckman et al. 1990) and high-redshift (e.g. Steidel et al. 2010, Shapley 2011) universe. These outflows are driven by the energy and/or momentum supplied by massive stars through their stellar winds, their supernova ejecta, and their radiation (e.g. Chevalier & Clegg 1985, Murray et al. 2011). While there are detailed multi-waveband studies of relatively small samples of local galactic winds (see the review by Veilleux et al. 2005), the largest census of galactic winds in the local universe was undertaken by Chen et al. (2010) based on using SDSS galaxy spectra to measure the interstellar absorption feature produced by neutral Na atoms that trace the outflow. Their work provided statistically robust evidence that local galactic winds are wide-angle bipolar flows along the galaxy minor axis and are associated with galaxies with high star-formation rates per unit area (cf.



Fig. 21.— Illustrative examples of feedback effects at work. The upper-left panel shows the 'Great Observatories' composite image of the starburst-driven galactic wind in M82: visible light is shown in yellow-green, infrared emission in red, Hα emission in orange and X-ray emission in blue (Credit: NASA/JPL-Caltech/STScI/CXC/UofA/). The upper-right panel shows jet-mode feedback in the Perseus cluster (data from Fabian et al. 2006). The color-scaling shows the X-ray emission, colored such that hard X-rays are in blue and soft X-rays in red. The contours indicate the radio emission, which can be seen to have evacuated cavities in the X-ray gas. The three lower panels illustrate AGN-driven feedback from a high luminosity radiative-mode AGN (reproduced from Liu et al. 2013b). They show, respectively, the surface brightness (in units of 10^{-14}erg s^{-1}cm^{-2}arcsec^{-2}), relative velocity (in km s^{-1}), and velocity width (W80 is the velocity width in km s^{-1} containing 80% of the emitted line flux) of the [OIII] emission line in the Type 2 QSO SDSS J0319-0019.

Fig. 21).

Investigations of starburst-driven outflows in the local universe have only been able to directly detect the flows out to radii of-order ten kpc (e.g. Grimes et al. 2005). However, recent work using absorption-line spectra of background QSOs shows that the wind affects the properties of the surrounding gaseous halo of a starburst galaxy all the way out to the galaxy's virial radius (Borthakur et al. 2013). This is consistent

with similar observations of Lyman Break Galaxies at z $\sim$ 3 (Steidel et al. 2010). While global feedback from massive stars clearly exists, the evidence that it limits the growth of black holes is only indirect so far. We have described above the result from Wild et al. (2010) that showed that in a large SDSS-derived sample of starburst and post-starburst galaxies, the growth of the supermassive black hole was delayed by about 200 Myr relative to the onset of the starburst. Wild et al. showed that the turn-on in black hole fueling in these galaxies occurred at the time at which the primary source of mass-loss from stars in the galaxy's central region switched from supernovae (with ejecta velocities far above the local escape velocity) to intermediate-mass AGB stars (with ejecta velocities far below the local escape velocity). On this basis they speculated that supernova feedback was preventing or inhibiting the accretion of gas by the black hole (Fig. 18). This idea had been previously suggested both theoretically (Norman & Scoville 1988) and based on detailed studies of small samples of local AGN (Davies et al. 2007).

It is also possible that feedback from massive stars is responsible for the saturation effect found by Kauffmann & Heckman (2009): once the specific star-formation rate in the bulge exceeds a value of $\sim 10^{-10}$ yr^{-1} the distribution of the Eddington ratio for the black hole assumes a universal log-normal form that does not change at still higher star formation rates. While higher star-formation rates are associated with a larger gas supply, they are also associated with higher levels of feedback. Kauffmann & Heckman (2009) presented an alternative interpretation: the saturation effect could be understood if the black hole regulated its own growth at a fixed average rate of a few percent of the Eddington limit when its fuel supply was plentiful. In a subsequent paper, Hopkins & Hernquist (2009) compared their observational results with their models for self-regulated BH growth, in which feedback produces a self-regulating phase after the AGN reaches some peak luminosity/BH mass and begins to expel gas and shut down accretion, and found good agreement at the bright end. On that note, we now describe the direct observational evidence for black-hole-driven feedback in radio-quiet local AGN.

6.1.2. Feedback from the Black Holes in Radiative-Mode AGN

As reviewed by Fabian (2012) there is ample direct evidence that radio-quiet AGN drive outflows. This is primarily based on the frequent presence of blue-shifted absorption-lines in the optical, ultraviolet, and soft X-ray spectra of Type 1 AGN (see Crenshaw et al. 2003 and references therein). These trace highly ionized gas with outflow velocities ranging from several hundred to several thousand km s^{-1} in low-luminosity AGN (Type 1 Seyfert nuclei) to tens-of-thousands of km/s in powerful QSOs (the Broad-Absorption-Line systems).

The uncertainty in the feedback effect of these flows arises due to the difficulty in measuring their basic physical properties. Simple arguments imply that the mass (energy) outflow rate will be proportional to the product of the outflow's total column density times its size times its solid angle times its velocity (cubed). The strong absorption-lines measured in the AGN-driven outflows are almost certainly saturated, making it difficult to determine even the ionic column density (let alone a total gas column density). Moreover, the sizes of these outflows have been largely unconstrained. The lack of the detection of such high-velocity outflows in the spectra of typical Type 2 Seyferts (e.g. Krug et al. 2010) is evidence that either the flows in Seyferts do not extend beyond the central few tens of parsec or that their column densities drop below detectable values on these larger radial scales. It is therefore not surprising that the spectroscopic data in SDSS on a vast number of local Type 2 AGN has not uncovered any direct evidence that they are driving large-scale outflows that cannot be attributed to the feedback from central star-formation described in Section 6.1.1 above.

Another line of evidence for outflows in typical radio-quiet AGN comes from mapping the physical and dynamical state of the ionized gas seen in the narrow emission-line region. This has been reviewed by Veilleux et al. (2005) in this journal and we refer the reader there for details. In a number of local Seyfert galaxies the ionized gas on a scale of $\sim$ a kpc from the AGN is clearly being impacted by the collimated outflows (radio jets), which are commonly present even in radio-quiet Seyferts (e.g. Wilson & Heckman 1985, Rosario et al. 2010a,b). It is difficult to accurately estimate the total outflow rates in these cases, but the kinetic energy flux appears to be a small fraction of the AGN bolometric luminosity in typical local Seyfert galaxies (see Veilleux et al. 2005 and references therein).

While direct evidence for black-hole-driven feedback in typical local AGN is lacking, recently there have been several exciting discoveries that imply that the most luminous AGN can indeed drive highly energetic outflows that could have a significant impact on both the fueling of the black hole and the evolution of the host galaxy. These are AGN with bolometric luminosities well above the knee in the local AGN luminosity function ($L_* \sim 10^{45}$ erg/s $\sim 10^{11.5}$ $L_\odot$). As such they are rare and only rather small samples have been studied so far.

The first such discovery is the prevalence of outflows of molecular gas in Ultra-Luminous Infrared Galaxies (ULIRGs) with AGN bolometric luminosities above about 3×10^{45} erg/s. This evidence is of two types. First, the PACS instrument on Herschel has been used to observe the far-IR emission and absorption features due to the OH molecule. Initial results were presented in Fischer et al. (2010) and Sturm et al. (2011). Most recently, Veilleux et al. (2013) and Spoon et al. (2013) have summarized observations of an expanded sample of ULIRGs and QSOs at $z < 0.3$. For each object, the fractions of the bolometric luminosity due to a starburst and AGN were determined following the analysis of Veilleux et al. (2009). The OH feature is detected in absorption in most objects, with the majority of these showing evidence for molecular outflows in the form of blue-shifted OH absorption lines. The equivalent widths of the OH absorption features (tracing the column density) do not depend upon the AGN luminosity or the ratio of the AGN/starburst luminosities. The outflow velocities do not depend upon the starburst luminosity but they do increase with both increasing AGN luminosity and AGN/starburst luminosity ratio. Characterizing the outflow speed by the midpoint in the line profiles yields outflow speeds of-order 100 km/s in the starburst-dominated systems and about 400 km/s in the AGN-dominated cases, but the most rapidly outflowing gas can reach speeds of-order 10^3 km/s. As noted above, deriving an outflow rate requires determination of a size for the flow. Sturm et al. (2011) have used a radiative-transfer code (Gonzalez-Alfonso et al. 2013) applied to the observed far-IR spectrum to estimate the size scales, and hence the outflow rates in five ULIRGs. For an assumed OH/H_2 ratio, the implied outflow rates range from 10^2 to 10^3 $M_\odot$ year^{-1} (comparable to, or larger than, the SFR).

Complementing these probes are measurements of molecular gas in emission in the mm-wave regime. The molecular outflow in the proto-typical AGN-dominated ULIRG Mrk 231 has been mapped in CO (Feruglio et al. 2010, Cicone et al. 2012) and HCO+, HCN, and HNC (Aalto et al. 2012) using the Plateau de Bure mm-wave interferometer. The flow is spatially-resolved with outflow speeds of up to 800 km/s detectable over a kpc-scale region and an estimated outflow rate of about 700 $M_\odot$ year^{-1}, in broad agreement with the estimates based on the OH absorption line seen with Herschel. Similar results using CO emission as a tracer have now been found for a small sample of other AGN-dominated ULIRGs (Cicone et al. 2013). They find that the kinetic energy in the molecular outflow is a few percent of the AGN bolometric luminosity and that the momentum flux is about 20 times larger than $L_{\rm bol}/c$. The primary uncertainty affecting these estimates is the conversion factor used to convert the CO luminosity into an H_2 mass.

These outflow rates are impressive, but the flows can only be traced out to modest radii (kpc-scale). Recently, the effects of AGN outflows on the global properties of the host galaxy have been discovered in

samples of Type 2 QSOs – obscured AGN with bolometric luminosities in excess of 10^{46} erg s^{-1} (Zakamska et al. 2004). Greene et al. (2011) reported on the analysis of long-slit optical spectroscopy probing the kinetics of the ionized gas surrounding 15 Type 2 QSOs at z $\sim$ 0.1 to 0.45. They found broad emission-lines of [OIII]5007 (full width at 20% of the maximum line intensity of $\sim$ 500 to 1500 km s^{-1}) that extended across the entire extent of the galaxy (radii of-order 10 kpc). More recently Liu et al. (2013a,b) used the Gemini integral field unit to fully map out the 2-D distribution [OIII] and Hβ emission-lines around a sample of 11 radio-quiet Type 2 QSOs at z $\sim$ 0.3 to 0.65 with typical bolometric luminosities of 10^{47} erg/s. They obtain similar results to Greene et al. (2011) but their complete spatial coverage enables them to better characterize the structure and kinematics (e.g. Fig. 21). They find that a simple model of a spherically symmetric outflow at a velocity of 500 to 1000 km s^{-1} reproduces the data. The estimated outflow rates are uncertain because the density (and hence the mass) of the emitting material is not directly measured. It appears that the entire interstellar medium of the galaxy could be expelled over a timescale of only a few tens-of-Myr implying a kinetic energy flow of-order 2% of the bolometric luminosity (similar to the estimates in the molecular outflows described above).

In summary, there is now some persuasive evidence that the most powerful radiative-mode AGN in the contemporary universe can drive outflows capable of severely impacting their host galaxies. Evidence for global outflows in typical low-redshift radiative-mode AGN is lacking.

6.2. Feedback from radio sources

As discussed in Section 5.3, radio-AGN can be fueled from their surrounding hot gaseous haloes, either directly through the Bondi process, or via gas which has cooled out of the hot phase in a cooling flow. The bulk of the energy generated from the accretion is channelled into the powerful radio jets, which drive their way outwards. The radio jets are confined by the hot halo gas, and produce expanding radio lobes filled with relativistic plasma, inflating bubbles or cavities in the hot gas. The bulk of the jet energy is deposited locally, through the mechanical work required to inflate these cavities. Since the repository of the AGN energy is the same gas as that which fuels the AGN, this offers the necessary conditions for a self-regulating AGN feedback cycle.

The most extreme examples of radio-AGN feedback occur in the massive galaxies at the centers of groups and clusters (see Fig. 21). In these systems the radiative cooling time of the surrounding gas can be substantially shorter than the Hubble time. In the absence of a heating source, a cooling flow would be expected to develop, whereby the temperature in the central regions of the cluster drops and gas flows inwards at rates of hundreds or even thousands of solar masses per year (see review by Fabian 1994). In reality, however, observations show that the gas temperatures in the cluster cores are at most a factor 3 below the value at large radii, and the amount of cooling gas is only about 10% of the cooling flow prediction (e.g. Peterson et al. 2001, 2003, David et al. 2001, Tamura et al. 2001).

A heating source must be balancing the radiative cooling losses to prevent the gas from cooling further, and this reduces the star-formation rates in the central galaxy by an order of magnitude (though not to zero – these galaxies can still have star-formation rates of tens of solar masses per year; e.g. O'Dea et al. 2008). The heating source is almost certainly the jet outflows from central black hole: the prevalence of radio-AGN activity is high (>70%) in central cluster galaxies (Burns 1990), and results from SDSS show that it is enhanced relative to other galaxies of the same mass (Best et al. 2007). Bubbles and cavities in the X-ray gas are also seen in a high percentage of clusters, reaching nearly 100% in those clusters with cooling

times below 3 Gyr (Dunn & Fabian 2006, Fabian 2012). As discussed in Section 2.3.2, the mechanical energy flow rates of the radio jets are calculable either from the observed synchrotron emission or from the pV work required to inflate the radio lobes. Analysis of these cooling clusters indicates that the energy input from the radio jets is in rough balance with the energy losses from radiative cooling within the cooling radius (see review by McNamara & Nulsen, 2007).

For feedback processes to be efficient, it is not only the total available energy that is important, but also how and where that energy is deposited. Radio jets are highly anisotropic structures, but gas cooling and inflow needs to be switched off in all directions. It is the expanding radio bubbles, rather than direct jet interactions, which must provide the bulk of the energy transfer to the ambient medium. This process is observed in the form of weak shocks or sound waves surrounding some radio bubbles, with the most striking example being the Perseus cluster where several concentric ripples in X-ray pressure are seen (Fabian et al. 2003, 2006). These ripples have been associated with repeated episodes of bubble-blowing activity from the central AGN. The energy in the sound waves or weak shocks is gradually dissipated over length scales of ∼100 kpc (depending upon the gas viscosity). This gentle feedback process is able to transfer the radio jet energy into its environment in a largely isotropic manner, without disturbing the intracluster medium to such an extent that the observed temperature and metal abundance gradients would be destroyed by mixing.

The radio-AGN activity appears to be switched on nearly all of the time in cooling flow clusters, and must be able adapt quickly to changes in its environment in order to maintain the close heating-cooling balance. This quick adaption is not possible for standard Bondi accretion, since the infall time of the hot gas from kpc-scales down to the black hole is more than a Gyr (Soker 2006). However, cold clump accretion occurs on a much faster timescale, especially in a viscous accretion flow, and therefore allows the black hole to react quickly to changes in the the state of its environment (Pizzolato & Soker 2010, Gaspari et al. 2013). This allows for efficient self-regulation of the feedback process.

Although brightest cluster galaxies offer the most striking examples of radio-AGN feedback, which can be individually studied in detail, these massive cooling-flow clusters are relatively rare. The data from large sky surveys have been invaluable in extending analysis to less extreme systems and providing a direct statistical comparison of radio-AGN feedback in systems of different scales. Best et al. (2006) investigated the role of radio-AGN feedback in elliptical galaxies using data from SDSS. On the assumption that all massive galaxies would go through recurrent short-lived radio-AGN outbursts, they considered the observed prevalence of powerful ($P_{1.4\mathrm{GHz}} > 10^{23}\mathrm{W\,Hz^{-1}}$) radio-loud AGN as a function of black hole mass and interpreted this as a measure of the duty cycle of powerful radio-AGN activity for galaxies of that black hole mass. They combined this with the black hole mass dependent radio luminosity function to estimate, probabilistically, the fraction of its time that a black hole of given mass would spend producing a radio source of a given radio luminosity. Using the radio luminosity to jet kinetic power conversion (Section 2.3.2) this then allowed a calculation of the average rate of jet kinetic energy production of the black hole. Note that most of the heating is produced by radio sources of $P_{1.4\mathrm{GHz}} \sim 10^{24}$–$10^{25}\mathrm{W\,Hz^{-1}}$. The heating contribution from periods of very low radio luminosity, where in this simple picture the radio AGN is considered to be 'off', can be neglected. Best et al. derived the heating rate for galaxies of different black hole mass, and compared these results with the X-ray luminosities (ie., cooling rates) of the hot haloes around the galaxies. They found that for elliptical galaxies of all masses, the radio-AGN heating rate provided a good balance to the gas cooling rate. AGN heating is therefore able to counter-balance cooling and thus explain the old, red and dead nature of the ellipticals.

The Best et al. (2006) analysis actually underestimated the jet-energy production rate, as they adopted only pV instead of $4pV$ for the cavity energies. Also, for gas cooling rates, they scaled from the total X-ray

luminosity, rather than considering only the luminosity within the cooling radius (which is the only region where cooling needs to be compensated in order to avoid catastrophic cooling collapse). Therefore, the radio-AGN provide, in a time-averaged sense, significantly more energy than is required to suppress cooling on galaxy scales. This was shown more clearly by Best et al. (2007) who compared the time-averaged AGN-heating rate against the rate of radiative-cooling within the cooling radius, for systems of different masses. They suggested that the average heating-to-cooling ratio decreased by two orders of magnitude when going from massive ellipticals / small groups to the most massive clusters. Updated observational determination of the black-hole mass dependent radio luminosity function and the radio luminosity to jet power conversion have decreased this scale-dependence, but it remains well in excess of an order of magnitude. Thus, if the radio-AGN heating rate is at the level that balances cooling in the most massive clusters (or at least the cool-core subset of these), then in smaller systems an order of magnitude more jet mechanical energy is produced than required.

Similar indications have been found by Nulsen et al. (2007; see also Figure 5 of Fabian 2012) who found that the pV energy stored in cavities seen in lower mass systems can be an order of magnitude above that required to balance cooling losses. This result is easily understood, because in individual galaxies or small groups a large fraction of the jet kinetic energy may get deposited on much larger scales than the cooling radius: the jets themselves can extend beyond the cooling flow region, and even if they don't then the bubbles they produce will still rise buoyantly to beyond the cooling radius, while the weak shocks produced by the expanding cavities dissipate their energy on similarly large (hundred-kpc) scales (e.g. Fabian et al. 2005).

In lower mass systems the duty cycle of radio source activity is also low, with the AGN being turned off for most of the time. The heating-cooling balance is a pseudo-equilibrium process, whereby in the brief periods where the radio source does turn on, the instantaneous energetic output is far above that required to balance cooling. This leads to over-heating of the gas, seen for example as a temperature difference observed between galaxy groups and low-mass clusters with and without radio-AGN (Croston et al. 2005, Maglioccetti & Brüggen 2007; see also Shen et al. 2008). After the radio-AGN outburst, the system will experience a period during which accretion rates are suppressed by the turbulent motions and heating that was induced, leading to effectively an off state for the black hole. This behavior is seen in hydrodynamic simulations (e.g. Gaspari et al. 2013) and is also suggested by both the episodic history of star-formation found by Chen et al. (2013) in massive galaxies ($M_* > 10^{11} M_\odot$) and by the apparent anti-correlation they find between a recent burst of star formation and the current presence of a radio source. This off-period lasts longer in less massive systems since the lower binding energy and gas sound speed lead to a longer recovery time before gas cooling and accretion re-commence. The black hole therefore acts as a cosmic thermostat, adjusting quickly to its surroundings and switching on powerful radio-AGN activity whenever the gas temperature drops sufficiently to allow significant cooling to occur. Rare intermittent activity (duty cycle 0.001 – 0.01) suffices to control gas cooling in typical massive ellipticals (of stellar mass $\sim 10^{11}$ $M_\odot$), with the system oscillating around an equilibrium state. In contrast, near-constant activity (duty cycle $\sim$1) is required to control gas cooling in the most massive cooling flow clusters.

7. THE SITUATION AT HIGH REDSHIFT

The focus of this review has been the contemporary universe as probed through large surveys (most notably, the Sloan Digital Sky Survey). It is then natural to ask whether the results we have reviewed apply only to the present-day, or whether a qualitatively similar picture also applies at higher redshift.

7.1. The Representative AGN Population

To begin, let us use the cosmic evolution of the bolometric AGN luminosity function to frame the issues. While it is customary to refer to the redshift range of 2 to 3 as the QSO era, this is actually rather misleading. It is true that the co-moving number density of the most powerful AGN ($L_{\rm bol} > 10^{14}$ $L_\odot$) peaked during this epoch. These are associated with the formation of the most massive SMBH ($> 10^{9.5}$ $M_\odot$), and as such comprise only a minor fraction of the black hole mass in the local fossil record (Shankar et al. 2009). A much better way to think about the growth of the black hole population is to use the data plotted in Fig. 1 to calculate the history of the cumulative growth of the relic mass in supermassive black holes over time. This leads to the striking result that the growth of black holes is actually a protracted process: 25%, 50%, and 75% of the present-day relic mass formed by cosmic ages of about 3.3 Gyr ($z \sim 2$), 5 Gyr ($z \sim 1.3$), and 7 Gyr ($z \sim 0.75$). The history of the mass build-up in galaxies via star formation is very similar (e.g. Shankar et al. 2009). So in a big picture sense, the physics that connected (connects) the growth of galaxies and black holes must have been in place over a significant fraction of the history of the universe and the bulk of this co-evolution took place at moderate redshifts.

To focus our discussion, we will therefore consider the population of AGN and their host galaxies over the redshift range of 0.5 to 2.5 (during which time about 75% of the current black hole mass was created by accretion). The shape of the bolometric luminosity function at $z \sim 2$ (Hopkins et al. 2007, Shankar et al. 2009) implies that most of the black hole growth then occurred for objects near L_*. More quantitatively, half the black hole growth occurred for AGN with bolometric luminosities between $L_{\rm bol} \sim 10^{12.5}$ and $10^{13.3}$ $L_\odot$ (or hard X-ray luminosities of 2×10^{44} to 8×10^{44} erg s^{-1}). At z $\sim$ 0.5, the same calculation implies that half the black hole growth occurred in AGN with bolometric (hard X-ray) luminosities between $10^{11.2}$ and $10^{12.3}$ $L_\odot$ (3×10^{43} to 2×10^{44} erg/s). We will use these fiducial values for redshift and luminosity to define what we will henceforth call *representative AGN*, by which we mean the objects most responsible for the creation through accretion of the mass locked up in black holes in the present fossil record.

7.2. The Host Galaxies of Radiative-Mode AGN

Most of the information about AGN host galaxies at high-z comes either from deep surveys of fields that probe co-moving volumes too small to sample the representative AGN population or from observations of individual AGN of exceptionally high luminosity. It is only over the past few years that we have learned quite a bit about the properties of the host galaxies of the representative AGN. For the most part these surveys have selected the AGN and quantified their properties based on (rest-frame) hard X-ray data. One potentially important caveat is that it is possible that the host galaxies of X-ray-selected AGN systematically differ from the host galaxies of AGN selected in the IR or optical (Hickox et al. 2009, Juneau et al. 2013, Koss et al. 2011).

The most detailed investigation of the dependence of AGN properties on the mass of the host galaxy was undertaken by Aird et al. (2012) for a population of X-ray detected objects over the range $z = 0.2$ to 1.0. They find that the distribution of AGN X-ray luminosity normalized by the stellar mass of the host galaxy (M_*) is essentially independent of M_* over mass bins with centers from $M_* = 10^{9.75}$ to $10^{11.75}$ $M_\odot$. Within the uncertainties, this is largely consistent with the [OIII]-based SDSS results at $z \sim 0.1$ we have plotted in Fig. 16, except that our plot shows a strong drop in normalized luminosity at high galaxy mass. As we noted, the normalized sum of $L_{\rm rad}$ plus $L_{\rm mech}$ is roughly independent of M_* out to the highest masses. In fact, Chen et al. (2013) found strong evolution in the emission-line AGN associated with very massive

galaxies ($M_* > 10^{11.4}$ $M_\odot$) between $z \sim 0.1$ and 0.6. They found that the equivalent width of the [OIII] emission-line (a rough proxy for L_{rad}/M_*) increased by an order of magnitude, and that the emission-lines changed from LINER-like (jet-mode) at low-z to Seyfert-like (radiative-mode) at higher-z. This is at least qualitatively consistent with the difference between the results of Aird et al. (2012) and what is seen in the contemporary universe.

Aird et al. (2012) also conclude that their sample of AGN shows a universal distribution in Eddington ratio that is independent of galaxy or black hole mass. This would be inconsistent with the picture of the downsizing of the population of black holes since the implied timescales for black hole mass-doubling through accretion would be independent of black hole or galaxy mass. However, their result is based on their assumption of a uniform ratio of black hole to total galaxy stellar mass ($M_{BH}/M_* = 0.002$) as a function of mass. As we showed explicitly in the right-hand panel of Fig. 9, in the SDSS sample at $z \sim 0.1$ the ratio of black hole to stellar mass increases by a factor of about 1.5 dex (from 0.0001 to 0.003) over the range in stellar mass bins studied by Aird et al. (centred from log $M_* = 9.75$ to 11.75). If the relationship between black hole and galaxy mass is similar at $z \sim 0.1$ and 0.6, the Aird et al. results would then be entirely consistent with the black hole down-sizing picture. This is supported by the conclusions of Kelly & Shen (2013) based on their analysis of the SDSS QSO population.

Mainieri et al. (2011) studied the host galaxies of a sample of 142 X-ray-selected Type 2 AGN from the XMM-COSMOS field. The typical redshifts are in the range 0.8 to 2 and X-ray luminosities are 10^{44} to 10^{45} erg/s. They find few detected AGN in host galaxies with stellar masses less than $10^{10} M_\odot$, and typical stellar masses of $\sim 10^{10.5}$ to $10^{11.3}$ $M_\odot$ (similar to local Seyfert galaxies). A stacked spectrum in the rest-frame optical shows values of the 4000Å break and high-order Balmer absorption-lines corresponding to a very young star-forming population. The masses (and the star-formation rates derived from Herschel far-IR photometry) imply that the specific star-formation rates are similar to those of normal galaxies on the star-forming main sequence at the same redshifts (see Fig. 22). Most host galaxies appear to be early-type galaxies (with a significant bulge component) and only a minority show either a prominent disk or a disturbed morphology indicative of a major merger.

Schawinski et al. (2012) investigated the host galaxy properties of a population of IR-selected heavily obscured AGN at $z \sim 2$ with typical bolometric luminosities of $\sim 10^{12.5}$ $L_\odot$. Their HST imaging reveals that most have a significant disk component and only a small fraction appear to be major mergers. At lower redshifts ($z \sim 0.7$), Cisternas et al. (2011) analyzed HST images of the hosts of AGN with X-ray luminosities of 10^{43} to 10^{44} erg/s. They found that at least 85% of the host galaxies have normal undisturbed morphologies (similar to their control sample of non-AGN galaxies).

Santini et al. (2012) investigated samples of X-ray selected AGN from the GOODS N and S field and the COSMOS field over the range $z \sim 0.5$ to 2.5. Only the COSMOS field has sufficient volume to probe the population of representative AGN. Based on Herschel far-IR photometry, the star-formation rates and specific star-formation rates of the AGN hosts in this field are enhanced by a factor of about 3 relative to the full population of normal galaxies at the same redshift. However, the SFRs in the AGN hosts are consistent with those of the star-forming population of normal galaxies (i.e. the AGN avoid the quiescent galaxy population). At $z \sim 0.7$, Bournaud et al. (2012) found a high incidence rate of Seyfert-like AGN in a sample of star-forming galaxies with clumpy disks. They argue that the fueling of AGN at high-z is primarily through inflows triggered by violent disk instabilities rather than major mergers (Bournaud et al. 2011, Elmegreen et al. 2008b).

Rosario et al. (2013) have examined the relationship between star-formation rate (from the far-IR



Fig. 22.— The specific star formation rate (sSFR = SFR/M_*) of radiative-mode AGN hosts compared to normal star-forming galaxies, as a function of redshift. The green shaded region shows the evolution of the sSFR of galaxies long the star-forming main sequence derived by Karim et al. (2011). The red points show the sSFR of the host galaxies of X-ray selected Type 2 AGN from the XMM-COSMOS field derived by Mainieri et al. (2011). The blue point indicates the average sSFR of emission-line selected Type-2 AGN with $L/L_{\rm Edd} > 0.01$ (ie. broadly radiative-mode) from the SDSS. At all redshifts, the sSFR of radiative-mode AGN hosts are consistent with those of galaxies on the star-forming main sequence.

luminosity) and AGN hard X-ray luminosity over the range from $z \sim 0$ to 2.5. They find that at $z < 0.8$ there is a correlation between the AGN luminosity and star-formation rate for AGNs with bolometric luminosities above $\sim 10^{10.5}$ $L_\odot$. At higher redshifts the star-formation rate no longer correlates with AGN luminosity, but rises with increasing redshift (from ~ 10 $M_\odot$ per year at $z \sim 1$ to ~ 50 $M_\odot$ per year at $z \sim 2$). Again, these star-formation rates are consistent with the properties of typical massive star-forming galaxies at these epochs. Harrison et al. (2012a) reach similar conclusions. These results regarding the complex connection between AGN and star-formation may be related to findings of Kauffmann & Heckman (2009) at low-z. As summarized above, they found a threshold value for the specific star-formation rate for effective black hole growth. Once this threshold is exceeded, black hole growth is switched on, but the rate of growth does not increase if the star-formation rate rises further.

To summarize: the hosts of the representative population of radiative-mode AGN out to $z \sim 2$ are mostly structurally normal galaxies with star-formation rates corresponding to those of the typical star-forming population of galaxies at that epoch. These results are consistent with most other investigations of the less powerful AGN population over the same range in redshift (e.g. Pierce et al. 2007, Gabor et al. 2009, Hickox et al. 2009, Silverman et al. 2009, 2011, Schawinski et al. 2011, Kocevski et al. 2012, Mullaney et al. 2012a,b, Aird et al. 2012, 2013, Bohm et al. 2013, Rosario et al. 2013, Juneau et al. 2013, Chen et al. 2013). These results are also consistent with the more detailed picture we have presented for radiative-mode AGN in the contemporary universe.

7.3. Evolution of the Radio Loud AGN Population

The cosmic evolution of the radio luminosity function has been studied for many years, since early work on understanding radio source counts indicated that high luminosity sources undergo substantially stronger cosmic evolution than low luminosity sources (Longair 1966). Seminal work by Dunlop & Peacock (1990) clearly established that the space density of both flat-spectrum (i.e. beamed) and steep-spectrum powerful radio sources is 2-3 orders of magnitude higher by $z \sim 2$ than in the contemporary universe. Beyond this redshift the space density peaks, or declines slowly. In contrast, the low luminosity radio sources show only a factor < 2 increase in space density out to $z \sim 0.5$ (e.g. Sadler et al. 2007, Donoso et al. 2009). Rigby et al. (2011) characterized this differential evolution, showing that the redshift at which the radio source space density peaks is strongly luminosity dependent with low luminosity sources showing a peak space density at $z < 1$.

As discussed earlier, the radio-AGN population comprises both jet-mode (radiatively inefficient) AGN, and radiative-mode (radio-loud QSO/Seyfert-like) AGN. Best & Heckman (2012) looked at the cosmic evolution of these two populations separately within the narrow redshift range probed by SDSS, and concluded that they showed different cosmic evolution. This has been confirmed by Best et al. (in prep), who show that out to $z \sim 0.7$ the radiative-mode population shows a factor $\sim$8 increase in space density, at all radio luminosities. The jet-mode sources, however, show only a small increase in space density out to $z = 0.5$, followed by a decline thereafter. These results are easily understood in terms of our earlier discussions on the fueling of these AGN. The radiative-mode radio AGN evolve in broadly the same manner as the upper-mass end of the radiative-mode radio-quiet population, increasing with redshift as the availability of an abundant supply of cold gas increases. If the jet-mode AGN are largely associated with cooling hot-gas haloes, then their evolution will be closer to that of massive galaxies, and thus slowly declining towards higher redshifts.

These results indicate that the luminosity-dependent cosmic evolution of the radio luminosity function as a whole is largely driven by the different cosmic evolution of these two AGN populations. As a result of this differential evolution, the dominant radio-AGN population also changes with redshift. Locally, except at the highest radio luminosities, the jet-mode population dominates the radio-AGN number counts. By $z > 1$ however, the QSO/Seyfert-like sources begin to dominate at all (currently-observable) luminosities. It is for this reason that the properties of radio-loud and radio-quiet AGN appear much more comparable in the early universe than in the contemporary universe.

Early work to extend the study of the host galaxies of the jet-mode AGN to higher redshifts finds a picture consistent with that in the contemporary universe. Tasse et al. (2008) and Donoso et al. (2009) both investigated the relationship between galaxy stellar mass and radio-AGN prevalence at $z \sim 0.5$. They found that, if consideration is restricted to only the jet-mode AGN, then a steep power-law dependence is found, similar to that for the contemporary universe (Section 4.3). Simpson et al. (2013) recently extended that analysis to $z \sim 1$, confirming the same results. Tasse et al. (2008) also showed that the jet-mode population was typically found in galaxy over-densities (groups or clusters). These results indicate that the feedback balance between radiative cooling and radio-AGN heating, seen in the contemporary universe, was already in place in some environments when the universe was half of its current age.

7.4. AGN Feedback at High-z

Feedback from AGN in the form of ionizing radiation clearly plays a fundamental role in ionizing and heating the intergalactic medium over much of the history of the universe. Here, we briefly summarize the

evidence regarding the existence and physical properties of bulk outflows of mass and kinetic energy driven by AGN. This evidence is based on detailed investigations of small samples of AGN.

In series of papers, Arav and collaborators (Arav et al. 2008, Korista et al. 2008, Moe et al. 2009, Dunn et al. 2010, Bautista et al. 2010, Edmonds et al. 2011, Aoki et al. 2011, Borguet et al. 2013, Arav et al. 2013) have been able to determine the main physical properties of outflows in high-z QSOs as traced by UV absorption-lines. The QSOs have bolometric luminosities of $\sim 10^{13.3}$ to $10^{14.7}$ $L_\odot$ and $z \sim 0.6$ to 3 (they are considerably more luminous than the representative AGN population). Of the eight outflows they have analyzed, four are extremely energetic with kinetic energy fluxes of 10^{45} to 10^{46} erg s^{-1}, representing ∼1 to 5% of L_{bol}. The typical outflows speeds are about 3000 to 8000 km s^{-1} and the inferred size-scales of the outflows range from several hundred pc to several kpc. Similar work by this group on less luminous AGN at lower redshift has so far found only very weak outflows with kinetic energy fluxes $\ll L_{bol}$ (Edmonds et al. 2011, Borguet et al. 2012).

Alexander et al. (2010) and Harrison et al. (2012b) have analyzed spatially-resolved maps of the kinematics of the ionized gas surrounding nine radio-quiet AGN at $z \sim 1.4$ to 3.4. The objects were selected from a parent sample of sub-mm galaxies on the basis of unusually strong and broad [OIII]5007 emission-lines. Evidence for galactic-scale outflows was found in the five AGN with bolometric luminosities of about 10^{13} $L_\odot$ (roughly L_* at these redshifts), but not in the less luminous cases. The strong rest-frame far-IR emission in these objects implies that they have much higher star-formation rates than typical AGN at these redshifts ($\sim 10^3$ $M_\odot$/year compared to ~ 30 to 100 $M_\odot$/year respectively). Thus, it is not entirely clear whether the outflows are driven by the AGN or the starburst in these objects.

Using similar techniques, galaxy-scale outflows of ionized gas have been mapped around a small sample of extremely radio-loud QSO-like AGN at $z \sim 2$ (Nesvadba et al. 2006, 2008). These outflows appear to be driven by the mechanical energy carried by the powerful radio jets in these systems. At the highest redshifts, Maiolino et al. (2012) have mapped an outflow from an exceptionally luminous ($L_{bol} \sim 10^{14}$ $L_\odot$) QSO at $z \sim 6.4$ using the [CII] far-IR emission-line. They estimate an outflow rate of several thousand solar masses per year at a velocity of-order 10^3 km/s. We conclude that direct evidence for AGN feedback at high-z is limited so far to objects of exceptionally high luminosity or other unusual characteristics. Little is known about whether the representative population of high-z AGN produce powerful global outflows. Again, this is all consistent with the results derived in the contemporary universe.

8. SUMMARY & IMPLICATIONS

Let us begin this final section by briefly summarizing what we regard as the most robust conclusions about the demographics of the populations of AGN and their host galaxies in the contemporary universe. We will then consider the degree to which these results may be extended to higher redshift, and conclude with some speculation about the implications these conclusions may have for our understanding of the formation and evolution of galaxies.

8.1. Some Robust Conclusions

In the contemporary universe there are two distinct families of AGN. We have designated them radiative-mode and jet-mode AGN. The radiative-mode population of AGN is characterized by the production of

significant amounts of radiation with typical bolometric luminosities of 1 to 100% of the Eddington limit. Historically these have been called Seyfert galaxies or QSOs depending upon their luminosity. The AGN properties can be explained within the theoretical context of a radiatively-efficient geometrically-thin accretion disk. In the contemporary universe these AGN are characteristically found to have black hole masses of 10^6 to 10^8 $M_\odot$ and to reside in host galaxies with typical stellar masses of a few $\times 10^{10}$ to a few $\times 10^{11}$ $M_\odot$ and high stellar surface mass densities ($\mu_* > 10^{8.5}$ $M_\odot$ kpc^{-2}). While these densities are characteristic of early-type disk galaxies, the AGN hosts (unlike most such galaxies) have significant amounts of on-going star-formation in the central few kpc. When examined at high spatial resolution these inner regions can usually be classified a pseudo-bulges. Major mergers or strong tidal interactions are not the dominant fueling mechanism for the central star formation and the AGN. Internal secular processes for the radial transport of gas are evidently more important. This summary pertains to the typical AGN that are the sites of the majority of the growth of supermassive black holes today. Things may differ for the rare objects with the highest luminosities.

The radiative-mode AGN are associated with populations of lower-mass black holes and lower-mass (pseudo-)bulges that both have volume-averaged mass-doubling times (via accretion and star-formation respectively) of roughly the Hubble time. The volume-averaged ratio of star-formation to black hole growth in these central regions is of-order a thousand (similar to the ratio of stellar mass and black hole mass in current classical bulges and elliptical galaxies). These are evidently living systems that have not yet reached their evolutionary end-point. While, there is indirect evidence that feedback is limiting the growth of the black hole, there is little direct evidence for AGN-generated feedback for typical objects. On the other hand, there is recent evidence that this may occur in the rare low-z AGNs having the highest luminosity ($L_{\rm bol} \sim 10^{12-14}$ $L_\odot$). The association of AGN with central star-formation implies that feedback from massive stars will be present but its effect on the fueling of the AGN has not been well-quantified.

The second, jet-mode, AGN class is characterized by the production of collimated energetic outflows (jets) but with little detected emitted radiation (characteristic luminosity below about 1% of the Eddington limit). Historically these have been called (low-excitation) radio galaxies. The more luminous LINERs are also likely to be members of this population. The AGN properties can be explained within the theoretical context of a radiatively-inefficient accretion flow. The probability of a galaxy or black hole producing a jet of a given radio luminosity is a steep function of mass: typical radio galaxies are structurally normal massive ellipticals ($M_* \sim 10^{11}$ to 10^{12} $M_\odot$) with black hole masses greater than 10^8 $M_\odot$. There is no evidence for substantial recent star-formation in typical radio galaxies (although there can be for radio-AGN in the BCGs of extreme cooling flow clusters). There is mostly indirect evidence that the fueling of the AGN is by the accretion of hot gas seen in X-ray observations. Feedback produced as the jets interact with this hot gas can be directly observed. While it is energetically possible for this feedback to prevent the gas from cooling rapidly, the details remain uncertain. These AGN are associated with the populations of higher mass black holes and spheroids that both have mass-doubling times orders-of-magnitude longer than the Hubble time. These are effectively dead systems in which the bulk of the star-formation and black hole growth occurred at high-redshift.

In examining the situation at higher redshift, we have emphasized the importance of focusing on the representative population of AGN that is responsible for the creation of the majority of the mass in relic supermassive black holes today. These are AGN in the redshift range $z \sim 0.5$ to 2.5 and with luminosities near the knee in the luminosity function. These representative AGN appear to be hosted by moderately massive galaxies ($M_* > 10^{10} M_\odot$) with star-formation rates that are typical of the star-forming galaxies at that epoch (they are located on the star-forming main sequence). They are typically found in structurally



Fig. 23.— Ratio of the total star formation rate per unit volume in galaxies to the total accretion rate per unit volume onto black holes as traced by Type 2 AGNs, plotted as a function of the black hole mass. The sample studied consists of all galaxies from the SDSS main galaxy sample with stellar surface mass density above the characteristic value $\mu_* = 10^{8.5}$ $M_\odot$ kpc^{-2}. Red lines show the result if the SFR is calculated within the fiber aperture for each galaxy and the blue lines show the result using estimates of the total SFR. Dotted lines show results restricted to the AGNs with (reddening corrected and star-formation corrected) $L_{[OIII]} > 10^{7.5}$ $L_\odot$. The horizontal dashed line shows the fiducial value of stellar to black hole mass in bulges and elliptical galaxies. Adapted from Heckman et al. (2004).

normal galaxies rather than highly disturbed systems (major mergers). The population of radio-loud AGN remains prevalent among massive galaxies. Evidence for feedback in the form of powerful AGN-driven outflows is limited so far to objects of either exceptional luminosity or other unusual properties (very high radio luminosity or star-formation rate).

All of this sounds similar to the situation in the contemporary universe. The main differences are quantitative rather than qualitative: 1) The characteristic luminosities of the actively growing black holes are larger than the present day (by a factor of about three at $z \sim 0.5$ and ∼30 at $z \sim 2$). The characteristic masses of these black holes are also correspondingly larger, by factors that are model-dependent (e.g. Shankar et al. 2013). 2) The specific star-formation rates of host galaxies on the main sequence are higher than the current value by factors of ∼3 at $z = 0.5$ and ∼20 at $z = 2$ (e.g. Elbaz et al. 2011). Thus, to zeroth-order, the situation at higher-z seems like a scaled-up version of the contemporary universe.

There is also (what we regard as) persuasive indirect evidence that the physical processes that link the formation and evolution of galaxies and black holes at high-z are still at play today. As we noted in the introduction, the ratio of the rate of build-up of galaxies through star formation to the rate of the build-up of black holes via accretion has been broadly independent of cosmic time over at least the last ~ 10 Gyrs with a value of ∼1500 (Shankar et al. 2009, 2013, Hopkins & Beacom 2006). This is hard to understand unless the underlying physics has remained basically the same over this time. See Heckman et al. (2004) and Mullaney et al. (2012b) for further discussion of this argument. Indeed, as Fig. 23 shows, this ratio applies not just to the total rates, but holds over all values for the mass of the SMBH.

8.2. Implications and Some Speculation

Our current understanding of the formation and evolution of galaxies is that the build-up of the stellar content of galaxies via star-formation is driven primarily by the accretion of gas from the cosmic web. At least since $z = 2$ or 3, the bulk of the star formation occurs in galaxies lying along a strongly evolving star-forming main sequence (a tight relationship between SFR and stellar mass). While major mergers of gas-rich systems do occur, and lead to strong bursts of star-formation, they are responsible for only a minority (of-order 10%) of the total cosmic star-formation. This picture is predicted by numerical simulations and is consistent with observations of the evolving population of star-forming galaxies (e.g. Dekel et al. 2009, Bouche et al. 2010, Elbaz et al. 2011, Wuyts et al. 2011b, Whitaker et al. 2012, Lilly et al. 2013).

Empirically, the accretion-driven mass-growth of the population of supermassive black holes is related to the growth (via star-formation) of the inner region of the host galaxy. Evidently, both rates track the rate at which gas is accreted by the galaxy (with relative efficiencies that differ by about three orders-of-magnitude). Mergers are not the dominant mechanism by which gas flows to these inner regions, and hence are not the dominant mechanism for growing the population of supermassive black holes. The gas-flows responsible for this may instead be driven by rather slow secular processes in the contemporary universe (e.g. Kormendy & Kennicutt 2004, Athanassoula 2008) or more violent and rapid instabilities in clumpy gas-rich disks at high-z (e.g. Genzel et al. 2013, Bournaud 2010, Elmegreen et al. 2008a, Dekel et al. 2009). This picture would imply that the representative population of actively growing supermassive black hole (AGN) would live at the centers of disk-like structures (rather than ellipticals or classical bulges).

This simple picture leaves out one critical fact: we know from observations that the effect of this co-evolution over cosmic time must ultimately place the relic (dead) black holes in dynamically hot structures (ellipticals and classical bulges) that contain little cold gas and correspondingly little star-formation. In the classical picture for the co-evolution of galaxies and black holes this is explained economically by positing that the supermassive black hole grew in the aftermath of a major merger that created an elliptical/classical-bulge and that feedback from the rapidly growing black hole blew away the remaining gas (e.g. Hopkins et al. 2006, 2008, Di Matteo et al. 2008). How can this be explained in the more sedate scenario we are advocating? Let us try a two-part answer.

First, while low-mass bulges can be built through secular processes and disk instabilities (e.g. Hopkins et al. 2012, Athanassoula 2008, Bournaud et al. 2011), it appears that major mergers are the only way to build the population of massive classical bulges and elliptical galaxies. In this case, the sedate scenario would imply that these major mergers only modestly augment the masses of gas accreted by the black hole and of gas turned into stars. The $M_{\rm BH}$ vs. σ relationship would have to be essentially pre-built before a major merger takes place (consistent with the recent simulations by Anglés-Alcázar et al. 2013). A major merger mostly rearranges the stars in the pre-existing disks (and their black-hole-containing pseudo-bulges) into a classical bulge or elliptical galaxy and a more massive (merged) black hole. Subsequent dry merging between classical bulges or ellipticals can further populate the upper end of the $M_{\rm BH}$ *vs.* σ relation (e.g. Shankar et al. 2010, Kormendy & Ho 2013).

The second part of the answer requires an explanation for the dry-up of the reservoir of cold gas and the subsequent quenching of star-formation. In current models, this shut-down in star-formation in a typical massive galaxy is connected to the transition from an accretion mode in which gas reaches the galaxy in a cold form (gas temperature much less than the virial temperature) to a mode where the accreted gas is heated to roughly the virial temperature upon arrival and then slowly cools (via radiation) and is gradually accreted. This transition is predicted to occur when the galaxy halo mass grows via mergers and exceeds

some critical value. Dekel et al. (2009) argue that this critical mass corresponds to the observed transition between high-mass mostly-quiescent galaxy population and lower mass galaxy population that defines the star-forming main sequence (see also Bouche et al. 2010, Lilly et al. 2013, Mutch et al. 2013). While current models still need to incorporate AGN feedback to quench star formation, it is possible that this is a result of the difficulty in incorporating the relevant physical processes with the necessary fidelity in current state-of-the-art numerical simulations. In this case, late feedback from AGN might only be required to be strong enough to suppress the late cooling flows of hot gas and keep the quiescent galaxy suitably red and dead. This may be accomplished by the low luminosity radio-AGN, through the self-regulating feedback loop we have described in Section 6.2 above (the so-called maintenance mode of AGN feedback).

As we have emphasized, this sedate model is designed to match the detailed picture we have of the contemporary universe and the emerging picture we have of the representative population of AGN and their host galaxies at higher redshift. What about the more extreme cases? More specifically, one might ask about the physical mechanism(s) responsible for imposing a characteristic AGN luminosity at a given epoch ($L_*(z)$) above which the number density of AGN steeply falls. In part this must reflects the knee in the black hole mass function. However, there is also evidence that the most powerful AGN (at both high-z and low-z) are different from their less luminous kin. There are indications that the fraction of AGN host galaxies that are major mergers increases at the highest AGN luminosities (e.g. Liu et al. 2009, Mainieri et al. 2011, Treister et al. 2013). This is at least qualitatively consistent with the models presented by Hopkins & Hernquist (2009), Draper & Ballantyne (2012), Shankar et al. (2012), and Hopkins et al. (2013), which partition the amount of black hole growth associated with mergers and secular processes. We have also seen that the most luminous AGN at low and high redshift can drive powerful outflows that could affect the fueling of the black hole and even the bulk properties of the gas in the host galaxy and its halo. It is tempting to speculate that the knee of the AGN luminosity function marks the transition from a sedate model of fueling by accretion and subsequent internal processes with weak/no AGN feedback to a dramatic model of fueling by mergers with strong AGN feedback.

In this review we have stressed the importance of large surveys of the contemporary universe in revealing the way in which galaxies and their super-massive black holes co-evolve(d). We fully expect that the next generation of large ground- and space-based surveys will extend this type of robust and sophisticated understanding to the era when the bulk of the mass in galaxies and black holes was assembled.

LITERATURE CITED

Aalto S, Garcia-Burillo S, Muller S et al. 2012. A&A, 537: 44-51
Aird J, Coil A, Moustakas J et al. 2012. ApJ 749: 90-112
Aird J, Coil A, Moustakas J et al. 2013 ApJ 775: 41-52
Alexander EM, Swinbank AM, Smail I, McDermid R, Nesvadba NPH. 2010. MNRAS 402: 2211-2220
Allen SW, Dunn RJH, Fabian AC, Taylor GB, Reynolds CS. 2006. MNRAS 372: 21-30
Alonso MS, Lambas DG, Tissera, P, Coldwell G. 2007. MNRAS 375: 1017-1024
Anderson SF, Voges W, Margon B et al. 2003. AJ 126: 2209-2229
Anglés-Alcázar D,Özel F, Davé R et al. 2013. arXiv:1309.5963
Antonucci, R. 1992. ARAA 31: 473-521
Aoki K, Oyabu S,Dunn J et al. 2011. PASJ 63: 457-467
Arav N, Moe M, Constantini E et al. 2008. ApJ 681: 954-964
Arav N, Borguet B, Chamberlain C, Edmonds D, Danforth C. 2013. arXiv: 1395.2181
Athanassoula E 2005. MNRAS 358: 1477-1488

Athanassoula E 2008. MNRAS 390: L69-72
Baade W, Minkowski R. 1954. ApJ 119: 206-214
Bailey ME. 1980. MNRAS 191: 195-206
Baldry IK, Glazebrook K, Brinkmann J et al. 2004. ApJ 600: 681-694
Baldwin JA, Phillips MM, Terlevich R. 1981. PASP 93: 5-19
Balick B, Heckman TM. 1982. ARA&A 20: 431-468
Balogh ML, Morris SL, Yee HKC, Carlberg R, Ellingson E. 1999. MNRAS 307: 463-479
Barthel PD, Arnaud KA. 1996. MNRAS 283: L45
Baumgartner WH, Tueller J, Markwardt CB et al. 2013. ApJS 207: 19-30
Bautista MA, Dunn JP, Arav N et al. 2010. ApJ 713: 25-31
Becker RH, White RL, Hefland DJ. 1995. Ap. J. 450: 559-577
Bell AR. 1978. MNRAS 182: 443-455
Bell EF, de Jong RS. 2001. ApJ 550: 212-229
Bentz MC, Denney KD, Grier CJ et al. 2013. ApJ 767:149-175
Best PN. 2009. Astronomische Nachrichten 330: 184-189
Best PN. 2004. MNRAS 351: 70-82
Best PN, Kauffmann G, Heckman TM, Ivezić Ž. 2005a. MNRAS 362: 9-24
Best PN, Kauffmann G, Heckman TM et al. 2005b. MNRAS 362: 25-40
Best PN, Kaiser CR, Heckman TM, Kauffmann G. 2006. MNRAS 368: L67-L71
Best PN, von der Linden A, Kauffmann G, Heckman TM, Kaiser CR. 2007. MNRAS 379: 894-908
Best PN, Heckman TM. 2012. MNRAS 421: 1569-1582
Bîrzan L, Rafferty DA, McNamara BR, Wise MW, Nulsen PEJ. 2004. Ap.J. 607: 800-809
Bîrzan L, McNamara BR, Nulsen PEJ, Carilli CL, Wise MW. 2008. Ap.J. 686: 859-890
Blandford RD, Payne DG. 1982. MNRAS 199: 883-903
Blandford RD, Znajek RL. 1977. MNRAS 179: 433-456
Blanton MR, Hogg DW, Bahcall NA et al. 2003. ApJ 594: 186-207
Blundell KM, Rawlings S. 2000. Astron. J. 119: 1111-1122
Bock DC-J, Large MI, Sadler EM. 1999. Astron. J. 117: 1578-1593
Böhringer H, Voges W, Fabian AC, Edge AC, Neumann DM. 1993. MNRAS 264: L25-28
Bondi H. 1952. MNRAS 112: 195-204
Borthakur S, Heckman T, Strickland D, Wild V, Schiminovich, D. 2013. ApJ 768: 18-37
Bouche N, Dekel A, Genzel R et al. 2010. ApJ 718: 1001-1018
Borguet B, Edmonds D, Arav, N, Dunn, J, Kriss GA. 2012. ApJ 751: 107-121
Borguet B, Arav N, Edmonds D, Chamberlain, C. 2013. ApJ 762: 49-61
Bournaud F, Dekel A, Teyssier R et al. 2011. ApJ 741: L33-38
Bournaud F, Juneau S, Le Floc?h E et al. 2012. ApJ 757: 81-100
Bower RG, Benson AJ, Malbon R et al. 2006. MNRAS 370: 645-655
Brinchmann J, Charlot S, White S et al. 2004. MNRAS 351: 1151-1179
Brandt WN, Hasinger, G 2005. ARA&A 43: 827-859
Brown TM, Ferguson HC, Stanford SA, Deharveng JM. 1998. ApJ 504: 113-138
Brown TM, Smith E, Ferguson H et al. 2008. ApJ 682: 319-335
Bruzual AG. 1983. ApJ 273: 105-127
Bruzual G, Charlot S. 2003. MNRAS 344: 1000-1028
Burbidge EM, Burbidge GR, Prendergast KH. 1959. ApJ 130: 26-45
Burns JO. 1990. Astron. J. 99:14-30
Cao X. 2010. ApJ 725: 388-393

Cao X, Rawlings S. 2004. MNRAS 349: 1419-1427
Capetti A, Baldi RD. 2011. A&A 529: 126-130
Cattaneo A, Best PN. 2009. MNRAS 395:518-23
Cattaneo A, Faber SM, Binney J et al. 2009. Nature 460:213-19
Cavagnolo KW, Donahue M, Voit GM, Sun M. 2008. Ap. J. Lett. 683:L107-10
Cavagnolo KW, McNamara BR, Nulsen PEJ et al. Ap. J. 720:1066-72
Churazov E, Brüggen M, Kaiser CR, Böhringer H, Forman W. 2001. Ap. J. 554:261-73
Churazov E, Sazonov S, Sunyaev R et al. 2005. MNRAS 363:L91-95
Cicone C, Feruglio C, Maiiolino R et al. 2012. A&A 543: 99-105
Cicone C, Maiolino R, Sturm E et al. 2013. arXiv1311.2595
Cid Fernandes R, Heckman T, Schmitt H et al. 2001. ApJ 558:81-108
Cid Fernandes R, González Delgado RM, Schmitt H et al. 2004. ApJ 605: 105-126
Cid Fernandes R, Gu Q, Melnick J et al. 2004. MNRAS 355: 273-296
Cid Fernandes R, Mateus A, Sodre L, Stasinska G, Gomes JM. 2005. MNRAS 358: 363-378
Cid Fernandes R, Stasińska G, Mateus A, Vale Asari N. 2011. MNRAS 413: 1687:1699
Ciotti L, Ostriker JP. 1997. ApJ 487: L105-108
Ciotti L, Ostriker JP, Proga D. 2010. ApJ 717: 707-723
Cisternas M, Jahnke K, Inskip KJ et al. 2011. ApJ 726:57-70
Cisternas M Gadotti DA, Knapen JH et al. 2013. ApJ 776:50-64
Chen CT, Hickox RC, Alberts S et al. 2013. ApJ 773: 3-11
Chen YM, Tremonti CA, Heckman TM et al. 2010. AJ 140: 445-461
Chen YM, Kauffmann G, Heckman TM et al. 2013. MNRAS 429: 2643-2654
Chevalier RA, Clegg AW. 1985. Nature 317:44-45
Colless M, Dalton G, Maddox S et al. 2001. MNRAS 328: 1039-1063
Condon JJ. 1989. Ap. J. 338: 13-23
Condon JJ. 1992. Annu. Rev. Astron. Astrophys. 30: 575-611
Condon JJ, Cotton WD, Greisen EW et al. 1998, Astron. J. 115: 1693-1716
Conselice CJ, Bershady MA, Jangren A. 2000. ApJ 529:886-910
Cooray A, Sheth R. 2002. Phys. Reports 372: 1-129
Crenshaw DN, Kraemer SB, George IM. 2003. ARA&A 41: 117-167
Croft S, de Vries W, Becker RH. 2007. Ap.J. 667: L13-L167
Croom SM, Boyle BJ, Shanks T et al. 2005. MNRAS 356: 415-438
Croom SM, Richards GT, Shanks T et al. 2009. MNRAS 399: 1755-1772
Croston JH, Hardcastle MJ, Birkinshaw M. 2005. MNRAS 357:279-294
Croton DJ, Springel V, White S et al. 2006. MNRAS 365: 11-28
Daly RA, Sprinkle TB, O'Dea CP, Kharb P, Baum SA. 2012. MNRAS 423: 2498:2502
David LP, Nulsen PEJ, McNamara BR et al. 2001. Ap.J. 557: 546-559
David LP, Durisen RH, Cohn HN. 1987. ApJ 316: 505-516
Davies RI, Müller Sánchez F, Genzel R et al. 2007. ApJ 671: 1388-1412
Dekel A, Sari R, Ceverino, D. 2009. ApJ 703:785-801
de Vries WH, Becker RH, White RL. 2006. Astron. J. 131: 666-679
Diamond-Stanic AM, Rieke GH, Rigby JR. 2009. ApJ 699: 623-631
Diamond-Stanic AM, Rieke GH. 2012. ApJ 746: 168-181
Di Matteo T, Springel V, Hernquist, L. 2005. Nature 433: 604-607
Di Matteo T, Colberg J, Springel V, Hernquist L, Sijacki D. 2008. ApJ 636: 33-53
Dong R, Greene JE, Ho LC. 2012. ApJ 761: 73-84

Donoso E, Best PN, Kauffmann G. 2009. MNRAS 392: 617-629
Donoso E, Li C, Kauffmann G, Best PN, Heckman TM. 2010. MNRAS 407: 1078-1089
Donoso E, Yan L, Tsai C et al. 2012. ApJ 748: 80-90
Draper AR, Ballantyne DR 2012. ApJ 751: 72-84
Dressler A, Gunn JE. 1983. ApJ 270: 7-19
Dunlop JS, Peacock JA. 1990. MNRAS 247: 19-42
Dunn JP, Bautista M, Arav N et al. 2010. ApJ 709: 611-631
Dunn RJH, Fabian AC, Taylor GB. 2005. MNRAS 364: 1343-1353
Dunn RJH, Fabian AC. 2006. MNRAS 373:959-71
Edmonds D, Borguet B, Arav N et al. 2011. ApJ 739:7-18
Elbaz D, Dickinson M, Hwang HS et al. 2011. A&A 533: 119-144
Ellison SL, Patton DR, Mendel JT, Scudder JM. 2011. MNRAS 418: 2043-2053
Elmegreen BG, Bournaud F, Elmegreen DM. 2008a. ApJ 688: 67-77
Elmegreen BG, Bournaud F, Elmegreen DM. 2008b. ApJ 684: 829-834
Fabello S, Kauffmann G, Catinella B et al. 2011. MNRAS 416: 1739-1744
Fabian AC. 1994. Annu. Rev. Astron. Astrophys. 32:277-318
Fabian AC. 2012. Annu. Rev. Astron. Astrophys. 50:455-89
Fabian AC, Sanders JS, Allen SW, Crawford CS, Iwasawa K, et al. 2003a. MNRAS 344:L43-47
Fabian AC, Reynolds CS, Taylor GB, Dunn RJH. 2005. MNRAS 363:891-96
Fabian AC, Sanders JS, Taylor GB, Allen SW, Crawford CS, et al. 2006. MNRAS 366:417-28
Falcke H, Körding E, Markoff S. 2004. Astron. Astrophys. 414: 895-903
Fanaroff BL, Riley JM. 1974. MNRAS 167:P31
Fardal MA, Katz N, Weinberg DH, Davé R. 2007. MNRAS. 379: 985-1002
Fender RP, Belloni TM, Gallo E. 2004. MNRAS 355: 1105-1118
Ferrarase L, Merritt D. 2000. ApJ 539: L9-12
Filippenko A, Ho L, & Sargent W. 1993. ApJ 410: L75-78
Fiore F, Puccetti S, Grazian A et al. 2012. A&A 537: 16-37
Fischer J, Sturm E, González-Alfonso E et al. 2010. A&A 518: L41-44
Fisher DB, Drory N. 2011. ApJ 733: L47-51
Gadotti DA. 2009. MNRAS 393: 1531-1552
Gallo E, Fender RP, Pooley GG. 2003. MNRAS 344: 60-72
Gaspari M, Ruszkowski M, Oh SP. 2013. MNRAS 432: 3401-3422
Gelbord JM. 2003. PhD Thesis: Johns Hopkins University
Gendre MA, Best PN, Wall JV. 2010. MNRAS 404:1719-1732
Gendre MA, Best PN, Wall JV, Ker LM. 2013. MNRAS 430: 3086-3101
Genzel R, Förster Schreiber, NM, Lang P et al. 2013. arXiv: 1310.3838
Gebhardt K, Bender R, Bower G et al. 2000. ApJ 539: L13-16
Giacconi R, Gursky H, & Paolini F. 1962. Phys Rev L 9: 439-443
Gisler GR. 1978. MNRAS 183: 633-643
González-Alfonso E, Fischer J, Graciá-Carpio J et al. 2013. arXiv: 1310.3074
González Delgado RM, Cid Fernandes R, Pérez E et al. 2004. ApJ 606:127-143
Gonzáalez Delgado RM, Pérez, E, Cid Fernandes, R, Schmitt, H. 2008. AJ 135: 747-765
Goto T. 2006. MNRAS 369: 1765-1772
Goulding AD, Alexander, DM. 2009. MNRAS 398: 1165-1193
Graham AW, Scott N. 2013. ApJ 764: 151-169
Greene JE, Ho LC. 2007a. ApJ 670: 92-104

Greene JE, Ho LC. 2007b. ApJ 667: 131-148
Greene JE, Zakamska, N, Ho, LC, Barth AJ. 2011. ApJ 732: 9-28
Grier CJ, Martini P, Watson LC et al. 2013. ApJ 773: 90-103
Grimes JP, Heckman T, Stickland D, Ptak A. 2005. ApJ 628: 187-204
Gultekin K, Richstone DO, Gebhardt K et al. 2009. ApJ 698: 198-221
Gürkan G, Hardcastle MJ, Jarvis MJ. 2013. arXiv:1308.4843 Haines CP, Pereira MJ, Sanderson AJR et al. 2012. Ap.J. 754: 97:113
Hainline KN, Hickox R, Greene JE, Myers AD, Zakamska NL. 2013. ApJ 774: 145-153
Hao L, Strauss MA, Tremonti CA et al. 2005a. AJ 129: 1783-1794
Hao L, Strauss MA, Fan X et al. 2005b. AJ 129: 1795-1808
Hardcastle MJ, Evans DA, Croston JH. 2007. MNRAS 376: 1849-1856
Haring N, Rix HW. 2004. ApJ 604: L89-92
Harrison CM, Alexander DM, Mullaney JR et al. 2012a. ApJ 760: L15-19
Harrison CM, Alexander DM, Swinbank AM et al. 2012b. MNRAS 426:1073-1096
Hasinger G, Miyaji T, Schmidt M. 2005. A&A 441: 417-434
Heckman TM. 1980. A&A 87: 152-164
Heckman TM, Balick B, Sullivan WTIII. 1978. ApJ 224: 745-760
Heckman TM, Blitz L, Wilson AS, Armus L, Miley GK. 1989. ApJ 342: 735-758
Heckman TM, Armus, L, Miley GK. 1990. ApJS 74: 833-868
Heckman TM, Kauffmann G, Brinchmann J et al. 2004. ApJ 613: 109-118
Heckman TM, Ptak A, Hornschemeier A, Kauffmann G. 2005. ApJ 634:161-168
Heywood I, Blundell KM, Rawlings S. 2007. MNRAS 381: 1093-1102
Hicks EKS, Davies RI, Maciejewski W et al. 2013. ApJ 768: 107-123
Hickox RC, Jones C, Forman W et al. 2009. ApJ 696: 891-919
Hillel S, Soker N. 2013. MNRAS 430: 1970-1975
Hine RG, Longair MS. 1979. MNRAS 188: 111-130
Hlavacek-Larrondo J, Fabian AC. 2011. MNRAS 413:313-21
Ho LC. 2005. Astrophys.Space Sci. 300: 219-225
Ho LC. 2008. Annu. Rev. Astron. Astrophys. 46: 475-539
Ho LC, Darling J, Greene JE. 2008. ApJ 681: 128-140
Hopkins AM, Beacom JF, 2006. ApJ 651: 142-154
Hopkins PF, Hernquist L, Cox TJ et al. 2006. ApJS 163: 1-49
Hopkins PF, Richards GT, Hernquist L. 2007. ApJ 654: 731-753
Hopkins PF, Hernquist L, Cox TJ, Keres D. 2008. ApJS 175: 356-389
Hopkins PF, Hernquist L. 2009. ApJ 694: 599-609
Hopkins PF, Quataert E. 2011. MNRAS 415: 1027-1050
Hopkins PF, Keres, D, Murray N, Quataert E, Hernquist L. 2012. MNRAS 427: 968-978
Hopkins PF, Kocevski DD, Bundy K. 2013. ApJ 776: 48-65
Hu EM, Cowie LL, Wang Z. 1985. Ap.J.Supp. 59: 447-498
Hubble EP. 1925. Pop Astr 33: 252-255
Hwang HS, Park C, Elbaz D, Choi Y-Y. 2012. Astron. Astrophys. 538: A15-A29
Ibar E, Cirasuolo M, Ivison RJ et al. 2008. MNRAS 386: 953-962
Ishibashi W, Fabian AC 2012. MNRAS 427: 2998-3005
Ivezić Ž, Menou K, Knapp GR et al. 2002. Astron. J. 124: 2364-2400
Janssen RMJ, Röttgering HJA, Best PN, Brinchmann J. 2012. Astron. Astrophys. 541: A62-A68
Jiang YF, Greene JE, Ho LC, Xiao T, Barth AJ. 2011. ApJ 742: 68-85

Juneau S, Dickinson, M, Bournaud F et al. 2013. ApJ 764: 176-194
Karim A, Schinnerer E., Martínez-Sansigre A. 2011. ApJ 730: 61-91
Kaspi S, Smith PS, Netzer H et al. 2000. ApJ 533: 631-649
Kauffmann G, Haehnelt M. 2000. MNRAS 311: 576-588
Kauffmann G, Heckman TM, Tremonti C et al. 2003a. MNRAS 346: 1055-1077
Kauffmann G, Heckman TM, White SDM et al. 2003b. MNRAS 341: 54-69
Kauffmann G, White SDM, Heckman TM et al. 2004. MNRAS 353:713
Kauffmann G, Heckman TM, Best PN. 2008. MNRAS 384: 953-971
Kauffmann G, Heckman TM. 2009. MNRAS 397:135-47
Kelly BC, Merloni A. 2012. AdAst 2012: 7-34
Kelly BC, Shen Y. 2013. ApJ 764: 45-69
Kerr R. 1963. Phys Rev L 11: 237-238
Kewley LJ, Dopita MA, Sutherland RS, Heisler CA, Trevena J. 2001. ApJ 556: 121-140
Kewley LJ, Groves B, Kauffmann G, Heckman T. 2006. MNRAS 372: 961-976
Kocevski DD, Faber SM, Mozena M et al. 2012. ApJ 744: 148-156
Kollmeier JA, Onken CA, Kochanek CS et al. 2006. Ap. J. 648:128-39
Korista KT, Bautista MA, Arav N et al. 2008. ApJ 688: 108-115
Kormendy J, Kennicutt RC. 2004. ARA&A 42: 603-683
Kormendy J, Ho LC. 2013. ARA&A 51: 511-653
Koss M, Mushotzky R, Veilluex S et al. 2011. ApJ 739: 57-76
Koss M, Mushotzky R, Treister E et al. 2012. ApJ 746 L22-28
Krolik, J. 1999. 'Active Galactic Nuclei'. Princeton NJ: Princeton University Press
Krug HB, Rupke DSN, Veilleux S. 2010. ApJ 708: 1145-1161
Lacy M, Storrie-Lombardi LJ, Sajina A et al. 2004. ApJS 154: 166-169
Lackner CN, Gunn JE. 2012. MNRAS 421: 2277-2302
Lagos CDP, Lacey CG, Baugh CM, Bower R, Benson A. 2011. MNRAS 416: 1566-1584
Laing RA, Jenkins CR, Wall JV, Unger SW. 1994. ASP Conf. Ser. 54: 201-208
LaMassa S, Heckman TM, Ptak A et al. 2010. ApJ 720: 786-810
LaMassa S, Heckman TM, Ptak A et al. 2012. ApJ 758: 1-27
LaMassa S, Heckman TM, Ptak A, Urry CM. 2013. ApJ 765: 33-38
Larson RB, Tinsley BM. 1978. ApJ 219: 46-59
Lee G-H, Woo J-H, Lee MG et al. 2012. ApJ 750: 141-152
Leitherer C, Schaerer D, Goldader J et al. 1999. ApJS 123: 3-40
Li C, Kauffmann G, Wang L et al. 2006. MNRAS 373: 457-468
Li C, Kauffmann G, Heckman TM, White SDM, Jing YP. 2008a. MNRAS 385: 1903-1914
Li C, Kauffmann G, Heckman TM, White SDM, Jing YP. 2008b. MNRAS 385: 1915-1922
Lilly SJ, Carollo CM, Pipino A, Renzini A, Peng Y. 2013. ApJ 772: 119-137
Lin Y-T, Shen Y, Strauss MA, Richards GT, Lunnan R. 2010. Ap.J. 723: 1119-1138
Lintott C, Schawinski K, Bamford S et al. 2011. MNRAS 410: 166-178
Liu X, Zakamska NL, Greene JE et al. 2009. ApJ 702: 1098-1117
Liu G, Zakamska NL, Greene JE, Nesvadba NPH, Liu X. 2013a. MNRAS 430: 2327-2345
Liu G, Zakamska NL, Greene JE, Nesvadba NPH, Liu X. 2013b. MNRAS 436: 2576-2597
Liu X, Shen Y, Strauss M. 2012. ApJ 745: 94-109
Longair MS. 1966. MNRAS 133: 421-436
Longair MS, Seldner M. 1979. MNRAS 189: 433-453
Lupton RH, Ivezic Z, Gunn JE et al. 2002. SPIE 4836: 350-356

Maccarone TJ. 2003. Astron. Astrophys. 409: 697-706
Machalski J, Condon JJ. 1999. Ap.J.Supp. 123: 41-78
Machalski J, Godlowski W. 2000. Astron. Astrophys. 360: 463-471
Magliocchetti M, Brüggen M. 2007. MNRAS 379: 260-274
Magliocchetti M, Maddox SJ, Lahav O, Wall JV. 1998. MNRAS 300: 257-268
Mahadevan R. 1997. Ap.J. 477: 585-601
Maiolino R, Ruiz M, Rieke, GH, Papadopoulos P.1997. ApJ 485: 552-569
Maiolino R, Gallerani S, Neri R et al. 2012. MNRAS 425: L66-70
Mainieri V, Bongiorno , Merloni A et al. 2011. A&A 535: 80-106
Malkan M, Gorjian V, Tam, R. 1998 ApJS 117: 25-88
Mandelbaum R, Li C, Kauffmann G, White SDM. 2009. MNRAS 393: 377-392
Mannering EJA, Worrall DM, Birkinshaw M. 2011. MNRAS 416: 2869-2881
Marconi A, Hunt LK. 2003. ApJ 589: L21-24
Marconi A, Risaliti G, Gilli R et al. 2004. MNRAS 351: 169-185
Martin DC, Fanson, J, Schiminovich D et al. 2005. ApJ 619: L1-6
Martínez-Sansigre A, Rawlings S. 2011. MNRAS 414: 1937-1964
Martini P, Kelson DD, Kim E, Mulchaey JS, Athey AA. 2006. Ap.J. 644: 116-132
Martini P, Dicken D, Storchi-Bergmann T. 2013. ApJ 766: 121-143
Mauch T, Sadler EM. 2007. MNRAS 375: 931-950
McConnell NJ, Ma CP 2013. ApJ 764: 184-197
McMahon RG, White RL, Helfand DJ, Becker RH. 2002. Ap.J.Supp. 143: 1-23
McNamara BR, Rohanizadegan M, Nulsen PEJ. 2011. ApJ. 727: 39-46
McNamara BR, Nulsen PEJ. 2007. Annu. Rev. Astron. Astrophys. 45: 117-175
Meier DL. 1999. Ap. J. 522:753-766
Meier DL. 2001. Ap. J. 548:L9-L12
Merloni A, Heinz S, Di Matteo T. 2003. MNRAS 345:1057-76
Merloni A, Heinz S. 2007. MNRAS 381: 589-601
Merloni A, Heinz S. 2008. MNRAS 388: 1011-1030
Miley G. 1980. Annu. Rev. Astron. Astrophys. 18: 165-218
Miley GK, Neugebauer G, Soifer BT. 1985. ApJ 293: L11-14
Miller CJ, Nichol RC, Gómez PL, Hopkins AM, Bernardi M. 2003. Ap.J. 597: 142-156
Miller JM, Raymond J, Reynolds CS, Fabian AC, Kallman TR, Homan J. 2008. Ap. J. 680:1359-77
Mirabel IF, Wilson AS. 1984. ApJ 277: 92-105
Moe M, Arav N, Bautista MA, Korista KT. 2009. ApJ 706: 525-534
Mullaney JR, Pannella M, Daddi E et al. 2012a. MNRAS 419:95-115
Mullaney JR, Daddi E, Béthermin M et al. 2012b. ApJ 753: L30-34
Murphy KD, Yaqoob T. 2009. ApJ 701: 635-641
Murray N, Menard B, Thompson TA. 2011. ApJ 735:66-77
Mutch SJ, Croton DJ, Poole GB. 2013. MNRAS 435: 2445-2459
Nagar NM, Falcke H, Wilson AS. 2005. Ap. J. 435:521-543
Narayan R. 2002. 'Lighthouses of the Universe' eds. M. Gilfanov, R. Sunyaev, E Churazov, pp. 405-429, Berlin,Heidelberg: Springer-Verlag
Narayan R. 2005. Astrophys.Space Sci. 300: 177-188
Narayan R, Yi I. 1994. Ap. J. 428: L13-L16
Narayan R, Yi I. 1995. Ap. J. 444: 710-735
Neilsen J, Lee JC. 2009. Nature 458:481-84

Nemmen RS, Bower RG, Babul A, Storchi-Bergmann T. 2007. MNRAS 377: 1652-1662
Netzer H, Mainieri V, Rosati, P, Trakhtenbrot, B. 2006. A&A 453: 525-533
Netzer H. 2009. MNRAS 399: 1907-1920
Netzer H. 2013. 'The Physics and Evolution of Active Galactic Nuclei'. Cambridge UK: Cambridge University Press
Nesvadba NPH, Lehnert MD, Eisenhauer F et al. 2006. ApJ 650: 661-668
Nesvadba NPH. Lehnert MD, De Breuck C, Gilbert AM, van Breugel W. 2008. A&A 491: 407-424
Norman CA, Scoville NZ. 1988.ApJ 332: 124-134
Nulsen PEJ, Jones C, Forman WR et al. 2007. In ESO Astrophys. Symp., ed. H Böhringer, GW Pratt, A Finoguenov, P Schuecker, pp. 210-15. Berlin,Heidelberg: Springer-Verlag
Nusser A, Silk J, Babul A. 2006. MNRAS 373: 739-746
O'Dea CP, Baum SA, Privon G, Noel-Storr J, Quillen AC, et al. 2008. Ap. J. 681:1035-45
O'Dea CP, Daly RA, Kharb P, Freeman KA, Baum SA. 2009. Astron. Astrophys. 494: 471-488
Osterbrock DE, Ferland G. 2005. 'Astrophysics of Gaseous Nebulae and Active Galactic Nuclei'. Mill Valley CA: University Science Books
Padovani P, Miller N, Kellermann KI et al. 2011. Ap.J. 740: 20-37
Panter B, Heavens AF, Jimenez R. 2003. MNRAS 343: 1145-1154
Panter B, Jimenez, R, Heavens AF, Charlot S. 2007. MNRAS 378: 1550-1564
Pasquali A, Kauffmann G, Heckman TM. 2005. MNRAS 361: 1121-1130
Peterson BM. 1997. 'An Introduction to Active Galactic Nuclei'. Cambridge UK: Cambridge University Press
Peterson BM. 2013. Space Sci Rev in press
Peterson JR, Bleeker JAM, Ferrigno C et al. 2001. Astron. Astrophys. 365:L104-9
Peterson JR, Kahn SM, Paerels FBS et al. 2003. Ap. J. 590:207-24
Pettini M, Pagel BEJ. 2004. MNRAS 348: L59-63
Pierce CM, Lotz JM, Laird ES et al. 2007. ApJ 660: L19-22
Pizzolato F, Soker N. 2010. MNRAS 408:961-74
Ponti G, Fender RP, Begelman MC et al. 2012. MNRAS 422:L11-15
Porciani C, Magliocchetti M, Norberg P. 2004. MNRAS 355: 1010-1030
Punsly B, Coroniti FV. 1990. Ap.J. 350: 518-535
Qiao E, Liu BF. 2009. Pub. Ast. Soc. Japan. 61: 403-410
Quataert E. 2001. ASP Conf Ser. 224: 71-85
Rafferty DA, McNamara BR, Nulsen PEJ, Wise MW. 2006. Ap. J. 652:216-31
Reviglio P, Hefland DJ. 2006. Ap.J. 650: 717-726
Rawlings S, Saunders R. 1991. Nature 349: 138-140
Reichard TA, Heckman TM, Rudnick G et al. 2009. ApJ 691: 1005-1020
Remillard RA, McClintock JE. 2006. Annu. Rev. Astron. Astrophys. 44:49-92
Rengelink RB, Tang Y, de Bruyn AG, et al. 1997. Astron. Astrophys. Supp. 124: 259-280
Richards G, Fan X, Newberg H et al. 2002. AJ 123: 2945-2975
Richards G, Lacy M, Storrie-Lombardi LJ et al. 2006. ApJS 166: 470-497
Rigby EE, Best PN, Brookes MH et al. 2011. MNRAS 416: 1900-1915
Rigby JR, Diamond-Stanic AM, Aniano G. 2009. ApJ 700: 1878-1883
Rosario DJ, Shields GS, Taylor GB, Salviander S, Smith KL. 2010a. ApJ 716: 131-143
Rosario DJ, Whittle, M, Nelson CH, Wilson AS. 2010b. ApJ 711: L94-98
Rosario DJ, Trakhtenbrot B, Lutz D et al. 2013. arXiv 1310.1922
Rosenfield P, Johnson L, Clifton G et al. 2012. ApJ 755: 131-143

Ross NP, Shen Y, Strauss MA et al. 2009. Ap.J. 697: 1634-1655
Roy AL, Norris RP, Kesteven MJ, Troup ER, Reynolds JE. 1998. MNRAS 301: 1019-1030
Russell HR, McNamara BR, Edge AC et al. 2013a. Ap.J. submitted, arXiv:1309.0014
Russell DM, Gallo E, Fender RP. 2013b. MNRAS 431: 405-414
Sabater J, Best PN, Argudo-Fernández M. 2013. MNRAS 430: 638-651
Sadler EM, Jenkins CR, Kotanyi CG. 1989. MNRAS 240:591-635
Sadler EM, McIntyre VJ, Jackson CA, Cannon RD. 1999. Pub. Astron. Soc. Aust. 16: 247-256
Sadler EM, Jackson CA, Canoon RD et al. 2002. MNRAS 329: 227-245
Sadler EM, Cannon RD, Mauch T et al. 2007. MNRAS 381: 211-227
Sadler EM, Ekers RD, Mahony E, Mauch T, Murphy T. 2013. MNRAS in press, arXiv:1304.0268
Saintonge A, Kauffmann G, Cramer C et al. 2011. MNRAS 415: 32-60
Saintonge A, Tacconi LJ, Fabello S et al. 2012. ApJ 758: 73-89
Salim S, Charlot S, Rich RM et al. 2005. ApJ 619: L39-42
Sandage A. 1965. ApJ 141: 1560-1580
Sanders DB, Soifer, BT, Elias JH, Neugebauer G, Matthews K. 1988a. ApJ 328: L35-39
Sanders DB, Soifer BT, Elias JH et al. 1988b. ApJ 325: 74-91
Santini P, Rosario DJ, Shao L et al. 2012. A&A 540: 109-128
Sargent MT, Schinnerer E, Murphy E et al. 2010. Ap.J.Supp. 186: 341-377
Sarzi M, Shields JC, Schawinski K et al. 2010. MNRAS 402: 2187-2210
Satyapal S, Vega D, Dudik RP, Abel NP, Heckman T. 2008. ApJ 677: 926-942
Satyapal S, Böker T, McAlpine W et al. 2009. ApJ 704: 439-452
Schawinski K, Thomas D, Sarzi M et al. 2007. MNRAS 382: 1415-1431
Schawinski K, Urry CM, Virani S et al. 2010. Ap.J. 711: 284-302
Schawinski K, Treister E, Urry CM et al. 2011. ApJ 727: L31-36
Schawinski K, Simmons BD, Urry CM, Treister E, Glikman E. 2012. MNRAS 425: L61-65
Scheuer P. 1974. MNRAS 166: 513-528
Schiminovich D, Wyder T, Martin DC et al. 2007. ApJS 173: 315-341
Schmidt M 1963. Nature 197: 1040
Seljak U. 2000. MNRAS 318: 203-213
Selwood J. 2014. arXiv 1310.0403 Seyfert CK. 1943. ApJ 97: 28-40
Shabala SS, Godfrey LEH. 2013. Ap.J. 769: 129-136
Shankar F, Weinberg D, Miralda-Escude, J. 2009. ApJ 690: 20-41
Shankar F, Marulli F, Mathur S et al. 2012. A&A 540: 23-31
Shankar F, Weinberg D, Miralda-Escude J. 2013. MNRAS 428: 421-446
Shao L, Kauffmann G, Cheng L, Wang, J, Heckman TM. 2013. arXiv 1304.7175
Shapley A. 2011. ARA&A 49: 525-580
Shen S et al. 2006. MNRAS 369: 1639-1653
Shen S, Kauffmann G, von der Linden A, White SDM, Best PN. 2008. MNRAS 389: 1074-1086
Shen Y, Strauss MA, Ross NP et al. 2009. Ap.J. 697: 1656-1673
Sheth RK, Mo HJ, Tormen G. 2001. MNRAS 323: 1-12
Shimasaku K, Fukugita M, Doi M et al. 2001. AJ 122: 1238-1250
Shlosman I, Begelman MC, Frank J. 1990. Nature 345: 679-686
Silverman JD, Lamareille F, Maier C et al. 2009. ApJ 696: 396-410
Silverman JD, Kampczyk P, Jahnke K et al. 2011. ApJ 743: 2-11
Silk J. 2013. arXiv 1305.5840
Simoes Lopes R, Ramiro D, Storchi-Bergmann T, de Fatima Saraiva, M, Martini P. 2007. ApJ 655: 718-734

Simmons BD, Lintott C, Schawinski K et al. 2013. MNRAS 429: 2199-2211
Simpson C, Rawlings S, Ivison RJ et al. 2012. MNRAS 421: 3060-3083
Simpson C, Westoby P, Arumugam V et al. 2013. MNRAS 433: 2647-2656
Soker N. 2006. New. Astron. 12: 38-46
Soltan A. 1982. MNRAS 200: 115-122
Spinoglio L, Malkan MA. 1989. ApJ 342: 83-99
Spoon HWW, Farrah D, Lebouteiller V et al. 2013. ApJ 775: 127-146
Springel V, Di Matteo, T, Hernquist L. 2005. MNRAS 361: 776-794
Stasinska G, Cid Fernandes R, Mateus A, Sodre L. Asari NV. 2006. MNRAS 371: 972-982
Steidel CC, Erb DK, Shapley AE et al. 2010. ApJ 717: 289-322
Steiner JF, McClintock JE, Narayan R. 2013. Ap.J. 762: 104-113
Stern D, Eisenhardt P, Gorjian V et al. 2005. ApJ 631: 163-168
Stern D, Assef RJ, Benford DJ et al. 2012. ApJ 753: 30-47
Stern J, Laor A. 2012a. MNRAS 426: 2703-2718
Stern J, Laor A. 2012b. MNRAS 423: 600-631
Strauss MA, Weinberg DH, Lupton RH et al. 2002. AJ 124: 1810-1824
Sturm E, González-AlfonsonE, Veilleux S et al. 2011. ApJ 733: L16-20
Tamura T, Bleeker JAM, Peterson JR, et al. 2001. Astron. Astrophys. 365:L87-92
Tasse C, Best PN, Röttgering HJA, Le Borgne D. 2008. Astron. Astrophys. 490: 893-904
Terlevich R, Melnick J. 1985. MNRAS 213: 841-856
Terlevich R, Tenorio-Tagle G, Franco, J, Melnick J. 1992. MNRAS 255: 713-728
Toffolatti L, Franceschini A, Danese L, de Zotti G. 1987. Astron. Astrophys. 184: 7-15
Treister E, Schawinski K, Volonteri M, Natarajan P. 2013. arXiv 1310.2249
Tremaine S, Gebhardt K, Bender R et al. 2002. ApJ 574: 740-753
Trump JR, Impey CD, Kelly BC et al. 2009. Ap.J. 700: 49-55
Ueda Y, Hiroi K, Isobe N et al. 2011. PASJ 63: 937-945
Veilleux S, Osterbrock DE. 1987. ApJS 63: 295-310
Veilleux S, Cecil G, Bland-Hawthorn J. 2005. ARA&A 43: 769-826
Veilleux S, Rupke DSN, Kim D-C et al. 2009. ApJS 182: 628-666
Veilleux S, Meléndez M, Sturm E et al. 2013. ApJ 776: 27-47
Vitale M, Zuther J, García-Marín M, Eckart A, Bremer M et al. 2012. Astron. Astrophys. 546: A17-A33
Voges W, Aschenbach B, Boller T et al. 1999. A&A 349: 389-405
von der Linden A, Best PN, Kauffmann G, White SDM. 2007. MNRAS 379: 867-893
Whitaker K, van Dokkum PG, Brammer G, Franx M. 2012. ApJ 754: L29-34
Willott CJ, Rawlings S, Blundell KM, Lacy M. 1999. MNRAS 309: 1017-1033
Wilson AS, Colbert EJM. 1995. Ap.J. 438: 62-71
Wilson AS, Heckman TM. 1985. Astrophysics of active galaxies and quasi-stellar objects: 39-109
Wild V, Kauffmann G, Heckman T et al. 2007. MNRAS 381: 543-572
Wild V, Heckman T, Charlot C. 2010. MNRAS 405: 933-947
Winter L, Lewis KT, Koss M et al. 2010. ApJ 710: 503-539
Woo J-H, Schulze A, Park D et al. 2013. ApJ 772: 49-57
Worthey G, Ottaviani DL. 1997. ApJS 111: 377-386
Wright EL, Eisenhardt PPM, Mainser AK et al. 2010. AJ 140: 1868-1881
Wuyts S, Förster Schreiber NM, Lutz D et al. 2011a. ApJ 738: 106-123
Wuyts S, Förster Schrieber NM, van der Wel A et al. 2011b. ApJ 742: 96-15
Xu C, Livio M, Baum S. 1999. AJ 118: 1169-1176

Yan R, Newman JA, Faber SM et al. 2006. ApJ 648: 281-298
Yan R, Blanton MR. 2012. Ap.J. 747: 61-85
Yee HKC, Green RF. 1984. Ap.J. 280: 79-90
Yip CW, Connolly AJ, Szalay AS et al. 2004. AJ 128: 585-609
Yu Q, Tremaine S. 2002. MNRAS 335: 965-976
Yuan F, Narayan R. 2004. Ap.J. 612: 724-728
Zakamska N, Strauss MA, Heckman T, Ivezic Z, Krolik J. 2004. AJ 128: 1002-1016
Zinn PC, Middelberg E, Norris RP, Dettmar RJ. 2013. ApJ 774: 66-75